FIRDN AGE

THE NATIONAL METALWORKING WEEKLY

ERY

tain

nche ture. with

rtain

r of

ning ories nand atics alers ees" good ituawere a tip sale. ficult ains alers lease used actly

alers ek to ules. two

ning spite busibal-

rices area

parwere are used ance, for yo is

ears rigi-

nore. ma-

what en or dicaeven

AGE

December 14, 1950



E. J. LAVINO AND COMPANY

1528 WALNUT STREET · PHILADELPHIA 2, PA.
Pittsburgh Office 22, 1819 Oliver Building



WILLIAM LONGING

CINTERCITY

As the white outline indicates, a standard unit of much greater frame size would be required to do the work of Speedaire. In fact, Speedaire is 37.2% smaller in cubic content, 12% lighter in weight and 14.5% lower in initial cast.

Photo by courtesy of R. C. Mahon Co., Detroit

pend

reco


They in sli

Va you other

In qual assu fines

up more space than the mill itself and interfered with moving materials into and out of the machine. The new drive, the small, but Powerful Speedaire in the lower left arive, the small, but powerful speedaire in the lower left foreground, occupies less than 3% of the old drive space. Speedaire is Cleveland's fan-cooled worm-gear speed reducer. Because it is fan-cooled, it does more work...will reducer. Decause it is ian-cooled, it does more work...win deliver up to double the horsepower of standard worm units of equal frame size, at usual motor speeds. It can be inor equal frame size, at usual motor specus, it can be me stalled economically on many applications where other statical economically on many applications where other types have been used heretofore—giving you the advantage types nave neen used neretoiore—giving you me advantage of a compact right-angle drive. Speedaire gives the same long, trouble-free service characteristic of all Clevelands. For full description, send for Catalog 300. The Cleveland Worm & Gear Co., 3252 East 80th St., Cleveland 4, Ohio. Affiliate: The Farval Corporation, Centralized Systems of Junate: The Parval Corporation, Centralized Systems of Lubrication. In Canada: Peacock Brothers, Limited.





You can trust them!

BETHLEHEM WIRE ROPE SLINGS


When you purchase Bethlehem slings, you can depend upon them to carry the loads for which they're recommended.

In making these slings, our Number 1 objective is quality . . . the sort of quality that brings complete assurance to the user. Bethlehem slings contain our finest rope, the Purple Strand improved plow grade. They are made by expert workmen who specialize in slings and nothing else.

Variety? Yes. Name your kind, we'll make it for you . . . single-rope, grommet, braided, bridle, and other types. With Bethlehem, every job is a "special" job, tailored to the needs of the individual user.

BETHLEHEM STEEL

Bethlehem slings are available with all types of end fittings, such as sockets, thimbles, hooks, rings, links, etc. Whatever combination you want, we can furnish. Promptly, too.



BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast
Steel Corporation. Expart Distributor: Bethlehem Steel Expart Corporation

BUSINESS STAFF

GEORGE T. HOOK Publisher

B. H. Hayes Production Manager

O. L. Johnson Director of Research

Charles T. Post

Manager Circulation and Promotion

James A. Crites
Assistant Promotion Manager

Editorial, Advertising and Circulation
Offices
100 E. 42nd St., New York 17, N. Y., U.S.A.

Regional Business Managers

B. L. Herman Peirce Lewis Philadelphia 37 Chilton Bida. Detroit 2 103 Pallister Ave. C. H. Ober Robert F. Blair Cleveland 14 1016 National City Bank Bldg. New York 17 180 E. 42nd St. Stanley J. Smith J. M. Spackman Chicago 3 1134 Otis Bldg. Pittsburgh 22 814 Park Bldg. Paul Bachman R. Raymond Kay West Hertford 7 62 La Salle Rd. Los Angeles 28 2420 Cheremoya Ave.

Harry Becker

European Representative 111 Thorley Lane Timperley, Cheshire, England

Circulation Representatives THOMAS SCOTT JAMES RICHARDSON

One of the Publications
Owned and Published by
CHILTON COMPANY
(Incorporated)
Chestnut and 56th Sts.
Philadelphia 39, Pa., U. S. A.

OFFICERS AND DIRECTORS

JOS. S. HILDRETH, President

EVERIT B. TERHUNE
P. M. FAHRENDORF
Vice-President
V

Member, Audit Bureau of Circulation



Cable Address "Ironage" N. Y.
Copyright, 1950, by Chilton Company (Inc.)

THE IRON AGE

CONTENTS

Editori	al
	We've Got Some Thinking To Do
News	Interpretations
	Newsfront 11 The Iron Age Summary 15 Machine Tool Highspots 33 On the Assembly Line 88 West Coast Progress Report 93 The Federal View 95
Regule	ar Features
	Fatigue Cracks 20 Dear Editor 24 Dates To Remember 28 Free Publications 34 New Production Ideas 35 Iron Age Introduces 84 Construction Steel News 129 The Clearing House 174
Techn	ical Articles
	New Process For Phosphoric Acid Pickling 97 Getting The Most Out of Your Drill Presses, Part I 100 Lathe Tools Used in Milling Cutter 103 New Lathe Has T-Shaped Bed 104 Anneal Ductile Iron For Better Machinability 105 New Blowpipe Drills Dynamite Holes Faster 108 Industrial Glove Salvaging Cuts Replacements 109 To Reduce Polishing Costs, Polish Flat 111 Patenting Furnace Features Lightweight Construction 112 Pointing, Shearing Part of Continuous Cycle 114
Spot I	News of Industry
	Material Restrictions Hit Detroit117Industrial Shorts118Farm Equipment Makers See Steel Pinch119Major \$228 Million Expansion Set by J & L122Steel's Price Rises Cause Little Concern124
Marke	ets & Prices
	Market Briefs and Bulletins147Nonferrous Metals Outlook148Nonferrous Prices149Iron and Steel Scrap Market150Iron and Steel Scrap Prices152Comparison of Prices154Steel Prices156Stainless Steel, Pipe and Tubing Prices158Warehouse Steel and Pig Iron Prices159Miscellaneous Steel Prices160Ferroalloy Prices164
Index	to Advertisers

December 14, 1950 . . . Vol. 166, No. 24

Special Article



7

15

33

93

95

28

35

84

129

174

100

103

104

105 108 109

111

112

114

117

119

122

124

148

149

150

152

154 156 158

159

164

185

N AGE

Cost of phosphoric acid pickling can be cut 66 pct by a newprocess which reclaims the acid for re-use. In many cases, cost is below that of pickling with sulfuric acid.—p. 97.

Issue Highlights



The drill press is such a simple, common tool that it doesn't always get the attention more complex tools do. Many attachments and modifications, some of which you may have overlooked, can increase the versatility of your drill presses.—p. 100.



Adequate machinability and physical properties can be obtained in ductile iron without complete pearlite decomposition. Increased silicon content speeds carbide solution. Small amounts of carbide can be tolerated if the matrix is basically ferrite.—p. 105.



Material restrictions are already beginning to strangle auto production. Although steel is the toughest item, nonferrous metals are causing plenty of worry, too. Independent producers are hardest hit.—p. 117.



Farm equipment makers who formerly favored free market distribution of steel are now beginning to favor the protection of a formal allocation system. Bigger food demands and a shrinking labor force make more mechanization necessary.—p. 119.



Jones & Laughlin Steel Corp will spend \$228 million for expansion in the next 2 years. Capacity will be increased by 1.5 million ingot tons. To help with financing, J & L is borrowing from General Motors and from banks.—p. 122.



The steel industry's modest price boosts are causing little fuss in Washington. The Economic Stabilization Agency doesn't believe it is necessary to take action (relating to steel increases) at this time.—p. 124.

Coming Next Week



Improved physical properties and reduced production costs through use of plain carbon steel instead of alloy grades were achieved by induction hardening axle shafts. Production was increased and some operations were eliminated by this method.

EDITORIAL STAFF

TOM C. CAMPBELL Editor

G. F. Sullivan Managing Editor

W. V. Packard D | Brown News-Markets Editor Feature Editor F. I. Winters G. F. Elwers Associate Editor Machinery Editor W. Czygan H. W. Van Camp Associate Editor Associate Editor R. L. Hatschek Ted Metaxas Assistant Editor Assistant Editor J. Kolb W. B. Olson Assistant Editor Assistant Editor

Regional Editors

E. C. Beaudet	John B. Delaney
Chicago 3	Pittsburgh 22
1134 Otis Bldg.	814 Park Bidg.
W. G. Patton	W. A. Lloyd
Detroit 2	Cleveland 14
103 Pallister Ave.	629 Euclid Ave.

Osgood Murdock R. T. Reinhardt San Francisco 3 1365 Market St.

Eugene J. Hardy

Karl Rannells

George H. Baker Washington 4 National Press Bldg.


Correspondents

Fred L. Allen	N. Levenson	
Birmingham	Boston	
James Douglas	Roy Edmonds	
Seattle	St. Louis	
F. H. Harley	F. Sanderson	

Fred Edmunds

Chilton Editorial Board
PAUL WOOTON
Washington Representative

Indexed in the Industrial Arts Index and the Engineering Index. Published every Thursday by the CHILTON CO. (INC.), Chestnut and 56th Sts., Philadelphia 39, Pa. Entered as second class matter Nov. 8, 1932, at the Post Office at Philadelphia under act of March 3, 1879. \$8 yearly in United States, its territories and Canada; other Western Hemisphere Countries \$15; other Foreign Countries \$25 per year. Single Copies 35¢. Annual Review Number, \$2.00.



CECO-DROP

• The Boardless Gravity Drop Hammer

No Boards • No Front Rod • No Back Rod Costs less to operate . . . Forges more minutes per hour . . . Is safer and easier to operate . . . This hammer is setting new records in cutting forging costs and in increasing production.

CHAMBERSBURG ENGINEERING CO., CHAMBERSBURG, PA.

Editorial

NDUSTRY VIEWPOINTS

We've Got Some Thinking To Do

EVEN now there are people who don't know what a fix the free world is in. They can read. They hear the news but for some reason they can't grasp the seriousness of our plight.

Of course we don't want war. But we don't want the kind of slave living that comes with Soviet Communism. There are some things that are worse than death to a free people.

We are told that our standard of living may suffer because it costs money to become strong. So strong we don't have to weasel. So strong we don't have to appease. So strong the Russian rulers will know we mean business and that we are for freedom in action as well as on paper.

Sure our standard of living will suffer. Russia has two allies. One is deflation in the free countries and the other is inflation. Either one running amuck would mean success for communism. We need a balance. That will be the hardest nut of all to crack.

To get this balance we need the best brains and experience in government. We must have clear-cut thinking without jealousies, stupidity or red tape. We must have this within the framework of democracy.

If we prize freedom a drop in our standard of living should not be too high a price to pay for it. If we have to eat crackling instead of fancy bacon so what?

If last year's car must do a while can we do it? If our electric refrigerator still keeps the milk cold need we fret?

If we have to drink beer instead of 12-year-old stuff will we suffer too much? If the little woman can't have the latest furs will that cause a divorce? If the old man can't have a new sport coat will it spoil his score?

If we have three squares a day will it starve us if we can't work in the fourth at night. If we can't have fancy box top cereal will corn meal mush turn our stomachs?

If we give up a few things, save and pay taxes for freedom we will live another day to catch up on all the things we missed. If we don't win the battle for freedom then we won't need our standard of living. A corpse or a living automaton won't get much pleasure out of an ice box, gimcrack or gadget.

Tom C. Campleso

Editor

Alloy Steels

A REPORT FROM
REPUBLIC STEEL'S

METALLURGICAL FILES





3-DIMENSION
Metallurgical Service

... combines the extensive experience and coordinated abilities of Republic's Field, Mill and Laboratory Metallurgists with the knowledge and skills of your own engineers. It has helped guide users of Alloy Steels in countless industries to the correct steel and its most efficient usage ... IT CAN DO THE SAME FOR YOU.

Other Republic Products include Carbon and Stainless Steels — Sheets, Strip, Plates, Pipe, Bars, Wire,

Dec

NEWSFRONT =

NEWS, METHODS AND PRODUCT FORECAST

► If President Truman should declare that a <u>state of emergency</u> exists, things will move forward <u>slowly</u>. The main object will be to give the President <u>psychological help</u> on various powers, most of which he already has by law.

The emergency edict will not do much to eliminate the red tape or lead time on setting up specific defense projects. But it will appear to add urgency for price, wage and material restrictions.

- ► It looks as though the steel industry in the U.S. will have to furnish about 8000 tons of steel a month for the <u>Canadian freight</u> <u>car building program</u>. On the same track—there is a <u>70,000 ton</u> <u>U.S. locomotive program</u> lurking in the background.
- A new steel continuous casting company is being formed; the plant may be in operation by late 1951. It is being designed to cast slabs at a rate of one ton per minute. The slabs will go into sheet and strip products.
- Some kind of wage control is expected after the first of the year but it may not be a definite ceiling freeze. Cyrus Ching hasn't got the men or the regulations to go into full control that soon. A formula may permit merit raises and revision of inequities—including room for the coal miners to get under the fence.
- Reductions in diameter of steel in drawing operations of as much as 66 pct in regular production and 78 pct in experiments have been obtained in a single press stroke. The process is the reverse of deep drawing: A ram forms a shallow cup, then literally turns it inside out as the draw continues.

inside out as the draw continues.

The process itself is not new but these figures are remarkable because: (1) The original diameter in the above case was $14\frac{1}{2}$ in.; and (2) the material was a high-strength low-alloy steel.

- Development of a stainless steel that will not use critical materials is a project that has just been given to an important research institute.
- Steel people hope it isn't so, but it looks as though the tight plate situation will force a general changeover on large continuous hot strip mills so they can roll <u>lighter gages of plate</u> as they did in World War II. For one thing, many qualified observers believe that <u>shipbuilding must be expanded</u> tremendously, though that project would not need additional steel for many months.
- A Midwest firm has developed king-size ammeters, wattmeters and voltmeters. Put at one end of a shop or power station they are big enough to be read at the other. Most such instruments in use today multiply readings from a conventional size meter onto a large dial, so any inaccuracies are multiplied. In the new instruments the electrical meter elements are of a size to match the meter dial.
- The big military requirements that should awaken the country to the emergency if nothing else does are <u>several months away</u>. There will be a lot of piecemeal ordering but the major slice of Mr. Truman's \$18 billion increase can't begin to be felt until about May 1.
- ► More limitation orders are expected. The steel industry is now curtailing <u>nickel bearing steel;</u> Washington may make it official. Cadmium, chrome and tin orders are in the talking stage.

Wire,

AGE



Dependable "ON-OFF" Controllers for Industry

THE kind of control instrument which industry calls on-off or 2-position is not only the oldest form of automatic regulator, but is one which many manufacturers still use, instead of more advanced types, for simple requirements. Usually, the instrument merely closes the valve when temperature reaches the control point, and opens valve again when temperature falls below point. The question of whether such on-off action is best for the given case can of course be settled by using the instrument with the best, most useful features. Here are some which L&N On-Off Controllers offer:

1. Instruments may be Recording Controllers with either strip-chart or round-chart, or Controllers with no charts at all.

2. Instruments can operate at high or moderate speed; can be located regardless of machine vibration, building tremors or distance from process.

3. Controls are outstandingly dependable because they "balance" temperature against a standard. Intermediate bearings and springs cannot increase, decrease or otherwise influence accuracy or sensitivity.

4. Low maintenance assured by machine-like design and construction.

More than 1000 standard ranges. Specials are available, but seldom needed.

Tell us your problem and we will send further information. Write either to our nearest office or to 4956 Stenton Avenue, Philadelphia 44, Pa.



MICROMAX MODEL C ON-OFF CONTROLLER

ELECTROMAX ON-OFF CONTROLLER

LEEDS & NORTHRUP CO.

Jrl. Ad ND4-33(3)

THESE instruments are fully automatic; need no standardizing; are ideal even for hard-toget-at or difficult locations.

THE IRON AGE

Acute Labor Shortage Feared

Price-Wage Controls Coming

The Iron Age SUMMARY

New Highs -Scrap, Pig Iron IRON AND STEEL INDUSTRY TRENDS

HIS week many manufacturers find themselves suspended in a vacuum between their regular peacetime production and military orders. Their regular production is being strangled by material restrictions and defense orders are not coming fast enough to take up the slack.

The result is that a few firms have already found it necessary to lay off workers. Others may have to follow suit if they can't land some defense business. What these firms fear most is that they will lose experienced workers at a time when a critical labor shortage is just around the corner.

The pinch on skilled labor is already tight. In trying to gear up production the aircraft, freight car building and machine tool industries have already scraped the bottom of the barrel looking for welders, machinists, tool and die makers, etc.

New Steel Programs Coming

LER

.

fully

ardiz-

rd-to-

AGE

S.

Several new steel allocation programs will soon be announced. A locomotive building program, now in the final planning stage, will take about 70,000 tons of steel per month during the second quarter. Canadian freight car builders are expected to get 8000 tons monthly. The petroleum industry and agricultural equipment makers will also get a share.

The petroleum people alone estimate next year's steel needs at 11.9 million tons. This program will probably be pared down to about 8 million tons before it is finally approved. But each new program that is added brings a controlled materials plan that much nearer. That it will come eventually is now a foregone conclusion. It will probably be put into effect sometime during the second quarter. It will take that long to collect the personnel needed to run it.

Price-wage controls are also only a matter of time. One thing holding them back now is that there is no staff to administer them. When they come they will be on a selective basis, and they will probably hit scrap, nonferrous metals and steel in that order. If prices of some items start to get out of hand there is a chance that price controls on them might be placed in effect at

Some Necessary Loopholes

Wage controls will not be airtight. They will allow for a cleanup of fifth round demands. And they will permit elimination of inequities and allow some merit increases.

A high level meeting in Washington this week might result in a declaration of national emergency by the President. The defense production act of 1950 already gives him most of the powers which would result from such a declaration. Such a move would give the President psychological help on powers he already has.

This week the cry for steel is louder in all Producers are still 1 to 2 months behind on deliveries, and DO orders are becoming more extended. Before the limits were raised on DO orders some producers had booked DO's on some items as far ahead as July. They believe that the higher limits will be filled quickly.


Serap Composite at Record High

Prices of steelmaking scrap are higher in all areas. Increases at Pittsburgh, Philadelphia and Chicago raised THE IRON AGE steel scrap composite price by \$4.33 a gross ton to \$45.08 per

Recent increases in pig iron prices have boosted the composite price \$3 a ton to \$52.69 a gross ton. Both the pig iron and scrap composite prices are now at an all-time high.

Steelmaking operations this week are scheduled at 101.5 pct of rated capacity, one point above the previous week.

(Nonferrous summary, p. 148)



TUBE MILLS

Electric resistance-weld and other types, combine low first cost, operating and maintenance cost with compactness, simplicity and high production of pipe and tubing from ½" up to 30" diameter. More Yoder mills are sold and in use than of all other makes of resistance-weld mills combined. 64-Page Book on Tube Making on request.

COLD ROLL FORMING MACHINES

For conversion of sheets and strip into plain and designed structurals, mouldings, panels, box and tubular shapes. Production from 25,000 to 40,000 feet per 8-hour day with only one operator. Highest accuracy in forming simple and intricate profiles. Send for 88-Page Book of Information on Cold Roll Forming.


ROTARY GANG SLITTERS

For multiple slitting of coiled strip and sheets. Highly standardized series of uncoilers, slitters, scrap choppers, recoilers, and coil cars. If you sell or use over 1000 tons of sheets or strip per year, investigate the economies of doing your own slitting. The economies of doing your own slitting, as well as equipment required, explained in 76-Page Book, sent on request.

OTHER MACHINES FOR OPERATIONS ON SHEETS AND STRIP

Coil Boxes, Strip and Plate Levelers, Brake Shoe Benders, Tub Beaders, Edge Conditioners and Trimmers, Scrap Flatteners, Power Hammers and other Special Machinery.

THE YODER COMPANY . 5510 Walworth Ave., Cleveland 2, Ohio



TUBE MILLS






Mercury JEEP

MODEL 230

Completely new and the most versatile fork truck of 2000 lb. rating. 130" extreme lift to permit full utilization of storage area... short 60" turning radius for greater maneuvering in narrow aisles and congested areas... ample "free lift" and many other improvements, that mean maximum operating efficiency at lower cost. Completely described in Bulletin 295. Request your free copy.

MERCURY MANUFACTURING COMPANY 4144 S. Halsted St. • Chicago 9, Illinois



Fatigue Cracks

By CHARLES T. POST

Hey, Charlie

Every once in a while we get an inkling of what the Social Security Administration must go through with its rows of files on William Smiths and John Joneses. For instance, a letter came in the other day from Lee Graybill, production superintendent of King-Seeley Corp. which went like this:

"During a recent conversation with Joe McGrath of Detroit, we were talking about the old days at Studebaker and Department No. 80. We were wondering about some of the old gang... Joe remarked that you were connected with THE IRON AGE... Well, Charlie, I am extending a cordial invitation to drop in for a visit if you ever are in this part of the country, and let's hear from you."

It was a sad duty to break the news to Lee Graybill that he had the wrong Charlie Post, because both Lee and his Charlie sounded like nice fellows. We explained how big the Charlie Post tribe seems to be. For years a Charlie Post was one of the top clowns with Ringling Brothers, and every time his picture appeared in the paper, friends sent it to us from all parts of the country. Almost everybody claims to have a friend or cousin named Charlie Post, and one store clerk slips us a discount on the strength of it. When we lived in San Francisco, there was another Charlie Post on the same street, but way at the other end, about 5 miles away. We were always trotting back and forth with each other's mail. The most eminent member of the tribe. perhaps, was Charles W. Post, who invented Post Toasties. He later fell to brooding, we understand, and came to a tragic end. As a child, we always felt that he, too, had gotten sick of Post Toasties.

We never had it so bad though, as our mother, Mary Post. In the same small California town where we spent our early youth there was another Mary Post who periodically was thrown in the jug for keeping a disorderly house. Mother never could quite explain to us moppets why this other Mary Post was in such bad odor with the law. We always warned mother that unless she kept the rugs swept, the beds made, and the dishes washed,

the cops would come around and say that our house wasn't orderly, either, and then there would be two Mary Posts in jail.

Puzzlers

Both C. E. Norton and John E. Toth have hastened to explain that the late great Charles P. Steinmetz's feat of mentally calculating the volume of material removed by drilling a 2-in. bar perpendicularly with a 2-in. drill does not rank with his greatest achievements. Says Mr. Toth, "The portion removed from the bar is divided equally into 8 parts, each of which resemble a special ungula of a right circular cylinder, the volume of which is $V = \frac{3}{2} r^2 H$. Since r = 1 and H = 1 the formula reduces to V = % for one part and % \times 8 or 5% cu in. for the total volume removed." As Mr. Norton puts it, it's a matter of recognizing at a glance that the "volume of the slug bears the same relation to the volume of an inscribed sphere that the area of a square bears to the area of an inscribed circle, namely

beyond the multiplication of $\frac{\pi}{6} \times \frac{4}{\pi} = \%$."

- . . . no mathematics is required

On the 2-in. cube with three 1-in. diam holes, Mr. Norton suggests: "Start with 6 cylinders, 1-in diam and 1-in. long. On one end of each, mill 4 flat faces at 45° with the center line, forming a square pyramidal point. Save the upper portion and scrap the lower portion." From there, its easy to work out the answer of approximately 3.2982 cu in. John P. Catlin of Remington Arms came to the same conclusion, but Mr. Toth declares it was 3.295 cu in. Mr. Toth cracked the oil drum problem, as did Walter Schroeder of Cincinnati Milling Machine Co. Several others cracked the formula, but slipped up later.

Last week's egg merchant made an average profit of 5/11¢ per dozen.



December 14, 1950

and rly, two

E. hat eining by arly ank ank reded ich

reand otal ton ing

the the hat the ely

in.
ts:
am
ch,
the
are
per
ork
ely
of
me
it
ced
ter
ng

GE

New. di acro **BOX FINGER BRAKE**

Four models 6" 12" 18" 24" Capacity-16 Gauge Steel



TOOLS IN ONE **BOX and PAN BRAKE** 2 STANDARD BRAKE 3 BAR FOLDER

One box or 10,000-can be economically produced with the versatile new Di-Acro Box Finger

Serves perfectly for all standard brake operations - an Acute Angle Bar converts the brake to a bar folder for locks, seams, hems and sharp angles.

The unique Di-Acro Open End Finger forms square or triangular tubes and other similar parts. The Box Finger Bar can be easily mounted on all standard Di-Acro Brakes.



Letters from Readers

Facts Issue Coming Soon!

Sir:

We have just been appointed general sales agents for the output of Mag-Iron Mining & Milling, Ltd. (subscribers to your publication), who own a large deposit of high grade magnetite in this province and produce a concentrate, in various size particles, which is of exceptional good quality, free from phosphorous and with only a trace of sulfur; when reduced, it makes an acceptable material for iron powder metallurgical processes in all its phases.

Can you give us any up to the moment statistics concerning the market for iron powder, its users, prices, market requirements, etc., and the same information regarding sponge iron, the resultant product after the concentrate has been reduced to a metallic state, id est, after the oxygen has been driven off.

R. E. HOLLIDAY Technical Advisor

Specialized Products & Sales Toronto, P/Ont., Canada

Our annual Metal Industry Facts Issue of Jan. 5, 1950, presented various data on iron powders, their price and use. Similar material, brought up to date, will be included in the Metal Industry Facts Issue of Jan. 4, 1951. Current issues of THE IRON AGE report prices. So far as we know, similar data on the consumption and use of sponge iron is not available in statistical form, its use being limited and specialized. The Metal Powder Assn., 420 Lexington Ave., New York 17, is a group of metal powder producers in the U. S.—Ed.

For Statistical Info . . .

For our economic history courses, we are preparing charts of production, consumption, export and imports of various commodities. Last year we prepared these charts showing the above data in the United States, the information for which was secured from the Statistical Abstract of the United States.

This year we are preparing similar charts which will show the data for Europe. We are primarily interested in England, France, and Germany. We are trying to secure, not only current data, but data in the historical perspective for as far back as possible (preferably 1850 or before). We would like to know if you would

have any information, or would know where we could possibly obtain such information on iron and steel.

C. E. MAYNARD Graduate Assistant

Bowling Green State University Bowling Green, Ohio

As central sources of statistical information on the iron and steel industries, the Industry Trade Assns. are probably the most satisfactory, and will save dealing with a number of scattered government agencies. For current production figures, and for recent years, we suggest consulting the annual statistical issues of THE IRON AGE.—Ed.

Rotarians Get Editorials

Sir:

The writer is a weekly reader of THE IRON AGE and very particularly of your weekly editorials. I am also proud to be a member of Rotary International and take a great interest in our local club.

There have been many times that I have felt the urge to use the information and very sound democratic principles you have brought out in your editorials and to pass these along in a mimeographed letter to include in our weekly Rotogram. I feel sure you want as many outstanding American businessmen to talk about and enlarge on your ideals as can be reached. With this in mind I am writing you to ask if this privilege of using your viewpoints with the credit given to THE IRON AGE may be granted. You can be sure it will be used to very good advantage.

F. J. WOOD President

app

du

sue

du

Th

mil

sul

rig

equ

has

use

tor

ord

for

der

sen

hov

equ

mil

of !

tor

De

De

mei

the

tion

Was

Bos

of

De

Peerless Steel Co. Detroit

Increased Capacity Costs

I was very much interested in a recent article appearing in the Survey of Current Business which pointed up plans of the steel industry to make a substantial increase in steel-producing facilities between now and the end of 1952. I believe the figures quoted represented an increase from 100.6 to 110 million tons of ingots per year.

Can you give me any idea of the capital expenditures involved in this expansion program for basic producers only, or give me a rough approximation of the amount of capital required to construct facilities capable of turning out some unit of primary steel, say capital required per ton or per thousand tons of output.

L. F. CHURCH Mgr., Market Research

Emery Industries, Inc. Cincinnati

Steel industry authorities have estimated the cost of building fully integrated steel capacity involved in the new expansion program at from \$250 to \$300 per ton of ingot capacity. This figure includes finishing at well as raw material and blast furnace for cilities. Naturally, the figure would be lower if you took into consideration only the openhearths and electric furnaces involved. However, this method is the one that is used in roughly figuring capital investment.—Ed.

MACHINE TOOL



Sales
Inquiries
and Production



mow

such

rma

, the

most

or re-

nnual Ed.

r of

larly

also

y In-

erest

nfor-

eratic

at in

these

to in-

I feel

nding

an be

I am

ge of

credit

ill be

OOD

in a

urvey

ed up

make

roduc-

ne end

quoted

00.6 to

of the

n this

pro-

ch ap-

capital

apable

rimary

ton or

ROH esearch

timated

d steel

of ingot hing as

se lower

d. How-

used in —Ed.

AGE

ar.

By W. A. LLOYD

Equipment Order Ratings—An application form for rating production equipment orders was issued this week by National Production Authority in Washington. The form, NPAF-2, is for use by military prime contractors and subcontractors in applying for the right to assign DO-98 ratings to specific orders for production equipment.

When an application on NPAF-2 has been approved, DO-98 may be used by military prime contractors and subcontractors in rating orders for production equipment for their own account. Such orders cannot be rated in the absence of specific authorization, however. Orders for production equipment placed directly by the military or by agents for the Dept. of Defense, or by military contractors for the account of the Defense Dept. will be assigned regular Dept. of Defense rating symbols.

Definition of Production Equipment—Instructions accompanying the form include the same definition of production equipment that was employed by the Munitions Board in its explanation of the use of certain DO rating symbols. No distinction is made between capital equipment, and maintenance, repair or operating equipment. Orders for both are probably ratable if specifically approved on the application form NPAF-2.

Criteria for Approval—The military may approve applications for the right to rate orders for production equipment if the contractor is employing suitable existing equipment, "to the fullest practical use on rated orders" and if the contractor is unable to obtain satisfactory delivery dates for new or used equipment on an unrated basis.

The Big Question—Among the questions asked on form NPAF-2 are history of attempts to obtain equipment on an unrated basis and a certificate to the effect that suitable equipment is being used to the "fullest practical extent on rated orders." "Fullest practical use" is not defined.

It is understood that this question is not intended to require that priority assistance be given only to firms doing 100 pct defense business. It is intended to require that contractors requesting priority assistance make a good faith determination that there are no reasonable alternatives to obtaining new equipment.

Copies of NPAF-2 will be available at field offices of the Dept. of Commerce and at local military procurement offices in the near future.

Boom of Orders—Around the country, a flood of new orders, foreign and domestic, rated and unrated, was pouring in the industry this week. A big break in the dike was the French machine tool program which was finally given au-

thorization. Dealers are placing the business for delivery during the last quarter of 1951. One company reported getting an order for the first 40 of 180 machines.

Placement of French business brings into sharp focus the ultimate size of the combined foreign programs, end of which is apparently not in sight. One guess made this week by a qualified expert put the total at \$300 million covering programs present and pending over the next 3 years.

Shortages Slow Output—While the industry is striving desperately to step up production, limited manpower and shortages of materials are holding shipments to less than \$30 million a month. Deliveries are greatly extended and, as a result, a certain number of companies in the industry need some working capital.

Some have been asking for a 25 pct down payment on the foreign orders, but have been turned down because ECA does not permit advance payment. However, such payments are currently under discussion.

It has been rumored that activation of the tentative emergency production schedules (pool orders or phantom orders) is being considered. If the pool orders should be released, accompanied by possibly a one-third down payment, the working capital problem would be solved.

Report on Portugal—In Cleveland, National Machine Tool Builders Assn. released a report on the machine tool industry of Portugal, revealing that production, which had been negligible, increased during the war, reaching a peak of 148 mechanical lathes, 37 shapers and 25 drilling machines a year. After the war, one of the principal producers of lathes discontinued manufacturing operations in 1946, and in 1949 production fell to 84 lathes, 27 shapers and 11 drilling machines.

In 1950, another company withdrew from machine tool production to concentrate on textile machinery and estimated production was reduced to 71 lathes, 15 shapers and 1 drilling machine.

December 14, 1950



PUBLICATIONS

Annealing Slide Chart

Annealing data for the principal analyses of alloy steels is contained in a convenient slide chart. Data for producing spheroidal structures in 40 alloy types, by both conventional and isothermal annealing processes, is on one side. The reverse side carries data for producing lamellar structures, also broken down by conventional and isothermal processes. This three-color chart is available upon request. Republic Steel Corp.

For free copy insert No. 1 on postcard.

Hydraulic Shear

How hydraulic operation of the Hydra-Shear packs power and control for true production shearing is explained on a new data sheet. The unit maintans high accuracy by holding minimum knife clearance on all gages and reducing curl and burring, as shown in the bulletin. Operation of the shear is described and specifications for three models are listed. Johnson Machine & Press Corp.

For free copy insert No. 2 on postcard.

Protects Metals

A new 4-p. bulletin describes and illustrates several applications of a process for protecting metals against heat oxidation, which increases life of these parts from 200 to 800 pct. One example cites untreated steel retort bottles used in magnesium production having a normal life of approximately 15 heats. When given this special metallizing treatment, these retorts reached 60 heats or more before retouching became necessary. This user has also reported increased life of one-ton foundry crucibles, which are subjected to New publications that describe money saving equipment and services are available free and without obligation. Copies can be obtained by filling in the attached card and mailing it.

temperatures varying from 1700° to 1900°, from approximately 500 hr to as high as 2000 hr. Metallizing Engineering Co.

For free copy insert No. 3 on postcard.

Overhead Crane

Trambeam, a light crane and monorail system especially designed for low-cost handling of loads from 250 to 20,000 lb, is fully described in a new 20-p. catalog. The booklet is not intended to show technical details but rather to convey a summary of the reasons where and how the equipment may be economically used. Whiting Corp.

For free copy insert No. 4 on postcard.

Swing Check Valve

Complete instructions for use of G-A cushioned swing check valves are presented in a new 4-p. bulletin. Installation, operation and adjustment are dealt with in the folder, which also lists specifications and general materials used in the valve. Engineering and cross-sectional drawings are accompanied by a dimension table, and all component parts of the valve are identified. Golden-Anderson Valve Specialty Co.

For free copy insert No. 5 on postcard.

For Inert Gas

The 2 new models of the Kemp Inert Gas generator, rated at 1000 and 2000 cu ft per hr respectively, are described in a new 4-p. bulletin. Seventeen leading features of the unit are keyed to a drawing to show operation, and specifications are also presented. The generators produce inert gases by complete combustion of gaseous fuels and appropriate processing of the products of combustion, as shown in the folder. Other Kemp products are also listed. C. M. Kemp Mfg. Co.

For free copy insert No. 6 on posteard.

Flexible Shaft Bulletin

A new 12-p. booklet outlines the basic principles of flexible shaft selection and application. The bulletin includes the latest developments in flexible shafting and is illustrated with drawings, photographs and tables showing construction details and performance data of both power drive and remote control types. Instructions are given on how to select flexible shafts for specific applications. Also included is a description of the variety of sizes and types of flexible casings available. S. S. White Industrial Div.

wa

flat

wh

du

We

sio

equ

Dec

For free copy insert No. 7 on postcard.

Hydraulic Cylinders

A complete standard line of double acting, single acting, telescopic oil hydraulic cylinders of the heavy duty type, suitable for operating pressures up to 1500 psi, are presented in a new 56-p. catalog. Full details covering many different types of mountings, style of fittings, ratings, dimensions and

Turn to Page 134

Contact KAYDDN of Muskegon

FOR ALL TYPES OF BALL AND ROLLER BEARINGS 4" BORE TO 120" OUTSIDE DIAMETER



THIS double head grinder permitted production of super precision accuracy in Naval gun mounts. It was designed to produce work of an angular accuracy of less than one-half thousandth (.0005") in 72", in flatness, squareness, concentricity, roundness and taper, and permitted interchangeability of gun mount parts which formerly were tediously hand scraped. Parts produced in regular production to an accuracy of .0002".

We believe this to be the world's largest, super precision industrial grinder, 26 of which were manufactured.

In heavy oil field machinery, ponderous steel-mill equipment, complicated paper-mill units...in rugged

road-building machines, excavators, hoists, crushers ... powerful bending machines, production units, and other industrial equipment . . . KAYDON bearings are improving performance and lengthening service-life. Look to KAYDON, Standard or Special, for the better bearing service your equipment deserves.

Counsel in confidence with KAYDON. Capacity now available for all sizes and types of KAYDON bearings . . . and for atmospheric controlled heat treating, precision heat treating, salt-bath and sub-zero conditioning and treatment, microscopy, physical testing and metallurgical laboratory services.

KAYDON

Spherical Roller • Taper Roller
Ball Radial • Ball Thrust
Roller Radial • Roller Thrust

ENGINEERING CORP.

MUSKEGON . MICHIGAN

December 14, 1950

ng to ations rators applete and prodin the s are y. Co. card.

es the

shaft

e bul-

evelopand is

photo-

con-

mance

nd re-

ections

lexible

ations.

ion of pes of

S. S.

teard.

ine of g, telelers of

ble for

00 psi, p. cata-

s, style

N AGE



PRODUCTION IDEAS

Continued

impact strength and crack-proof steel-bar feet. Ball or split-sleeve type bearings provide long wearing qualities, and are easily accessible for inspection and maintenance. Electric Machinery Mfg. Co.

For more data insert No. 23 on postcard, p. 35.

Hydraulic Press

Versatile press hot presses or cold forms variety of parts.

A 5000-ton hydraulic press which features unusual flexibility of operation is single-action, with both pushbutton and manual control. It is open four-column construction, arranged for rapid advance to the work. A quick reversal feature makes its operating cycle desirable for hot forging work, minimizing wear and tear of the dies by avoiding prolonged contact of the hot metal with the dies. Designed




originally for cold rubber-pad forming of sheet metal parts used in airplane frame construction, the press is now making hot-forged parts for earth-moving equipment. Its large reserve capacity permits it to be adapted to many purposes. Birdsboro Steel Foundry & Machine Co.

For more data insert No. 24 on postcard, p. 35.

Spot Welder

Adjustable for welding aluminum, ferrous and nonferrous alloys.

A new resistance welder for spot welding can be quickly and easily adjusted to welding aluminum, magnesium, stainless steel, Inconel, Monel, brass, mild steel and other alloys by change of control settings, and will handle various thicknesses of each. Welding speeds are said to be greater with this new welder and because it is a three-phase welder it can be used where there are power limitations. The PMCO2ST resistance spot welder



is a press type machine rated at 100 kva at 50 pct duty cycle; operates on 220 and 440 v three phase, 60 cycle current. Standard throat depth is 36 in. Welding on low carbon steel is from 0.022 to 0.156 in. (two thicknesses) and on aluminum and magnesium alloys a range from 0.025 to 0.081 in. Ranges for other metals vary. Sciaky Bros. For more data insert No. 25 on postcard, p. 35.

Raintight Multi-Breakers 1 through 20 circuits; approved

1 through 20 circuits; approved by Underwriters for outdoor use.

A complete line of raintight multi-breakers have formed and welded galvannealed steel enclosures. Conduit hubs are furnished in a variety of sizes in the top, and all knockouts in the sides, bottom and back are below the lowest electrical part. They are equipped with thermal-magnetic operating mechanism, give positive protection against dangerous overloads and act instantaneously on shorts. Similar multi-breakers are available for indoor use with combinations from 1 through 42 circuits. Square D Co.

For more data insert No. 26 on postcard, p. 35.

Special Machine Tool

Finishes 85 automatic transmission cases per hr at 100 pct efficiency,

A new Transfer-matic machine drills, chamfers, reams and taps 32 holes in the ends, sides and tops of



automatic transmission housinga. The operations are conducted at 2s stations. The first station is for loading and is followed by 7 drilling and 5 idle stations for the ends; 1 for indexing; and 10 drilling and 4 idle stations for the side and top. Eighty-three tools are used. Only one unskilled operator is required, the parts moving automatically from station to station. The machine uses the Cross machine control unit with Toolometers. Cross Co.

Fore more data insert No. 27 on postcard, p. li.

Flash Welder Control

Converts mechanically driven flash welders to hydraulic operation.

A low priced control known as Hydra-Flash has been developed for use with any make flash welder.



new or used, having transformed capacity up to 500 kva. It is a full hydraulic unit with adjustment calibrated, making duplication of setups as easy as turning a dial Hydra-Flash is said to greatly or

Turn to Page 138

New ladle crane carries 300-ton loads—keeps'em rolling with TIMKEN® bearings

THIS giant new ladle crane was designed and built by The Morgan Engineering Company to handle loads up to 300 tons. To insure dependable, trouble-free service under tremendous loads, the crane is equipped with 286 Timken® tapered roller bearings at vital points. As a result, maintenance on the new crane will be almost negligible, and the possibility of production delays from bearing trouble

ission iency.

taps 32 tops of

ousings.

is for

7 drill-

for the 10 drillhe sides ools are operator ng autostation. oss ma-Toolo-

en flasi ition. nown as leveloped

nsforme

is a full

justment cation d g a dial reatly e

ON AG

is minimized.


Made of Timken fine alloy steel, Timken bearing rollers and races have a hard, wear-resistant surface, and a tough, shock-resistant inner core. The line contact between rollers and races provides extra load capacity. Tapered construction enables Timken bearings to carry both radial and thrust loads, holding shafts in alignment and preventing wear on related parts. Under normal


conditions, Timken bearings last the life of the machine in which they are used.

Insist on Timken bearings in the machines you buy or build. Remember, the trade-mark "Timken" is your guarantee of value. The Timken Roller Bearing Company, Canton 6, Ohio. Canadian plant: St. Thomas, Ont. Cable address: "TIMROSCO".



This symbol on a product means its bearings are the best.





GREATER LOAD AREA

Because the load is carried on the *line* of contact between rollers and races, Timken bearings carry greater loads, hold shafts in line, wear longer. The Timken Roller Bearing Company is the acknowledged leader in: 1. advanced design; 2. precision manufacturing; 3. rigid quality control; 4. special analysis steels.

TIMKEN
TRADE-MARK REG. U. S. PAT, OFF.

TAPERED ROLLER BEARINGS



NOT JUST A BALL O NOT JUST A ROLLER THE TIMKEN TAPERED ROLLER BEARING TAKES RADIAL AND THRUST OF LOADS OR ANY COMBINATION

December 14, 1950

Iron Age Introduces



WILBUR R. LEOPOLD, appointed assistant vice-president of Worthington Pump & Machinery Corp., Harrison, N. J.



J. L. NEUDOERFER, elected president of Wheeling Steel Corp., Wheeling, W. Va.



ALEXANDER ZEITLIN, named vicepresident of Hydropress, Inc., New York and Loewy Construction Co., Inc., New York.

Joseph H. Woodward II, elected a member of the board of WOODWARD IRON CO., Woodward, Ala., to succeed his father, the late A. H. Woodward.

Fred M. Garland, named assistant to the president and general traffic manager of PRESSED STEEL CAR CO., Pittsburgh.

Myles L. Mace, chairman of the U. S. Dept. of Commerce Small Business Advisory Committee, and George M. Hansen, president of the National Federation of Financial Analysts, appointed directors of BETTINGER ENAMEL CORP., Waltham, Mass.

Roy C. Ingersoll, president of Borg-Warner Corp., Chicago, elected a director of KELSEY HAYES WHEEL CO., Detroit.

Leonard Happ, elected vice-president in charge of purchases for T. E. CONKLIN BRASS & COPPER CO., New York. Mr. Happ has been with the firm for 40 years. Bruce C. Conklin and Theodore B. Conklin, Jr., elected assistant treasurers.

Dr. R. H. Boundy, elected a director of DOW CHEMICAL CO., Midland, Mich., succeeding John S. Crider, who resigned.

Glen McDowell, formerly roll sales manager, Aetna Standard Engineering Co., has joined the roll sales force, Lewis Foundry & Machine Div. of BLAW-KNOX CO., Pittsburgh. W. B. Hackett, appointed assistant to the president in charge of engineering; C. W. Baker manager, contract engineering; A. C. Fisher, manager, sales engineering and service; and G. T. Andrews, manager, machinery sales.

M. E. Coyle, resigned as an executive vice-president and member of the board of directors of GENERAL MOTORS CORP., Detroit, effective Dec. 31. Mr. Coyle has been associated with the company for 39 years. Louis C. Goad, will succeed Mr. Coyle as executive vice-president in charge of the car and truck group, body and assembly divisions group, and the accessory group. John F. Gordon, elected a director and a member of the administration and operations policy committees. He will succeed Mr. Goad as

group executive in charge of Fisher Body, Ternstedt and Buick-Oldsmobile-Pontiac assembly division. Charles A. Chayne, made vice-president in charge of the engineering staff. Carl H. Kindl. Harry J. Klingler and Cyrus R. Osborn, named directors and members of the operations policy committee. Henry C. Alexander, elected to the financial policy committee.

William F. Lewis, named a vicepresident, and Stephen G. Harwood, formerly district sales manager in New York, appointed sales manager of MONTREAL LOCOMOTIVE WORKS, LTD.

Harold R. Potter, named sales manager, Cleveland district, for CAR-PENTER STEEL CO., Reading, Pa. Mr. Potter succeeds James S. Bailey who has been made assistant to the vice-president in charge of sales.

E. A. Erickson, appointed manager of the Hornell, N. Y., plant of SKF INDUSTRIES, INC., Philadelphia. Mr. Erickson has been with the company for 38 years. Harry R. Fillmore, promoted from general foreman to assistant plant manager.

84

THE IRON AGE

sale age Det gan the

SS

th

tat

chen NEB Del. Notr ager

AIR:

MIU

Jairepre office CO., water tive,

Jul Harti SHAI has r firm. Mr. T Henry presid sistan

Leon manag rate Wayne TRIC appoin equipn

Euge sistant of AM burgh. for 29

Decen

Merritt W. Jones, appointed manager for the newly created Baltimore sales district of SIGNODE STEEL STRAPPING CO., Chicago.

Robert T. Daily, promoted to the position of field engineer in charge of the Chicago office for LORD MFG. CO., Erie, Pa.

Robert M. Clark, named representative of the president in Washington, effective Jan. 1, for the SANTA FE RAILWAY CO., Chicago.

James E. Blue, formerly assistant sales manager and Ohio branch manager of TRUSCON LABORATORIES, Detroit, named manager of the Michigan branch. Mr. Blue has been with the firm for 35 years.

Chet Borlet has joined the sales and service staff of UNITED CHRO-MIUM, INC., New York.

Charles B. McCoy, appointed assistant general manager, Electrochemicals Dept. of E. I. du PONT de NEMOURS & CO., INC., Wilmington, Del. Mr. McCoy succeeds Donald O. Notman, who was made general manager, Electrochemicals Dept.

T. F. Riddle has joined LUSCOMBE AIRPLANE CORP., Dallas. Mr. Riddle was formerly factory manager for Huey & Philp Co., Dallas.

her

ile-

A.

rge

ndl.

08-

bers

ttee.

the

vice-

rood,

r in

ager

VE

man-

CAR-

, Pa.

ailey

o the

nager

SKF

iphia.

com-

more,

n to

AGE

James H. Jones, appointed sales representative, San Antonio district office of ALLIS-CHALMERS MFG. CO., Milwaukee. Frank Barilla, named water conditioning sales representative, Cleveland district office.

Julian G. Tabor, in charge of the Hartford office of BROWN & SHARPE MFG. CO., Providence, R. I., has retired after 45 years with the firm. Herbert Richardson will succeed Mr. Tabor as Hartford representative. Henry D. Sharpe, Jr., elected a vice-president, and Paul R. Hatch, an assistant secretary.

Leon C. Swager, assistant to works manager, named in charge of wage rate administration for the Fort Wayne Works, GENERAL ELECTRIC CO., Schenectady. S. B. Fuerst, appointed supervisor of methods and equipment, Fitchburg Works.

Bugene Mowlds, Jr., appointed assistant general contracting manager of AMERICAN BRIDGE CO., Pittsburgh. He has been with the company for 29 years.

Iron Age, Salutes

RICHARD E. Le BLOND

IF, as somebody has said, the world belongs to a patient man, Richard E. LeBlond, recently-elected president of National Machine Tool Builders Assn., will some day have title to a lot of acreage.

He is president of the R. K. Le-Blond Machine Tool Co., one of the world's largest manufacturers of lathes. His knowledge of his company, where he started as a machine operator in 1922 immediately following graduation from Purdue, and the industry, is a constant source of amazement to his associates.

Born in Cincinnati in 1900, he has a keen interest in the machine tool industry and in its advancement.

Behind his calm exterior lie the qualities of direction, clarity of purpose, an affinity for detail and a 24-hr-a-day interest in his plant and its operation. His constant search for improvement in his company's products is tempered by a well-developed sense of caution.

One of Mr. LeBlond's associates said of him recently, "Rich has the judicial mind," an attribute which Xavier University, Cincinnati, saw fit to recognize formally by awarding him an honorary LLD. in 1948. A less-articulate friend has said, "Rich has his flywheel on the engine all the time."

A family man with a wife and five children, his moments of relaxation are devoted to golf (he shoots in the low eighties), yachting and farming.

His business and civic accomplishments comprise an imposing list. He is a director of the R. K.



LeBlond Machine Tool Co., Cleveland Automatic Machine Co., Cincinnati Electrical Tool Co., Multi-Colortype Co., Printing Machinery Co., Security Storage Co., Fifth-Third Union Trust Co., all of Cincinnati, and the Ohio Mechanics Institute of Cincinnati.

He is a member of the executive committee of the Machinery & Allied Products Institute, a member of the Engineering Society of Cincinnati, the American Society for the Advancement of Management.

He served in the government relations committee of the National Machine Tool Builders Assn. and on the Civilian Officer Naval Procurement Board in World War II.

His election to the presidency of NMTBA puts him at the helm of one of the nation's key industries, in what may prove to be one of the great crises in history. His sincerity and considered judgment will be potent assets in the job that lies ahead.



JAMES C. HAMILTON, appointed assistant to vice-president-contracting, of American Bridge Co., Pittsburgh.

Walter H. Sarraf, appointed to the Pittsburgh district sales staff of HARBISON - WALKER REFRAC -TORIES CO., Pittsburgh.

R. E. Florine, appointed district manager for the new district sales office in Seattle of the WHITING CORP., Harvey, Ill. A. C. Kukral. named resident sales engineer at the new sub-sales office in Cleveland.

C. A. Gordon, appointed representative in Buffalo for LACLEDE-CHRISTY CO., St. Louis.

Ray A. Bland has joined the sales engineering department of SUTTON ENGINEERING CO., Bellefonte, Pa. He was formerly associated with the sales department, United Engineering & Foundry Co., Pittsburgh.

Dan C. Swander, Jr., named sales manager of COLUMBIAN VISE & MFG. CO., Cleveland. Mr. Swander will continue as vice-president.

Clarance Stanley, named a member of the financial staff of GENERAL MOTORS CORP., Detroit.

Raymond M. Lyons, named industrial relations manager, Lincoln plant, Lincoln-Mercury Div. of FORD MOTOR CO., Dearborn.

Harold L. Greenhut, appointed project engineer of ROTOR-CRAFT CORP., Glendale, Calif.

Erle I. Shobert II, made supervisor of the electrical laboratories of STACKPOLE CARBON CO., St. Marys, Pa. Mr. Shobert will continue as technical director, rare metal contacts and nonferrous metallurgy.

C. F. Duff, formerly representative in Cleveland for MORSE TWIST DRILL & MACHINE CO., New Bedford, Mass., named district manager of Ohio and Indiana. A. E. Boot and Harold Symes will now represent Morse in the Cleveland territory.

Earl C. Blaine, appointed plant manager and Robert J. Kalbfleisch, assistant works manager of the BUDD CO., Philadelphia.

J. J. Thompson, named manager of the sales personnel and training division of WORTHINGTON PUMP & MACHINERY CORP., Harrison, N. J. He has been associated with the firm for 17 years.

Walter A. McLean, named manager of erection of the INDUSTRIAL BROWNHOIST CORP., Bay City, Mich., replacing the late John J. Schreck.

Daniel E. McBride, appointed treasurer of PAUL & BEEKMAN, INC., Philadelphia. Mr. McBride succeeds J. E. Schmidt, who was promoted from secretary-treasurer to secretary-controller.

William A. Callison, vice-president in charge of western regional sales of AMERICAN LOCOMOTIVE CO., Schenectady, assigned in charge of eastern regional sales.

George A. Hinckey, appointed sales manager, New York factory branch of the AUTOMATIC TRANSPORTA-TION CO., Chicago.

John W. Pennington, former staff engineer for the Caterpillar Tractor Co., named chief engineer, Piston Ring Dept. of KOPPERS Co., INC., Pittsburgh.

Ellis C. Wester, named sales manager, Cutting Tool Div., CHARLES H. BESLY & CO., Chicago, and Hal Seger, named manager, of drill and reamer sales.

Bert Cole, formerly general manager of Crosley Distributing Corp., New York, has rejoined the PHILCO CORP., Philadelphia, as district sales representative for the New York-Newark area. Mr. Cole succeeds Clare Courtney who was appointed sales manager of the Accessory Division.

C. E. Lesher, for the past 27 years associated with the PITTSBURGH CONSOLIDATION COAL CO., Pittsburgh, has retired.

Edward J. Gardner, formerly superintendent of blast furnaces and coke ovens, made assistant to Hjalmar W. Johnson, vice-president of INLAND STEEL CO., Chicago. Lee B. Luellen,



WALTER C. FOOTE, appointed sales manager of Dearborn Gage Co., Dearborn, Mich.

named assistant general superintendent in charge of primary operations and mills; J. Foster Mayberry, assistant general superintendent in charge of the flat rolled departments. Theodore F. Plimpton, formerly blast furnace superintendent will replace Mr. Luellen as assistant general superintendent in charge of industrial relations. M. M. McClure, promoted to administrative assistant to Mr. Plimpton. William A. Blake, promoted to director of community relations; James F. Peters, made superintendent of blast furnaces; and William C. Kostbade, superintendent of the hot strip mills.

A. W. Plier, elected exe utive vicepresident and general manager of D. J. MURRAY MFG. CO., Wausau, Wis. D. J. Everest, made vice-president; C. L. Durkee, director, vice-president and sales manager; W. A. Marquardt, secretary; P. W. Hoeper, assisant secretary; and Grover Keeth, assistant treasurer.

OBITUARIES

Frank J. Itts, 54, assistant supervisor of employment, Youngstown district, Youngstown Sheet & Tube Co., Youngstown, died Dec. 3.

Clifford B. Cornell, 63, assistant director of personnel, Chrysler Corp. Detroit, died recently.

L. W. Copeland, Detroit manager of Jones & Lamson Machine Co. Springfield, Vt., passed away recently.

Henry P. Kerber, former official of Gulf States Steel Co., Birmingham, died recently.

Charles Englehard, 83, president of Baker & Co., Newark, N. J., died recently.

Dece

SEVEN STRONG REASONS

Appreciation of its many advantages explains the trend to N-A-X HIGH-TENSILE steel by manufacturers of commercial vehicles.

HIGH STRENGTH

HIGH FATIGUE RESISTANCE

turers of commercial vehicles.

FINER GRAIN STRUCTURE

GREAT IMPACT TOUGHNESS

EXCELLENT WELDABILITY

HIGH CORROSION RESISTANCE



GREAT LAKES STEEL CORPORATION
N-A-X Alloy Division, Ecorse, Detroit 29, Michigan

NATIONAL STEEL CORPORATION

December 14, 1950

87

blast eplace eneral astrial ted to Plimped to tions; endent arm C. he hot

ntentions , ast in

nt and lt, secsecresistant

, Wis. ent; C.

be Co...
ssistant
Corp.,

wn dis-

ne Co., ecently. ficial of ingham,

ident of died re-

N AGE

On the ASSEMBLY LINE

AUTOMOTIVE NEWS AND OPINIONS

Auto industry begins streamlining for defense production . . . Nonferrous shortage blow to Detroit . . . Controlled Materials Plan coming . . . U. S. Asks GM, Ford to hold prices.



By WALTER G. PATTON

Credit Rule Hits—Detroit automobile manufacturers last week began an all-out campaign to hold auto production in high gear. K-F has already been hit hard enough by Regulation W and got help from RFC. Other independent producers are deeply concerned about credit restrictions. Meanwhile, Nash opened a Washington office, indicating the company is streamlining its organization to take on whatever war contracts may be available.

Also, last week M. E. Coyle, GM executive vice-president, resigned unexpectedly ahead of his scheduled retirement. The prospect of shifting huge GM from a peacetime to a war economy undoubtedly contributed to Mr. Coyle's decision to retire.

Unemployment Threatens—The U. S. move toward a war economy

is going ahead fast enough so that the threat of widespread unemployment in the automobile industry has become very real.

Tooling orders are already running out in Detroit die shops. Detroit is just winding up its greatest year both from a standpoint of total vehicles produced and value of product. As we go to press, some local automobile executives will settle for 1951 output at about half the 1950 rate.

Nonferrous Shortages—There is much talk here about shortages of nonferrous materials. Observers see the new limitation on copper as a serious blow to the industry. Many hardship cases are expected in the wake of the 35 pct reduction in aluminum.

As usual, the industry is juggling its available material with considerable success. General Motors, for example, is reported to have switched aluminum from its Frigidaire Div. to some of the car and truck divisions. Cadillac and Oldsmobile which use aluminum pistons are expected to be hardest hit by the aluminum order. Meanwhile, Chevrolet and Pontiac have happily continued in 1951 the use of cast iron pistons.

Companies Disagree — There is some difference of opinion in the automobile industry between large and small companies about allocating available materials.

Most small companies would

have preferred an across-the-board percentage cut in automobile production. Large companies favor a percentage reduction in available materials. This gives them an opportunity to juggle materials, making possible maximum output under government restrictions.

h

fr

st

pe

pi by

in of fu

In

on

tie

tin

st

lio

\$2

pr

ou

(1

wi

du

da

K-

for

wh

the

los

pr

fin

ch

gu

ah

wa

no

C.

of

low

De

See Controlled Materials — The feeling in Detroit seems to be that sooner or later a controlled materials plan will be set up. When this happens, there will be government decisions about essential and non-essential industries.

Larger automobile circles feel that many vendors classified as non-essential may be switched to meet essential transportation needs, permitting optimum automobile output. Recent history has demonstrated the resourcefulness of the industry in obtaining whatever raw materials are available.

Washington Steps In — If any further evidence was needed that direction of the automobile industry is moving from Detroit to Washington it was available in the government's request last week to the nation's automakers to "suspend" car price increases already announced or contemplated.

Each of the automobile producers has been asked to hold back on contemplated price increases until further government action on price and wage controls can be taken. Previously, GM had an-

nounced increases averaging about 5 pct on its passenger cars. Simultaneously, Ford which has been holding back its price increase, announced advances ranging from \$87.50 on Fords to \$165 on Lincolns.

Request Turned Down — Telegrams to the automobile industry from Allen Valentine, economic stabilization chief, requesting suspension of previously announced price increases have been rejected by General Motors and Ford.

The automobile industry is meeting this week with government officials in Washington to discuss future policies of the industry—including what to do about prices. In the opinion of practically everyone here, wage and price stabilization is now only a question of setting up the proper controls.

poard

pro-

vor a

lable

n op-

mak-

t un-

- The

e that

mate-When

gov-

ential

feel

ed as

ed to

tation

auto-

y has

lness

what-

lable.

f any

d that

indus-

oit to

in the

eek to

lready

roduc-

ack on

es un-

on on

an be

d an-

AGE

K-F Loan Has Strings—Kaiser-Frazer got its loan from Reconstruction Finance Corp. but not without strings attached. The original request was for a \$38 million loan but this was reduced to \$25 million by RFC. This loan is in addition to the \$44,500,000 loan previously granted to K-F.

In granting the loan, RFC held out for the following conditions:

(1) No price increases without written consent from RFC, (2) reduce production to 600 units per day by the end of December, (3) K-F must make "conscientious efforts" to obtain defense work which will be given priority over the production of automobiles. The loan can be used to finance defense production.

The K-F loan was requested to finance warehousing of cars which K-F dealers are unable to purchase. With its hands tied tight on auto production, it's a good guess K-F will order full speed ahead in its efforts to convert to war production.

Higher Material Costs—In announcing GM's price increase, C. E. Wilson indicated that prices of commodities used in car production have jumped from 7 to 300 pct. These increases are as follows: aluminum 11.8 pct; nickel 20

pct; copper 32.4 pct; lead 41.7 pct; tin 66.9 pct; zinc 68.5 pct; wool 72.4 pct; and rubber 300 pct. Prior to recent price advances, the cost of steel had advanced 7 pct. GM wages have increased 11.1 pct during 1950, Wilson said.

M. E. Coyle Retires—The retirement of Marvin E. Coyle, executive vice-president and director of General Motors Corp., came without notice to outsiders. Mr. Coyle has been associated with GM since 1911. An accountant, he headed Chevrolet with distinction. Appointed a vice-president of General Motors and a director, he was advanced to executive vice-president in 1946. His prodigious memory earned him the undisputed title, "Mr. Facts and Figures."

In his meetings with the press, Coyle quoted statistics from memory at a rate that left reporters dizzy. His ability to marshall facts was best exemplified by a statement he made before the Senate sub-committee on profits in Washington, Dec. 20, 1948. This is still regarded as the most masterful

presentation of automobile industry policy ever assembled.

Louis C. Goad will succeed Mr. Coyle as executive vice-president in charge of the car and truck group, body and assembly divisions. John F. Gordon, formerly head of Cadillac, succeeds Mr. Goad as group executive in charge of Fisher Body, Ternstedt and Buick-Oldsmobile-Pontiac assembly divisions. Gordon also becomes a member of the administration and operations policy committee.

Promotions Come Fast—This is Gordon's second promotion within 6 months. Last July, he was named vice-president in charge of the corporation's engineering staff. Charles A. Chayne succeeds Gordon as head of the GM engineering staff. Chayne has been chief engineer of Buick since 1936.

Other year-end GM promotions include Harry J. Klingler of Pontiac as group head of passenger car and truck divisions; S. E. Skinner of Oldsmobile as group head in charge of Accessory Div.

THE BULL OF THE WOODS

By J. R. Williams



I,84I,000 TONS WITH ONE "NATIONAL" CARBON LINING!







• Carbon is the ideal material for lining blast furnaces. One example proving this statement is the record of one of the largest blast furnaces in this country, in which a "National" carbon block lining was installed several years ago. This furnace has produced approximately 1,841,000 tons of iron as of September 1, 1950 and is still going strong with the original lining.

The terms "National" and "Eveready" are registered trade-marks of

NATIONAL CARBON DIVISION

UNION CARBIDE AND CARBON CORPORATION

30 East 42nd Street, New York 17, N.Y.

District Sales Offices: Atlanta, Chicago, Dallas, Kansas City, New York, Pittsburgh, San Francisco
Foreign Department: U. S. A.

MORE THAN DOUBLE THE USABLE LIGHT!

The biggest news since the invention of flashlights—the brand new, leak-proof "Eveready" No. 1050 flashlight battery—gives more than double the usable brilliant white light for critical uses than any

other flashlight battery we have ever made.

NO METAL CAN TO LEAK OR CORRODE



WEST COAST PROGRESS REPORT

Digest of Far West Industrial Activity—By R. T. REINHARDT



Biggest Geneva Month—Finished steel production of the Geneva Steel Co. for November exceeded the best previous month by more than 15,000 tons. November total was 112,759 tons and the old record was May 1950 with 97,649 tons. November shipments totalled 113,540 tons, exceeding the previous high last August by more than 17,000 tons.

Lots More Chryslers—Chrysler caused elation in Southern California with an announcement by Manager C. C. Rowles that the automotive assembly division in Los Angeles will be trebled in production capacity with the addition of 880,000 sq ft. The new unit will be in operation sometime in 1951 and will add some 1200 employees to the payroll.

Present Chrysler production is 400 cars per day. It is estimated automotive assembly plants in the Los Angeles area purchase well over \$100 million worth of component parts annually from metal fabricators and casting and stamping producers.

Seattle Scrap-Short — Formerly the softest and most over-supplied market for scrap metal in the nation, the Pacific Northwest expects to be scrap hungry by late winter or early spring. Inquiries and orders for February and March deliveries are 50 pct above normal requirements, according to the

Seattle trade and there is every prospect of increased demand and pressure.

Shortage of Workers—All those statistics on increased Pacific Coast population and mass migration to the Far West seem belied by a scramble for manpower in heavy industry and an increasing shortage. California's Dept. of Industrial Relations reports an all-time high of 3 1/3 million wage and salary workers in non-agricultural establishments for October and only 143,000 unemployed, less than half of the same month a year ago.

Screw Machine Census—A survey of automatic screw machine facilities in the Portland area was recently completed by the Industries Dept. of the Portland Chamber of Commerce.

In 16 plants there are a total of 57 single spindle screw machines ranging in capacity from \%-in. to 4-in. with the greatest frequency in \\\^2_2\, \\^3_4\ and \1\\\^2_2\-in. capacities.

In addition there are three 4-spindle machines, one 6-spindle and one 8-spindle in the 15%-in. capacity. Several of these shops have been operating on a 3-shift basis since World War II.

Garrett to Phoenix — Garrett Corp. of Los Angeles announces a new 60,000 sq ft plant on 33 acres at Phoenix, Ariz., to be operated as AiResearch Mfg. Co. to manufac-

ture air turbine refrigerators and cabin pressure controls, requiring tolerances so fine that a completely air-conditioned plant in a new labor market inland is preferable. The expansion involves \$1½ million and will immediately add 300 personnel to the company's 2600 staff.

Add Forging Billets — Forging quality carbon steel billets have been added to its production by Bethlehem Pacific at Seattle, South San Francisco and Los Angeles. Another recent addition was Bethlehem's "Mayari R" low-alloy, high-strength corrosion-resisting steel.

Expansionist Undaunted—When Henry Kaiser conceived his first shipyard 10 years ago at Richmond, eyebrows raised at the earthmover who dared a new element. But skeptics have become converts so far as Henry Kaiser is concerned.

Therefore, when last week from Washington Henry Kaiser proposed a \$200 million expansion program which "he hoped to boost to \$500 million in the near future" newspapers at Portland and in the San Francisco area spread the news. The \$25 million tinplate mill at Fontana is reasonably sure to come, but the reopening of the shipvards at Vancouver and Richmond may be less likely. As was pointed out in these columns last week, shipbuilding on the Pacific Coast is costly except for large quantity assembling.

N AGE

Extra Toughness



Better Machinability



DESEGATIZED BRAND*

HIGH SPEED STEELS

HI CARBON - HI CHROME DIE STEELS

Fewer Heat Treat Losses



LATROBE ELECTRIC STEEL COMPANY

ste

gar

tar

gra CM

De

LATROBE, PENNSYLVANIA

Branch Offices and Warehouses located in principal cities.



THE FEDERAL VIEW

THIS WEEK IN WASHINGTON

CMP Sooner—A Controlled Materials Plan by second quarter 1951, rather than the original schedule of second half 1951 is now in the cards. This is the story as relayed to the Steel Producers Advisory Committee by officials of the National Production Authority.

NPA officials, including Dave Carson, Director of the Iron and Steel Div., do not foresee any orders cutting back steel usage across-the-board, as in the case of aluminum, copper, nickel, etc. Cutbacks in the use of these other materials will take care of demands for civilian steel before CMP takes over. There will be end-use limitations on steel, however, probably very soon. Also on the books is a series of orders specifying end-uses of alloy steels.

New Allocations — Meanwhile, the steel producers were told of several new allocation programs that will be announced soon. These cover locomotives, Canadian freight car production (8000 tons monthly), a program for Canadian warehouses paralleling the domestic warehouse order, and a February landing mat program. A major program for the petroleum industry is also under active consideration.

This industry estimates 1951 steel needs at 11.9 million tons. NPA is now attempting to get these requirements into realistic form, for as presented by the industry they include everything made of steel bought by the industry, regardless of source. Addition of these programs to the 10 pct military needs for steel and other programs still to come will hasten CMP.

Forms to File—NPA also told the steel producers that they will be required to file two monthly By EUGENE J. HARDY



forms, now in preparation. The first forms will cover January 1951 data. These are: (1) A shipment report by product and program, also showing past due orders. (2) orders accepted under "DO" priorities, directives and all allocation programs.

There is no program contemplated for the steel industry's own expansion program. Instead it will be worked out by the industry.

Plate Conversion and IAC's—Another must will require conversion of some sheet and strip capacity to plate to meet increasing plate requirements. If necessary, government directives will be issued, although it is believed the industry can meet this situation satisfactorily.

Individual product advisory committees are being established to cover the following items: Plates, bars, stainless, tubing, alloy and rolled armor. Eventually, there will be committees covering all major products, but it is still NPA policy to set up these committees only as they are needed.

Metals Price Executive—On the price control front Sam Ewing, Youngstown Steel & Alloy Co., last Wednesday moved into the Economic Stabilization Agency as consultant on ferrous and nonferrous metals pricing. A former OPA metals official, Mr. Ewing is the first appointment to the agency from the metals industry. His major task probably will be to set

up divisions covering iron and steel and other metals.

Civilian Requirements—Civilian economy needs during mobilization will be looked after by an office within the NPA bearing the exact name of its WPB predecessor—the Office of Civilian Requirements. At present, the OCR exists only in skeleton form, its nucleus being the Marketing and Distribution Div. of the Office of Industry and Commerce.

OCR will determine requirements and act as claimant agency for civilian goods and services; act as claimant for all civil government; present requirements for materials needed for consumer goods and services; and review proposed orders and the administration of existing orders to assure that full consideration is given to civilian needs.

Centralize Controls — Don't be surprised if the Senate Preparedness Subcommittee (the 1950 version of the Truman Committee) soon calls for centralization of emergency control activities now scattered in about a dozen groups within four Cabinet departments and three independent agencies. Centralization of such activities would not only make it easier for the businessman but should also minimize the World War II civilian vs. military battle.

Meanwhile, the subcommittee expects to issue reports on steel, nickel and tin before the end of this month.



she's really two ships in one!"

"I'm Clyde Johnson, Second Mate on the S. S. Wilfred Sykes, newest ship in the Inland Fleet. If you live near the Lakes, you may have seen her. In that case you'll know what I mean when I say the Sykes is two ships in one. She's big—678 feet long, with a capacity of 20,000 tons of ore. And she's fast—makes a round trip between Superior and Indiana Harbor in five days. That's why she can haul 880,000 tons of iron ore in one season . . . actually the work of two ordinary lake freighters."

The addition of the S. S. Wilfred Sykes to Inland's iron ore fleet is just one more step in a continuous modernization and expansion program. This constant improvement of every phase of steelmaking facilities is further evidence that Midwest steel users can put their confidence in Inland as a progressive and dependable source of steel in peace and war.


INLAND STEEL COMPANY

38 South Dearborn Street • Chicago 3, Illinois
Sales Offices: Chicago • Davenport • Detroit • Indianapolis • Kansas City
Milwaukee • New York • St. Louis • St. Paul



Products: Sheets, Strips, Tin Mill Products, Bars, Plates, Structural Shapes, Sheet Piling, Reinforcing Bars, Pig Iron, Rails and Track Accessories.

TO ALLENDER CIT



New Process

Slashes Cost of

Phosphoric Acid Pickling



n-

nt

is

d-

nd

d-

Rails

N AGE

By C. F. PAULSON,
Research Chemical Engineer
and
M. E. GILWOOD,
Manager of Chemical Research,
The Permutit Co.,
New York



Cost of phosphoric acid pickling can be cut 66 pct by new process which reclaims the acid for reuse. In many cases, cost will be below that of the less desirable pickling with sulfuric acid.

OST steel undergoes pickling at one time or another before it becomes part of a finished product. Pickling is done on some steel in the mills where it is produced. In the plants of steel users, pickling is common as a surface preparation, especially prior to applying a phosphate coating to the steel. While some alloy steels are frequently pickled with muriatic acid, nitric acid, or mixtures of acids, the common grades of steel are usually pickled with a 6 to 10 pct sulfuric acid solution.

Actually, pickling with phosphoric acid is preferable to sulfuric acid pickling. The number of dipping and rinse tanks is less than in a sulfuric acid pickling system, where rinsing must be more complete. This means lower investment and less floor space occupied. Phosphoric acid is not so corrosive as sulfuric acid under normal conditions of use, so that less expensive construction is possible and less maintenance is required. There are no obnoxious or corrosive strong acid fumes which are objectionable to operating personnel.

In addition, it has been known for many years that steel treated with dilute phosphoric acid or a phosphate solution acquires an adherent phosphate coating which is rust resistant and forms an excellent base for paint. Some phosphate coatings on machined parts that are to receive wear, or on metal, which is to be drawn or extruded, provide a surface which absorbs oil and reduces friction.

A phosphoric acid pickling treatment generally utilizes a solution of 15 to 50 pct phosphoric acid in water. Frequently the process also includes chromates, solvents or detergents to assist in removing mill scale, grease and oil. The phosphoric acid first dissolves the rust and mill scale and then forms a coating of iron phosphate on the surface. The various commercial phosphate coating processes in use today utilize a solution with a lower free acid content, which is

capable of producing a much heavier phosphate coating. With these solutions, prior pickling with sulfuric acid is usually required.

In phosphoric acid pickling, base metal is not so strongly attacked as is the case with sulfuric acid. This is the reason for the reduced rinsing requirement when phosphoric acid pickling is used. It also means that control of the pickling is much simpler, because overtreatment does not result in as high loss of metal as in the case with sulfuric acid. And, the disposal of the waste pickling solution is simplified since it contains less dissolved base metal.

Despite these advantages, phosphoric acid pickling has not been used extensively because the acid itself is so much more expensive than sulfuric acid. Now a process which makes phosphoric acid pickling competitive, costwise, with sulfuric acid pickling has been proven successful. The new process depends on continuous purification and reclaiming of the phosphoric acid pickling solution.

During the pickling operation, phosphoric acid reacts with rust and mill scale to form iron phosphate. In the reclaiming process, the acid is pumped directly from the pickling tank through a cation exchange unit of special design containing a hydrogen zeolite cation exchange resin. This resin has the property of releasing hydrogen ions and binding, in exchange, iron ions from the acid solution. The resin thus absorbs the dissolved iron from solution and simultaneously converts the iron phosphate in the pickling solution back to phosphoric acid.

When the exchange medium becomes exhausted and no longer removes iron, the flow of pickling solution is stopped and the solution remaining in the shell and piping is rinsed to the pickling tank with water. This results in a small amount

PICKLING COST COMPARISONS


Cents per squero fee?

Sulfuria Acid Pickling Phospharia Acid Pickling Phospharia Acid Pickling Phospharia Acid Pickling Phospharia Phospharia Phospharia Acid Pickling Posting Pickling Picklin

of dilution of the phosphoric acid which serves to make up for water evaporation and dragout losses. The losses of phosphoric acid itself from the solution are negligible.

The unit is then backwashed and regenerated with sulfuric acid. The chemical reactions which take place give hydrogen ions back to the zeolite, restoring it to its original condition, and pick up the iron ions to form iron sulfates. This solution is then discarded as waste. After proper rinsing, the unit is once again ready to treat the phosphoric pickling acid.

In operation, the reclaiming process is used to maintain the metal content of the bath at the optimum point, rather than to remove all of the



FLOWSHEET of typical phosphoric acid pickling system. Note how equipment for acid reclamation can be superimposed on an existing pickling installation.

iron. The most satisfactory surface coating is produced when there is a substantial quantity of iron dissolved in the solution. However, if the iron content is too high the pickling operation becomes too slow.

An iron content of 2 pct expressed as ferrous iron in a 40 pct phosphoric acid solution appears to be most suitable for cold rolled steel. Therefore only a portion of the total pickling bath is passed through the hydrogen zeolite unit and most of the iron from this portion is removed. This treated portion is returned to the pickling bath to mix with the remainder of the pickling solution, lowering the overall iron content. The only phosphoric acid consumed is that which actually forms the rustproof coating.

The accompanying diagram shows how the phosphoric acid reclaiming process may be super-imposed on existing facilities for phosphoric acid pickling. Installation of the process necessitates no other changes in the existing conventional pickling installation. The unit can be designed to operate either manually or automatically.

The reclaiming process was originally developed to reduce the operating cost of existing phosphoric acid pickling installations. But the operating economies are so marked that the process is of interest wherever stamped, machined or otherwise processed iron and steel are

WILLTHUM! LIDING

now being pickled with sulfuric acid before further fabrication.

The accompanying table gives cost information for typical pickling of cold rolled 13 gage sheet, in cents per square foot of finished metal. These figures were prepared for sheet which is processed by the fabricator. Since the finished product is sold by weight, obviously the fact that less metal is dissolved in the pickling treatment means a direct cost saving. These cost figures are also representative of pickling operations in a metal fabricating plant, except that in most cases there would be no direct saving in steel costs attributable to the fact that less metal is dissolved in pickling. However, there is a saving in the disposal costs of wastes since they will contain less iron.

d

is

ty he

rs reis nd ed. ng ng

ch

he

er-

cid

tes

nal

ned

de-

the the naare

GE

This installation has been operating successfully since the early part of this year. At first the work treated was chiefly cold rolled steel which had been stamped and formed. A portion of this steel is also welded into subassemblies. However, the current steel shortage has led to the use of a great amount of hot rolled steel and rusty metal. This has tripled the phosphate conversion load of the Permutit unit.

The increased use of off-grade steel has made it necessary to lower the iron content in the pickling bath from 2 pct to 1 pct in order to clean surfaces in the allotted time. The unit has satisfactorily produced this lower iron content in the bath. The phosphoric acid solution used is Prep-Pik-L, supplied by the Neilson Chemical Co. Phosphoric acid pickling was chosen, among other reasons, because it gave a

HOW IT WORKS

Pickling Operation

 $3 FeO + 2 H_3 PO_4 \longrightarrow Fe_3 (PO_4)_2 + 3 H_2 O$

 $Fe_2O_3 + 2H_3PO_4 \longrightarrow 2FePO_4 + 3H_2O$

Acid Reclaiming

 $\mathrm{Fe_3(PO_4)_2} + 3\mathrm{H_2Z^*} {\longrightarrow} 3\mathrm{FeZ} + 2\mathrm{H_3PO_4}$

2FePO4 + 3H2Z ------ Fe2Z3 + 2H3PO4

Exchange Resin Regeneration

 $H_2SO_4 + FeZ \longrightarrow H_2Z + FeSO_4$

 $3H_2SO_4 + Fe_2Z_3 \longrightarrow 3H_2Z + Fe_2(SO_4)_3$

*Z in these equations is not the symbol of a chemical element, but represents the zeolite resin.

surface, after painting, superior to other commonly used phosphate coating methods.

During a recent month, approximately 3600 lb of iron was dissolved in the phosphoric acid in this installation. Without regeneration, this amount of iron would be enough to necessitate the replacement of the complete bath three times each month at a total monthly cost of \$30,000. Contrasting with this, the cost of the regenerant sulfuric acid used during a month is less than \$450.

INSTALLATION of phosphoric acid pickling and reclaiming facilities, treating 500 tons of steel per day. Exchange resin is in tall tower at left. Short center unit is an acid-regenerated water softener. Tank at right contains strong sulfuric acid for regeneration.



Are You Getting the Most

Out of Your



WILLIAM LIBRARIE

By JOHN E. HYLER
John E. Hyler and Associates,
Peoria, Ill.

The drill press is such a simple, common tool that it doesn't always get the attention more complex tools do. There are many attachments and modifications, some of which you may have overlooked, that can increase the versatility of your drill presses.

HE drill press is one of the most widely used of all machine tools. Most metalworking shops, no matter how small, have at least one. But, often simply because it is so familiar, the drill press does not receive the inventive attention of shop personnel that more complex machines do. This is especially true in small shops. When full use is made of the many attachments and modifications available, the drill press can be an exceptionally versatile tool. It is worthwhile for the shop foreman or superintendent occasionally to review the various types of

drill press equipment available, to make sure he is not missing something that would help him make fuller use of his drill presses.

Versatile Drill Chucks Available

Important advances have been made in standard drill chucks, the use of keyless chucks often speeding drill changes. Special drill chucks and tool holders are in use which supplement standard drill chucks to high advantage in many places. There is the quick-change drill chucks, in which a drill may be changed in a second with the spindle revolving. It being unnecessary to stop the machine, and there being no keys, collets or wrenches needed to make a drill change, time is saved and tools last longer. Such chucks have great value production-wise at drill presses where tool changes take place continually.

One remarkable development is a special device which imparts a slight reciprocating action to the drill at each revolution. Known as a drill chip breaker, it is located directly above the drill chuck. The value of the slight reciprocating action is particularly great in cases where deep holes are being drilled. In most conventional drilling, drill flutes are so nearly clogged by the continuous chip that it is difficult for coolant to reach down to the cutting edges. Where a drill chip breaker is employed, the slight lifting and falling action on the drill at each revolution terminates the chips and immediately starts new ones.

Thus the chips are made substantially uniform in size. Instead of whipping about on the drill above the work, they may be readily washed away by an adequate flow of coolant. And, each time the drill lifts slightly in the manner described, it allows coolant to go directly to the



THE MECHANISM ABOVE THE CHUCK on this drill press imparts a slight vertical reciprocation of the drill. This breaks up the chips and aids flow of coolant.

Drill Presses?

Part I

bottom of the hole and to the cutting edges of the drill. On deep drilling of conventional type, one must withdraw the drill from the hole a number of times to clear the drill flutes of chips and to adequately lubricate the drill point. Using a drill chip breaker, holes are often drilled as deep as 29 diameters of the drill at a single pass.


Special Drills Often Useful

Special cases often arise in which regular or standard drills should be laid aside in favor of special-purpose drills. Cases are on record where small holes drilled quite deep in very hard stock would permit drilling only a half-dozen holes or so between drill grinds. Often, substitution of drills more particularly designed for such work greatly stepped up the number of holes obtainable between grinds. Leading drill manufacturers often manufacture several special-purpose drills, and such possibilities should always be explored where out-of-the-ordinary drilling on a production job is at hand.

An interesting proposition to men who have a moderate amount of scrolling and design work to perform in light-gage metals is a special type of drill which makes its own starting hole for any interior design, after which the upper part of the tool may be used for working out the design. This drill press tool is made of high-speed steel.

Subland Tools Do Multiple Jobs

It is often desirable to use a combined drill and countersink, so holes may be drilled and countersunk in the same operation. Step drills are increasing in use for drilling holes having two or more diameters. With them the different diameters can be drilled with perfect concentricity, in one pass. Certain grinders are in use by means of which step drills may be made from standard drills. The cutting edges of the step drills may also be properly maintained on the same grinding machine.



A SPECIAL FORM cutter on this recessing tool is used for a necking operation on a small radio clutch gear. Plant-built clamping fixture is operated by an air cylinder.

Subland drills differ from ordinary step drills in that they do not have their different diameters on the same land, but have two separate lands running almost the full length of the flutes. Due to resharpening advantages, the subland drill often has a much longer working life.

Subland tools are obtainable which combine other operations with drilling. Some subland tools drill and ream at one pass. Others drill and counterbore. Some are made to core drill and ream. Recently, some subland tools have been made that drill and tap at one pass. The drilling portion of the tool in this case is necessarily smaller than the tapping portion, but has a diameter slightly greater than root diameter. Subland tools of spe-



DEBURRING HOLES in an aircraft forging on a drill press. Manipulating the knurled sleeve, as shown, retracts the deburring tool into its shank for insertion into the hole.

cial types are used in predrilled holes. One has been observed which reams, counterbores and forms a radius, all in one operation.

Carbide tipped drills, as well as solid carbide drills, are available from various leading drill manufacturers, and are finding extended drill press use. So-called hardsteel drills are very extensively used in drilling very hard materials. Use of these drills requires special drilling technique for good results. Operators using hardsteel drills must remember they differ completely from twist drills, and follow the instruction of the manufacturer touching their use. Long-length, straightshank high-speed drills are readily available, and used in specialized applications. Oil-feeding drills are chiefly used for drilling deep horizontal holes where gravity does not assist coolant to reach the drill point, but there are some cases in which they may well be used in a drill press.

One interesting proposition is use of form drills. Special form drills can be and have been made on order for drilling holes having irregular contours longitudinally. Examples are flat-bottomed holes, holes incorporating one or more radii, or holes incorporating one or more tapers in their length. Some firms have furnished such drills on special order, working directly from a submitted part print.

Tools Other Than Drills Are Available

Tools other than drills are often applied to drill presses with advantage. The adjustable hole cutter is an example. Some of these tools, incorporating an extended pilot to run into a preliminarily drilled hole, make finished cuts in boiler plate, pipe, plastics, hard fiber, stainless steels and other materials. The cutters are made adjustable so that a hole of any desired size may be cut. One line of such tools contains seven different models, covering an aggregate diameter range for holes from $\frac{5}{8}$ to 5 in. They have a thickness penetrating capacity ranging from the cutting of thin sheets to material an inch thick.

It quite often becomes important to stub a drill, to obtain maximum rigidity and reduce stress on the tool to a minimum. Yet such cases do not arise often enough in the small shop to justify carrying a wide assortment of stub drills. The solution generally lies in use of a good collet chuck which is either so designed that it will receive and efficiently grip on fluted portions of broken drills, or so it will receive a considerable part of the length of a drill in the collet shank. One collet chuck has a contracting member which is merely slitted through down one side. Thus it has a continuous wrap-around action which enables it to hold and grip securely on the fluted portion of broken drills. It is particularly good for use where one wishes to utilize broken drill portions as stub drills.

Where a collet chuck is to receive a considerable portion of the length of a drill, thereby allowing stubbing of the tool, it is necessary that the shank of the tool be hollow-bored. One make of collet chuck has its shank axially bored through the major portion of its length. This bore is tapped and fitted with a simple headless setscrew. The



THIS AIR-POWERED CLAMP is readily adjustable on the drill press column. The clamp permits rapid change of the wooden fixture to three different tapping positions and holds firmly in each position.

setscrew is so arranged that it can be adjusted to any selected position within the internally threaded shank. Thus, it forms a stop for the drill so the tool cannot drive back, and allows stubbing any drill to any desired degree.

Recessing tools are often applied to the drill press with profit, and may be modified in such a manner as to perform necking operations also when desired. A tool of this kind is usually built for a given job. They have been provided and used in holes as small as 5/16 in. diam. They often incorporate a ball bearing stop collar, which either strikes against the work or against a provided stop bushing. This limits the forward or downward movement of the leading part of the tool, while the following portion continues downward to drive and to laterally feed one or more tool bits which do the actual recessing or necking.

Deburring Is Done With The Drill Press

Rotary files have been used in the drill press chuck for different duties. One instance is use of a rotary clearance file for putting an accurate clearance break on punches. Rotary files have also been employed in the drill press for some kinds of deburring. There are also other ways of using the drill press as a deburring unit. Steel wool is made

up in ribbon form and wrapped around a spindle which can be held in the drill press chuck, the ribbon-form steel wool and the auxiliary spindle for this purpose being provided by a steel wool manufacturer. The steel wool ribbon is about 4 in. wide, and gets into irregular openings. As the pad becomes worn through long use, additional ribbon is wound in place. Winding is done in a direction opposite to that of rotation.



THIS LIGHT DRILL PRESS is equipped with a special dial feed for the workpieces, and an air feed for the dual spindle head.

One special tool applicable to the drill press has been developed especially for deburring the edges of holes which have been drilled, reamed, or bored in plastics or metal. It consists of an extended shaft which pilots in the hole being deburred, and of a cutting blade seated in and revolving with the shaft. The shaft is also provided with a knurled sleeve that may be slid back manually. This action retracts the cutting blade to a position inside the shaft for passing the tool through a hole when necessary. When the sleeve

is released, the cutting blade emerges to cutting position for removal of the burr.

An interesting arrangement which aids in deburring and certain other operations is use of an angle adaptor on light drill presses having a tubular column to support the drilling head and the motor. Using this angle adaptor, the entire drill head with its motor may be removed from the tubular column and remounted in such manner as to hold a tool with its axis at any desired angle and at any desired height. This greatly increases the versatility of a light drill press. Different drill presses of this general type are available but angular adaptors may be obtained for most standard types now in use.

Clamps Aid Productivity

The right kind of a clamp or vise often adds greatly to productivity of a drill press. There are clamps fitted with a handwheel-nut, operating a compound leverage through a drawscrew and clevis, by means of which one may obtain 8000 psi equalized, and many other types of mechanical clamps are available.


In many instances, especially on lighter drilling operations, use of compressed air clamps is found highly advantageous. The clamping element in such units is actuated by an air cylinder and piston. Such clamps are often made with a split-sleeve fitting which holds them to the column of drill presses of tubular column design. However, air clamps sometimes are mounted on special table fixtures where tables are tee-slotted. Foot control of such clamps is popular because it leaves both hands free to manipulate work.


Many clamping problems are often simplified by use of a combination drill press table and clamp. This is really a two-part circular drill table. It has a screw clamp by means of which the two table parts may be spread apart to receive a workpiece, then clamped together upon it. By use of this device, shaft or bar-type work may be readily drilled in the end, if it is not so long that its lower end interferes at the floor.

Lathe Tools Used in Milling Cutter

TWO-PASS milling of a turbine part with a conventional 14-blade cutter has been cut to one pass by use of a simple step fly-cutter at the Fitchburg, Mass., plant of General Electric. On this operation, use of a fly-cutter, which mounts four standard carboloy 1-in. shank carbide lathe tools in an old fly-cutting head, has also cut tool grinding and resetting costs.

Used in a Sellers horizontal mill, the step cutter removes ½ in. of material, the tools being set so that the cut is broken up into four ½-in. steps. No operating difficulty has been experienced in taking the entire cut in one pass, whereas the former cutter frequently stalled while taking the cut in two passes. The flycutter also produces a good finish and the tools need sharpening only once every 8 hr.





New Lathe Has T-Shaped Bed

JET engine blade shrouds, which are large diameter stainless steel rings, presented a machining problem at Pratt & Whitney Aircraft Div., United Aircraft Corp. About 2 years ago, P&W began investigations on more efficient methods for handling this work, some of which was done on vertical boring mills. The more common practice was to use raised- or gap-bed engine lathes.

Workpiece diameters required a large heavyduty type of lathe. However, the shrouds are short, thin-walled rings and the cuts to be made are relatively light and precise. For this reason, the long bed and high horsepower of a lathe large enough to handle the shroud diameters are not actually needed. Pratt & Whitney took up this question with Lodge & Shipley Co., Cincinnati. Together, they have developed a right-angle chucking lathe, especially designed for short, large diameter thin-walled work.

Bed Is T-Shaped

The new lathe has a T-shaped bed; that is, the section of the bed carrying the carriage is at right angles to the center line of the lathe. The carriage carries a cross slide which can move in a direction parallel to the lathe center line or at any angle to it. Thus, the machine can handle facing and straight or taper turning, or boring.

The machines made to date for Pratt & Whitney use a standard lathe headstock, a 25-in. heavy-duty type with an 11½-in. hole. This permits chucking of work pieces having a shaft or other extension, or work can simply be clamped to the faceplate. All other types of headstocks used with ordinary lathes can be furnished.

Current models of this new machine have a 37-in. faceplate and a maximum swing over the bed of 60 in. The travel of the facing carriage is 31 in. in one direction and 6 in. in the other. The travel of the compound rest is 12 in. forward and 4 in. back. The compound rest has a swivel range of 90°. Maximum depth of the work piece that can be handled is 12 in. from the faceplate.

The machine has 24 spindle speeds, ranging from 4 to 225 rpm. A maximum of 15 hp is delivered at 225 rpm. The carriage and compound rest have 55 speeds between 0.001 and 0.064 ipr, and the carriage can be rapid-traversed at 10 fpm.

Since the lathe was designed primarily for precise work on short, thin-walled sections of relatively large diameter and light weight, it embodies special characteristics for this class of work. Controls are sensitive and easy to operate. All operating functions are controlled from the apron. Since there is no long bed extending beyond the work piece, the work is extremely accessible for loading and unloading, measurements, and following the operation of the tool. The lathe was designed for use with carbide tools.

A distinct advantage of the T-bed lathe is the reduced floor space requirement. It occupies about half the space needed for a standard lathe having a 60-in. swing. Other features of the machine include independent control of facing and turning speeds in either direction and rapid traverse in either direction by light pressure on the apron control levers. The apron has a direct reading dial and counter for diameters, and a direct reading dial for lengths. The carriage has pads on each side for use with gage blocks. The spindle has a Warner electric brake and an electric jog button for use when changing spindle speeds.

Costs Less Than Straight Bed Lathe

It is expected that the new lathe will find extensive application as a general purpose lathe; it might well become the standard machine for thin-wall, short-length work of varying diameters. Contributing to this is the fact that the new lathe is less expensive than conventional straight-line lathes capable of handling equivalent diameters. It is also more accurate and faster in operation. The machine is less cumbersome, and loads and unloads with greater ease. It also offers more sensitive control and greater accessibility of controls to the operator.

WILLIAM LEDICAN

Anneal Ductile Iron

For Better Machinability





f

n

e

S

e

e

g

n

t

a

e

n

g

r

e-

1e

al

d

n-

er.

nd

r.

E

By J. F. KAHLES, Associate Professor of Metallurgy, and R. GOLD-HOFF, Graduate Student, University of Cincinnati, Cincinnati.

Adequate machinability and physical properties can be obtained in ductile iron without complete pearlite decomposition. Increased silicon content speeds carbide solution, while pearlite decomposition is mainly a function of manganese content. Small amounts of carbide can be tolerated if the matrix is basically ferrite.

A NNEALING characteristics of ductile irons are important in a commercial sense both to the manufacturer and user of ductile iron castings. For many years, vast emphasis has been placed upon high strength in cast irons. This approach has often led to the application of high strength irons where a lower strength iron with markedly improved machinability would be much more economical.

To correlate the influence of annealing on the physical properties and machinability, two basic types of ductile irons were considered:

(1) The carbidic irons, which are ductile irons of the usual chemistry. When this analysis is cast in thin sections such as found in thin plates and pipe fittings, the microstructure shows appreciable quantities of free iron carbide.

(2) The regular ductile irons having spheroidal carbon in a matrix of pearlite and ferrite. In the as-cast structures, the percentage of pearlite is greater than that of ferrite. Consequently, they are often referred to as pearlitic, in contrast with the carbidic irons.

The chemical analyses of materials used in this investigation are listed in Table I. Specimens 1A, 1B, 1C, 1D, and 1E are carbidic irons having the same base chemistry. A variation in ferro-silicon inoculation was used to provide data on the effect of varying silicon content. Specimens from No. 2 were taken from the thin section in a step bar.

Pearlitic specimens were obtained from three sources: No. 3 from the 1-in. section of a step bar; No. 4 from 30-in. lengths of 3-in. rounds; and No. 5 from a 6-in. square section. Originally, all of the above materials were in the ascast condition. It might be well to note that with heavy sections and in long lengths, there are variations in the percentages of structures.

The procedures used were dictated to some extent by current practices in ductile iron annealing. Briefly, most cycles now used involve a temperature of 1650° or 1700°F for about ½ hr followed by cooling to 1275°F and holding for about 5 hr.

Carbide Solution Times Vary

All of the carbidic iron specimens showed similar carbide decomposition characteristics. Carbide decomposition implies solution of the iron carbide in austenite and any attending graphitization. Fig. 1 shows the typical rate of carbide decomposition at temperatures of 1600°, 1700°, and 1800°F. Virtually complete decomposition is a matter of less than 1 hr, particularly at the higher temperatures. Complete carbide solution was reported to vary from 1½ to 7 hr, depending on the temperature and the chemical composition of the iron in question. Table II shows the effect of silicon content on the rate of carbide decomposition.

Variables besides the silicon content are present. The iron compositions involved are

Continued

fairly comparable, however, and the data are considered representative of at least a trend in the effect of silicon content on subsequent carbide decomposition. The resulting lower times of solution with increased silicon content follow typical white iron decomposition characteristics. Other compositional effects can probably be inferred from typical malleable and white iron behavior.

Appreciable amounts of carbide (even as low as 3 pct) in the microstructure are known to drastically decrease tool lift in pearlitic gray irons. This occurs because such structure is imbedded in a relatively hard pearlite matrix. In steel, the spheroidization basically provides a soft ferritic matrix for the carbide, increasing machinability. Residual amounts of carbide might then be tolerated in ductile irons with a basically ferritic matrix. The difference in cost between annealing times for complete carbide solution and decreased tool life from residual carbide might favor the latter.

Pearlite may be decomposed in one of two ways. First, specimens may be cooled from above the critical slowly through the critical temperature range, then held at a constant subcritical temperature for a definite length of

TABLE I							
CHE	MIC	AL A	ANA	ALYS	IS		
	Si	s	Mn	P	Ni	Mg	T.C.
(1) Carbidic Iron							
1A	3.12		0.52			0.082	3.5
1B	3.27	0.02	0.45		0.70	0.066	3.3
ID			0.45		0.70	0.066	
1E	3.98	0.02	0.43	0.084	0.70	0.066	3.30
(2) Carbidic Iron	2.98	0.010	0.61	0.06			
(3) Pearlite-Ferrite (Ductile Iron)	2.98	0.019	0.61	0.06	1.37	0.060	3.4
(4) Pearlite-Ferrite (Ductile Iron 3 in. Round)	2.33	0.010	0.40	0.052	1.55	0.076	3.5
(5) Pearlite-Ferrite (Ductile Iron 6 in. Square)	2.46	0.009	0.43	0.098	1.91	0.085	3.5

	Time for 95 pct Fe	3C Decomposition
Silicon, Pct	1700 °F (min)	1800 °F (min)
2.98 3.12	38 40	32
3.12 3.27 3.28 3.75	38 40 32 32 16 20	32 32 32 13

TABLE III
CHEMISTRY vs PEARLITE DECOMPOSITION

		Compo	Time to		
Ductile Irons	C	Si	Eff. Mn	P	Reach 15 pc Pearlite, hr
(3) Pearlite-Ferrite, step bar	3.42	2.98	0.55	0.08	8
3 in. round	3,52	2.46	0.40	0.052	4
6 in. square	3.58	2.33	0.37	0.096	2.8

TABLE IV AVERAGE PHYSICAL PROPERTIES

Amount of Pearlite, Pct	Tensile Strength, 1000 Psi	Yield Strength, 1000 Pai	Elong., Pct	R.A., Pet	Hardness Bhn
65 50 20 3	103 80 75 77	60 55 62	6.5 16.0 19.0 20.0	3.5 12.0 15.5 22.0	230 200 180 180

PEARLITE VS TOOL LIFE

TABLE V

			Relative Cu Fpm	tting Speed, , for
Structure, Pct Pearlite	Anneal Time at 1275 °F, hr	Bhn	40 min Tool Life	200 cu in Tool Life
85 (as east) 50	.75 1.5 5.0	230 200 180 180	325 405 520 550	320 420 565 600

time. Fig. 2 shows the rate of pearlite decomposition where the specimen has been held at 1750° for ½ hr, furnace cooled to 1275°F and held. An alternate procedure involves simply eliminating the austenitizing treatment and therefore heating to subcritical temperatures only. Fig. 3 shows this decomposition for the same chemical analysis used in Fig. 2.

In both cases, a rather rapid rate of pearlite decomposition was followed by much longer indicated times for the elimination of small amounts. All of the pearlitic irons noted in Table I showed comparable decomposition trends. Microstructures seemed equivalent except for the form of pearlite involved. The specimens decomposed on subcritical holding show more pearlite spheroidization when examined at magnifications on the order of 1000X. This leads to questioning the necessity of solution heat treatment in the austenite field, where small amounts of carbide cannot be decomposed anyway. The answer might lie in the determina-




FIG. 1—Typical decomposition of iron carbide in a carbidic iron at various temperatures. Chemistry of the iron was 3.27 Si, 0.02 S, 0.45 Mn, 0.084 P, 0.70 Ni, 0.066 Mg, and 3.34 T.C.




FIG. 2—Graph showing decomposition of pearlite in the pearlitic type of ductile iron, austenitized at 1750°F for 30 min and decomposed on continuous cooling to and holding at 1275°F. Chemical composition was 2.33 Si, 0.01 S, 0.40 Mn, 0.052 P, 1.55 Ni, 0.076 Mg, and 3.58 T.C. Hardness (Bhn) is shown at the points.




FIG. 3—Pearlite decomposition in a pearlitic ductile iron held at a subcritical temperature of 1275°F. Iron composition is the same as in Fig. 2, and Bhn is shown at the various points on the curve.

tion of physical properties obtained for each type of treatment.

Compositional effects have already been estimated by Rehder.^{1, 2} Information obtained here substantiates his findings, even though the data are not extensive. Apparently the Mn-S ratios or effective manganese contents in ductile irons are determining factors in rates of pearlite decomposition. Reference is made to Table III. Virtually all of the manganese is effective as an alloying element because ductile iron is practically sulfur-free. The implications of this fact are far reaching because of the enormous savings of manganese that may be achieved—a very vital factor in our metal economy.

As with other gray irons, there was a persistence of pearlite in areas where steadite was present. The amount of steadite present for these irons was small, as one might expect from the phosphorus present in these irons.


Machining data were not taken on all of the irons, but were directed primarily to the machining of material analysis No. 4. This ductile iron was vertically cast in 30-in. lengths, 3-in. rounds, which were convenient for the evaluation of machinability. Twenty-three bars were cast. Some of them were subsequently annealed at 1650°F, followed by a 1275°F treatment to give the various combinations of pearlite and ferrite shown in Fig. 4. Table IV lists physical properties for the No. 4 analysis, obtained from keel blocks accompanying the casting and annealing practice.

Turning tests were made on an infinite-variable-speed lathe under the following conditions: Feed, 0.011 ipr; depth of cut, 0.100 in.. with a carbide tipped tool (Kennametal K6). No back rake was set on the tool, and side rake was at a 6° angle; the end cutting edge angle was 6°, as were the side and end relief angles;

there was no side cutting edge angle.

The relation between tool life and cutting speed for the various annealed structures is shown in Figs. 5 and 6. In Fig. 5, the tool life in minutes required to produce 0.030 in. wear land on the flank of the carbide is plotted against cutting speed. In Fig. 6, the same data are replotted with tool life given in terms of cubic inches of metal removed instead of time.

Considerable improvement in tool life was ob-



C

FIG. 4—As-cast structure (A) containing about 65 pct pearlite; other micros show structures annealed at 1650°F for ½ hr and held at 1275°F for (B) ¾ hr, (C) 1½ hr, and (D) 5 hr. Sample B contains about 50 pct pearlite, C is about 20 pct pearlite and D has about 3 pct pearlite. Nital etch, 100X.





FIG. 5—Curves showing the effect of microstructure on tool life at varying cutting speeds, with tool life plotted against cutting speed. Sample A Sample A is as-cast, B is the 50 pct pearlite structure, C has 20 pct pearlite and D is 3 pct pearlite. Physical properties are those listed in Table IV, chemistry is No. 4 in Table 1.

tained by annealing so as to transform the structure from 65 pct pearlite to 20 pct pearlite. Only a small further improvement in tool life was obtained by continuing the annealing to provide 3 pct pearlite, as shown in Table V. It thus appears that the economical structure for machining in this particular case would be the 20 pct pearlite, which was held at 1275° for only 11/2 hr.



-The same data as in Fig. 5 replotted with tool life given in terms of cubic inches of metal removed instead of time.

Table IV shows rather conclusively that relatively high ductility is obtained before pearlite is completely removed. This work, along with other experience, indicates that in ductile irons one can rely to a great extent upon microstructure in predicting machinability. This correlation has been shown in other cast irons by Field and Stansbury.3

References

¹ J. E. Rehder, "An Introduction to the Annealing of Nodular

In Tron," AFS Reprint No. 50-17, 1950.

J. E. Rehder, "Effect of Mn-S Ratio on the Rate of Anneal of Black Heart Malleable," AFS Trans., vol. 58, 1948, p. 138.

M. Field and E. Stansbury, "Effect of Microstructure on Machinability of Cast Irons," ASME Trans., August 1947, p. 665.

U. S. Air Force Machinability Report; Curtiss-Wright Corp.,

New Blowpipe Drills Dynamite Holes Faster

BLOWPIPE that drills blast holes in hard, abrasive rocks and ores by burning a mixture of oxygen and either kerosene or fuel oil at 3000 to 4000°F has been introduced by The Linde Air Products Company, New York. According to this manufacturer, these burning gases are directed against the rock with supersonic velocity, and the resulting speed of pierc-



THE LINDE BLOWPIPE drills 11/8-in. blast holes in rock and hard, abrasive ores to depths of 5 ft or more. Fuel is burned within a combustion chamber in the head, and burning gases are directed against the rock through a nozzle with an expanding taper. Cooling water onters through the hose inlet and passes around the combustion chamber, leaving through the water-spray cap and turning to steam.

ing is much greater than that of older drilling methods. The new blowpipe drills 11/8-in. holes from any angle 5 ft deep in sandstone and feldspathic quartzite at a rate of 50 ft to 60 ft per hr and in granite at 22 ft to 25 ft per hr. Longer blowpipes are available on special order for piercing holes to depths of 7 ft to 9 ft or

The Linde blowpipe does not usually melt rock, but, instead, the intense heat it produces causes a continuous, localized thermal expansion. A rapid spalling or fragmenting of the material in the developing hole occurs. The steam, which is automatically generated from the blowpipe cooling water, together with combustion gases, flushes spallings from the hole.

The Linde FSJ-1, as this manual blowpipe is designated, has a sliding shield to protect the operator from exhausted steam and spallings. A hole-sizing shell is used to assure proper hole diameter. The blowpipe is 7 ft in length and weighs 17 lb, 7 oz. It is easily operated by one man, while holding it in his hands.

Oxygen requirements for the blowpipe are approximately 520 cu ft per hr at a blowpipe pressure of 150 lb per sq in. Fuel consumption is 28 lb, or about 4 gal per hr, at the same blowpipe pressure. Fifty gallons of cooling water is used per hr, at 50 psi.



PATCHES, COM-PLETE GLOVE sections and other rencovating materials are matched as closely as possible to each glove's original material of construction. Adhesives, resewing and stapling are used to affix patches to worn areas.

Industrial Glove Salvaging Cuts Replacements

By WALTER G. PATTON.

Detroit Editor, THE IRON AGE

Both large and small plants in the Detroit area are having gloves cleaned and repaired—sometimes as often as eight times. Renovation tends to reinforce gloves so that they wear better.

EVELOPMENT of special techniques for renovating worn and torn cloth and leather gloves has enabled the U.S. Industrial Glove Corp., Detroit, to offer a unique cleaning and repair service to a growing number of plants in the metalworking and other industrial fields. Large automotive plants, steel mills, foundries, steel fabricators, appliance manufacturers, office machine producers, glass plants, petroleum refineries, plating and metal finishing shops have also found the service attractive. It assures them a minimum outlay for new gloves, seven-day cleaning and repair, low flat rates regardless of volume of work and prompt pick-up and delivery by the salvaging company.

Experience has shown that firms which may not have attempted to salvage gloves before, or whose attempts have proved unsuccessful, are now reclaiming more than 80 pct of the gloves turned in by their workers. In recent months, still other factors have stimulated interest in the salvage plan. These are the increases in the price of new gloves and the growing threat of cotton and leather shortages. In addition to all kinds of gloves the company is extending its repair and renovation service to include any and all types of industrial protective apparel.

Both large and small plants have reported several examples of substantial savings since adopting this salvage plan. Over a period of months, a large automobile manufacturer has saved \$279,162 in the cost of gloves that would otherwise have been bought and used in 29 plants engaged in a wide variety of assembly and fabricating operations. More than a million gloves of all types were processed for this manufacturer during the period studied. Percentage of gloves salvaged was 83.9 pct. Complete results of the cost study are given in the accompanying table.

Another customer is now using renovated gloves on a line handling hot auto wheel rims. No reconditioning was previously attempted. Repaired gloves in this plant permit, on an average, eight wearings. Original cost of the gloves used is \$1.15 each, or \$2.20 a pair.

A typical example in the field of small manufacturing is that of a lock manufacturer whose glove requirements were excessive, even though he employed less than 300 people. Several unsuccessful attempts had been made through the conventional industrial laundering methods. However, most of the gloves were found to be useless because of shrinkage, wrinkles and holes found in them after cleaning. A recent test revealed a salvage of 92 pct at a saving of 48 pct on the replacement cost.

Successful salvage work such as these examples demonstrate results largely from the



CLOTH AND LEATHER gloves, typical of those received from metalworking and other industrial plants by U. S. Industrial Glove Corp. for cleaning and repairing.

special emphasis placed on restoring materials to their original efficiency. A variety of materials and repairing techniques, patterned after those used in the original manufacturing, are employed. Reconditioned items will withstand cutting oils, solvents, heat and water.

Salvaging operations begins when gloves are picked up on a regular basis at plants within a 300-mile radius of Detroit. Containers are provided at no extra cost or those selected by the customer may be used. All transportation costs are included in the service charge.

Gloves are first cleaned in the laundry. Ap-

ANALYSIS OF SALVAGE—"X" CORPORATION

		1	EATHER	GOODS					CLOTH C	COODS		
	1 Cleaned Only	2 Cleaned & Repaired	3 Scrap	4 Total	8 Pet Salvage	8 Pct Scrap	7 Cleaned Only	8 Cleaned & Repaired	9 Scrap	10 Total	11 Pet Salvage	12 Pct Scrap
Plant A. Plant B. Plant C. Plant D. Plant E.	8,068 48,634 1,706 43 701	463 45,150 2,710 32,458 480	2,854 63,747 1,771 975 122	11,385 157,531 6,187 33,476 1,303	0.75 0.60 0.72 0.97 0.91	0.25 0.40 0.28 0.03 0.09	15,041 57,295 656	538 62,179 320	3,228 39,873 654	18,807 159,347 1,630	0.83 0.75 0.60	0.17 0.25 0.40
Plant F Plant G Plant H Plant I	94,942 5,971 10 3,965	54,776 1,942 74 3,216	3,601 124 12 312	153,319 8,037 96 7,493	0.98 0.96 0.86 0.96	0.02 0.02 0.12 0.04	2,516	663	67	3,238	0.98	0.02
Plant J. Plant K. Plant L. Plant M. Plant M.	318 6,886 34,712 228 513	9,144 29,070 56 63	1,510 11,118 98	463 17.520 74,900 380 587	0.88 0.92 0.86 0.75 0.99	0.12 0.08 0.14 0.25 0.01	9 119,948 25,755 1,720 158	7.290 20,276 72 47	2,729 9,879 141	122 129,965 55,910 1,933 205	0.98 0.98 0.83 0.93 0.100	0.02 0.02 0.17 0.07
Plant O Plant P Plant Q	71,369	65,507 1,765	518 1,387	137,394 3,325	0.97	0.03	3,909 11,970	5,121 838	2,662 109	11,092 12,917	0.78	0.22
Plant 8	10,675 11,252 176 731	3,725 3,594 90 517	2,720 2,061 197 2,825	17,120 16,907 463 4,073	0.85 0.88 0.58 0.31	0.15 0.12 0.42 0.69	34,593 8,019 8 3,017	11,085 3,433 11 1,817	6,203 1,465 13 7,429	51,881 12,917 32 12,263	0.88 0.89 0.59 0.40	0.12 0.11 0.41 0.60
Plant V Plant W Plant X Plant Y	2,457 13,503 5,724	2,709 25,735 1,418 5,404	652 19,556 495 4,064	5,818 57,794 1,913 15,192	0.89 0.68 0.75 0.74	0.11 0.32 0.25 0.26	4,441 4,681	5,389 58 1,934	1,733 188 583	11,583 4,927 2,517	0.85 0.96 0.77	0.15 0.04 0.23
Plant Z. Plant AA. Plant BB.	836 302 38 30	2,249 179 55 68	450 27	3,535 508 93 100	0.88 0.95 1.00 0.98	0.12 0.05	830	104 72	18	950	0.98	0.02
	323.943	292,702	120,267	736.912	0.837	0.163	294,564	121,357	78,993	492,914	0.844	0.15

FECAPITULATION 1,032,566 Glove Total Gloves Scrapped 197,260 Pct of Salvage 83.9

As indicated in this analysis of the year-long salvaging service performed by U. S. Industrial Glove Corp. for one of the large automobile manufacturers, the percentage of gloves salvaged was 83.9 pct, representing a saving of \$279,162 in the cost of gloves that would otherwise have had to be bought and used.



THE SAME GLOVES after they have been washed, patched, resewn, restapled and otherwise renovated. They are brought back to their original centours and freed of wrinkles and creases by a reshaping process performed on steam-heated forms.

proved sanitizers are added for disinfecting purposes. After cleaning, gloves are tumbled and dried at high temperatures. Segregation in processing is always practiced so that all of each individual customer's work is kept together during the entire cleaning and repair operation.

After cleaning, the gloves are sorted into three groups: gloves requiring no repair work, gloves to be repaired and gloves to be scrapped.

Where the glove has been severely damaged, it may be necessary to reface it with a patch covering the palm area and a large portion of the inside finger area. Repairs readily withstand subsequent cleaning, as well as most conditions to which they are exposed in industrial use. Because repaired portions of gloves are

also reinforced areas, it has been found in many cases that a reconditioned glove will outlast a new glove.

The next step in the renovating process is reshaping the glove on a steamheated form which counteracts slight degrees of shrinkage and eliminates wrinkles and creases. Finally, reconditioned gloves are classified as to type and color, matched into pairs and packaged five to a bundle to provide convenient handling, storage and control for the customer.

Large quantities of heavy weight gloves, mitts and hand pads are handled. In most cases, these items are completely "torn down" and reassembled with new material. The reassembly is a repetition of the original manufacturing and a reconditioned hand pad is hardly distinguishable from a new one.

Besides its reconditioning service, the salvaging company is frequently called upon to act in an advisory capacity, performing "post mortems" on gloves to determine the reasons for excessive wear or failure. In general, inferior materials or faulty construction will be more apparent after a glove has once been used then when it is brand new.

Extended experience has demonstrated that practically all of the types of gloves used today in industrial plants can be repaired. This includes cotton flannel, terry cloth, and similar materials. Leather gloves, including chrome leather and horsehide designed for hard service in steel mills, foundries and auto body shops, are being repaired regularly.

According to reports from several users, renovated leather gloves that have been restored to their original shapes may actually be preferred by some workmen to a pair of new leather gloves that require breaking in.

To Reduce Polishing Costs, Polish Flat

AUTOMATIC polishing of steel in the flat, followed by phosphate coating and lubrication to protect the surface during the forming operation, has marked economic advantages over polishing of formed articles. At least a part of the automobile industry has turned to this method for bumpers and other parts. The steps in this procedure, including the cleaning prior to phosphating, were discussed by H. J. McVey and V. M. Darsey in a paper presented at the recent American Electroplaters' Society meeting in Boston.

Flat polishing is far less expensive than polishing on contoured parts, even with fully automatic equipment. An example was cited showing that contour polishing on one part had cost 9¢ per sq ft and was being replaced by flat polishing at a cost of 0.6¢ per sq ft.

Equipment is available for flat polishing steel to 8-12 microinches finish, consisting of abrasive belts with or without lubricants. After polishing, the parts are cleaned and pre-conditioned for a phosphate coating by spraying or brushing, both of which are better than immersion. The resultant coating should not increase the roughness of finely polished steel, and might even have a leveling or reduced roughness effect.

After cleaning, the phosphate coating is applied in the type suitable for the subsequent finishing operation. It might be heavy, for resistance to wear, or lighter for undercoats or bases for paints. It might also serve as an aid in drawing, in which case a lubricant would have to be used. Soap base material in aqueous medium is a satisfactory drawing lubricant, easy to remove before plating.




FIG. 1 — Charging end of one of the three new wire patenting furnaces at Macwhyte Co. The unit is free standing, which provides a ventilated hearth.

Patenting Furnace Features

Lightweight Construction

By W. R. Bloxdorf Metallurgist, and A. M. Naysmith Plant Engineer, Macwhyte Co., Kenosha, Wis.

Increased fuel economy and reduced operating costs are achieved by a new automatic wire and wire rod patenting furnace. Proper design, coupled with use of lightweight insulating firebrick, improves efficiency of the process, gives greater uniformity.

As part of a program aimed toward modernization of heat treat facilities, three newly-designed wire patenting furnaces were installed at the wire mill of the Macwhyte Co., Kenosha, Wis. The new furnaces have been in successful operation on a continuous 24-hr basis for about a year, with regular shutdowns on Sundays and holidays. These furnaces are used in the patenting treatment on medium and high carbon steel round wire and wire rod, ranging from 3/32 to 9/32 in. in diam.

Patenting is a specialized form of heat treatment for obtaining structural characteristics necessary for subsequent cold drawing of such products as rope and spring wires and tire bead wire. The treatment is continuous, with single strands of the wire or rod pulled through the furnace at various speeds consistent with their size. Temperatures employed in patenting vary from around 1650° to 1850° F, depending upon steel composition and ultimate physical properties de-

sired in the finished cold drawn product. Most important, the furnace must maintain uniform temperature throughout the greatest possible length of the heating chamber.

A wide variety of sizes and compositions is encountered, and it often becomes necessary to change abruptly from one size and grade of steel to another. This may also require immediate changes in furnace conditions. For this reason, it is highly advantageous if the furnace temperature can be quickly raised or lowered to new levels with the shortest possible time lag.

The use of lightweight insulating firebrick in the construction of wire and rod patenting furnaces has proven to be entirely suitable. Through use of these materials, a great reduction in weight of equipment has been realized. This in turn lowers appreciably the heat storage value required for any one temperature in a given

The new furnaces (Fig. 1) and the ones which

they replaced are identical in only two respects. The heating chambers of both are of the openfired type and of the same overall hearth length and width, namely, 50 ft and 4 ft respectively. They differ widely in such features as general construction, combustion system, mode of temperature control, and capacity.

The old furnaces were built upon a solid foundation consisting of concrete, red brick, and sand. The arch, walls, and hearth sections representing the hot faces were of ordinary firebrick construction having a thickness of approx. 9 in. Surrounding these sections was a 9-in. thick solid layer of brick of relatively low insulating value. All of this brickwork was encased in the conventional manner by a steel plate shell.

In the construction of the new furnaces, lightweight insulating firebrick was used throughout. In addition, the solid foundation in direct contact with the earth was eliminated. The hot faces of the new furnaces represented by the arch, walls, and hearth are constructed with Babcock & Wilcox K-23 insulating firebrick. This structure has a nominal thickness of 9 in., as shown in Fig. 2. Surrounding the 9-in. layer of K-23 is a 41/2-in. thick layer of B & W insulating firebrick K-16. In addition, a 31/2-in. layer of refractory castable, B & W Kaocast, is placed upon the hearth or furnace floor. Instead of a solid foundation, the furnace bottom rests upon a steel floor 18 in. from the ground, thereby providing a so-called ventilated hearth.

Furnaces Propane Fired

The combustion system of the old furnaces utilized manufactured gas having a heating value of 520 BTU per cu ft. This was supplied to the burners under a pressure of about 10 psi. In a burner installation such as this, the energy of the gas was used in providing the air needed for combustion. The new furnaces employ entirely a low pressure combustion system with low pressure propane gas as fuel. The air required for complete and satisfactory combustion is supplied at 1 psi pressure by a McKee centrifugal pressure blower to each of the

furnace zones.

There are four distinct and separate temperature zones in the 50-ft furnaces. All employ McKee-Eclipse proportioning burners supplied by Eclipse Fuel Engineering Co., Rockford, Ill. The capacities of the burners were selected upon a consideration of the heating load of the furnace and of the desirability of maintaining a uniform temperature throughout the furnace length.

Control of temperature throughout the old 50-ft furnaces was manual. Assisting such control was a 3-point recording pyrometer employing chromelalumel thermocouples at three points in the furnace. The new furnaces are operated under automatic temperature control entirely. Such control in each of the four zones is effected by a Wheelco Xactline Capacitrol.

The Wheelco Capacitrols serve to operate Barber-Colman motors which actuate variable port North American air valves, thereby supplying the air necessary for the fuel demand. A second thermocouple is used in each of the four zones for the purpose of temperature recording. Such recording is accomplished by a Leeds and Northrup Micromax continuous recorder.

Higher Production With Less Fuel


Insofar as steel heating capacity is concerned, the old furnaces were able to treat approx. 1000 lb per hr. While the new furnaces were designed to treat 2500 lb per hr, they have been found capable of satisfactorily treating from 2700 to 4000 lb per hr and are doing so regularly.

Very pronounced increase in fuel economy has also been effected. With the old furnaces, fuel consumption averaged around 1000 Btu per lb of steel treated at a rate of 1000 lb per hr at 1750°F. At the same temperature, the new furnaces satisfactorily treat 2500 to 3000 lb per hr with a fuel consumption of 600 Btu per lb. Overall fuel efficiencies of the old furnaces ranged from 20 to 27 pct. At a production rate equal to 105 pct of design capacity, the new furnaces show an overall fuel efficiency of 42 to 47 pct.

Flexibility in temperature control is desirable in a patenting furnace. The use of lightweight insulating firebrick in the construction of the present furnaces has enabled a true realization of this feature. For example, at a temperature of 1780°F with a heating load of 3000 lb per hr, it is possible to lower the furnace temperature 100°F and obtain temperature uniformity within a 5 to 10 min period of time. Temperatures can be raised an equivalent amount in the same

period.

Another feature in favor of the use of insulating firebrick in wire and rod patenting furnaces is the relative ease with which the furnace can be brought to operating temperature. It required from 2 to 4 days to reach the desired temperature and attain temperature uniformity in the old furnaces. In the new furnaces, a temperature of 1750° to 1800°F can. be reached in from 31/2 to 4 hr, starting at about 200°F.



9 in. of B. a.W. K-23 insulating fire brick

4 in of B. a.W. K-16 insulating fire brick

FIG. 2—End section through one of the 50-ft steel wire or rod patenting furnaces. Use of lightweight B&W insulating firebrick is shown.



SPECIAL DESIGN
pay-off and tapered
drum for easy removal of drawn coils
are features of new
Aetna - Standard
horizontal bull block.

Pla

C

capa

Proc

be d

plete

which

star

piece

toolr tion powd

SKF

incen

more

grant to 28

perso

with

ers, (open 1951. works

Dece

Pointing, Shearing Part of Continuous Cycle of New Bull Block

Pointing and shearing done continuously while the block is in motion contribute to high production in drawing copper tubing on a new horizontal bull block. Recently announced by the Aetna-Standard Engineering Co., Youngstown, the bull block eliminates the need for starting or stopping until a draw is complete, by including a push pointer and shear as an integral part of the unit.

The need for coil pushoff is eliminated in the new bull block by use of a tapered drum which enables the operator to unload the coil with ease when a draw is completed. Another feature is a special coil pay-off integral with the bull block. Drawing can be done from either straight tubing or coils.

The bull block's auxiliary equipment includes a lubricating unit for internal and external lubrication of tube. A conically-shaped lubricating insert, placed in the tube before drawing begins, is used to inject drawing lubricant inside the tube during operation.

After insertion of the floating plug into the tube, it is passed through the shear and gripped by the hydraulic push pointer. By push button

control, the pointer is operated to force the tube end through the die to the gripper jaws.


The crop shear, used to cut the trailing end of the tube near the end of the draw, operates while the draw is in progress. It is not necessary to stop the draw to shear off the end, as is the case with conventional equipment. Dynamic braking of the main drive motor stops the block smoothly and quickly when the end of the tube is pulled through the die, completing the draw.

Aetna-Standard's demonstration machine is rated at 20,000 lb pull, though other ratings will be available. Speed range is adjustable between 150 and 600 fpm. The main motor can operate on standard dc shop current, being rated at 100/125 hp, 230 v.


A typical drawing cycle produces tubing of % in. OD with a 0.035-in. wall and from 1%-in. OD, 0.070-in. wall tubing in 5 passes. The maximum size tubing drawn to date on this unit had a 1%-in. OD and 0.090-in. wall.

The demonstration machine was fitted with a 48-in. diam drum having a 40-in. face. It can accommodate up to a 54-in. diam drum. The unit includes a hydraulically movable drum guard.

SHEAR and hydraulic push pointer are integral part of new bull block. Both can operate while drum is in motion, eliminating need for stopping or starting until drawing cycle is completed.



THE IRON AGE



Crucible Signs Union Shop

Pittsburgh — Crucible Steel Co. of America has signed the first union shop contract with the United Steelworkers (CIO) in current negotiations. The agreement, covering 11,500 employees, also includes the standard 16¢-per-hour average increase accepted by other steel producers.

Crucible is not the first company in basic steel to agree to the union shop, however, When Kaiser Steel Co. signed its first contract with the USW, the union shop was part of the agreement.

Plan to Double Capacity

Chicago — Present production capacity of the Powdered Metal Products Corp. of America will be doubled when a new addition to its Belmont Ave. plant is completed. The plant addition, on which construction has been started, will house presses for piece part production and provide toolroom facilities for the production of the metal dies required in powdered metal fabrication.

SKF Grants Voluntary Wage Rise

Philadelphia—A voluntary pay rise averaging 5½¢ an hr for non-incentive workers and slightly more for incentive employees was granted by SKF Industries, Inc., to 2800 of its Philadelphia plant personnel. Under its contract with Local 2898, United Steelworkers, CIO, SKF was not required to open negotiations until August, 1951. SKF has hired 20 pet more workers in the past 6 months because of increased demand.

Materials Restrictions Hit Detroit

But auto makers fight to assure supplies . . . Procurement is an old problem to them . . . Steel seen toughest . . . but non-ferrous metals are causing worry, too—By Walter Patton.

Detroit—Even without the threat of a controlled materials plan the production outlook for the automobile industry remains uncertain. While it can be predicted that the auto industry will aggressively pursue all available materials and supplies, it is still uncertain whether the companies can keep their schedules up to 120,000 units per week after January.

There have already been substantial cuts in auto production. Under the terms of its new \$25 million loan, Kaiser-Frazer will reduce its schedules to 600 units per day. This compares with a peak of 1400 in October. Ford has reduced its output by 80,000 units. Reductions are set for January and February.

Independents Hit Hardest

Independent auto producers have been hardest hit. One manufacturer, for example, has reduced its auto output 25 pct. There has been no planned switch from appliances to refrigerators or vice versa by the industry, except where available materials have dictated such a change.

There appears to be some sharp difference of opinion within the industry as to government policy of cutting car schedules by reducing available raw materials rather than making a direct cut in auto production. Generally speaking, the independent car makers favor an across-the-board reduction. The big three, however, with their greater resources and more effective bargaining power, naturally prefer the elbow room they have under the present method of indirect cutbacks.

Essential or Nonessential

Informed Detroit sources believe that eventually—and probably in the not too distant future
—production throughout the U. S.
will have to be broken down into
essential vs. nonessential items.
When that occurs, the auto industry will make a strong effort to get
a large part of its present output
earmarked as "essential transportation."

At the moment, steel is definitely the tightest item on the material list. Aluminum will undoubtedly be a serious factor for every car maker by the end of the first quarter. However, following anticipated reductions in January and February schedules for lack of steel, the nonferrous reductions may not prove to be the controlling factor determining the amount of auto production. A serious consequence of the aluminum order is that unless modified it will hit some producers—Cadillac and Oldsmobile, for example-particularly hard. However, GM is believed to have taken some steps to parry this blow by switching aluminum from its refrigerator division to its car, truck and bus divisions

A substantial quantity of Euro-

INDUSTRIAL SHORTS

ACQUISITION—The Kollsman Div. of the Square D Co., Elmhurst, N. Y., manufacturers of aircraft instruments, has been acquired by the STANDARD COIL PRODUCTS CO., INC., Chicago. The purchase price is believed to be around \$5 million. A subsidiary of Standard Coil will take over the Kollsman business with Victor E. Garbonara as president.

TEST FACILITIES—New laboratory test facilities have been completed by AEROL CO., INC., Burbank, Calif. The test equipment was designed to speed the resolution of design problems posed by widely-different wheel and caster requirements of industry.

TOOL ADVISER—Herbert L. Tigges, president of the American Society of Tool Engineers and executive vice-president of Baker Bros., Toledo, has been appointed adviser and consultant on machine toools to the NATIONAL PRODUCTION AUTHORITY in Washington.

MOVES PLANT—The Dallett Co. of Philadelphia, purchased in 1947 by the REED ROLLER BIT CO., has been moved to the Cleco Div. plant in Houston, where they will produce Dallett tools and accessories.

IN BUSINESS—Service for impregnated hi-pressure test castings is being done by the newly organized SEAL CAST CO., INC., at 1145 North Mill St., Reading, Pa.

GROUP LEADERS—Thomas H. Chilton, technical director of the development engineering division of E. I. du Pont de Nemours & Co., has been elected president of the AMERICAN INSTITUTE OF CHEMICAL ENGINEERS. William I. Burt, vice-president of the B. F. Goodrich Chemical Co., was named vice-president. Stephen L. Tyler and C. R. De Long were reelected secretary and treasurer respectively.

DISTRICT OFFICERS — The Capitol District chapter of the INSTITUTE OF SCRAP IRON & STEEL has elected Leonard C. Klein of Joseph C. Klein, Inc., Albany, as president. The new vice-president is Herman Garbowitz of Samuel Garbowitz & Son, Schenectady.

SELLS BUILDING — Arrangements have been made by FOL-LANSBEE STEEL CORP. for the sale of its general office and warehouse building in Pittsburgh to the Urban Redevelopment Authority. Negotiations are under way for purchase of another building in Pittsburgh.

INCREASES CAPACITY — A warehouse building adjacent to its Pittsburgh warehouse plant has been acquired by FORT DUQUESNE STEEL CO. An additional coil slitting line will be installed within the next 60 days.

SOUTHERN PLANT — Work has begun on a new plant in Birmingham by GENERAL AMERICAN TRANSPORTATION CORP., Chicago, to do various types of fabricating. It is expected to be in operation during the third quarter of 1951.

EXPANDING — Expansion has been started on the oxygen producing plant of the LINDE AIR PRODUCTS CO. at East Chicago, Ind. This plant supplies oxygen principally to the steel and metalworking industry in a large portion of the Middle West.

SALES AGENT — Roots-Connersville Blower Corp., Connersville, Ind., has appointed the KOERNER ENGINEERING & SUPPLY CO., Portland, Ore., as exclusive sales agents for all R-C products in the states of Oregon and Washington.

ADDITION—Construction of a second \$250,000 addition to the plant of the ANNISTON FOUNDRY CO., Anniston, Ala., manufacturers of soil pipe, has begun.

pean steel is now coming into Detroit. Some of this steel, at least, is being bought at prices reasonably close to Pittsburgh quotations. All of the European sheet, however, is handmill steel and its application to deep drawn parts is not practical.

th

si

st

de

m

ja

ar

fo

de

ch

eq

to

E

re

SE

N

it

tie

tu

th

ta

its

th

as

ma

re

se

on

a

ne

th

sti

tal

Bi

tio

ac

tha

to

rie

sh

eq

De

The continued eagerness of the industry to obtain more steel is illustrated by these facts: (1) An estimated 30 pct or more of the steel being used by the auto industry today is obtained by conversion, (2) a substantial percentage of this steel costs \$200 or more and the price is increasing constantly as scrap prices continue to soar.

Washington and Steel

This week General Motors made its second substantial investment in new capacity. GM has agreed to loan Jones and Laughlin \$28 million for an expansion of its Otis Works in Cleveland. GM will take 20,000 tons of steel per month from J & L as long as the company continues to operate full blast. GM had previously made a substantial investment in McLouth Steel Corp. in order to assure itself an adequate supply of steel.

It can be counted on that the auto industry will keep rolling full blast until production is cut back, either by orders out of Washington or a lack of parts or raw materials. The possibility that sharp reductions in nickel will force many changes in plating is already present. Threatened cutbacks in copper and tin are not being overlooked. However, the real immediate threats to auto output continue to be Washington and steel.

FTC Wins Campaign Against Corn Items Basing Point Pricing

Washington—The Federal Trade Commission last week announced final victory in its 3½-year campaign against basing-point pricing in the corn products industry.

The prohibition against the controversial pricing practices, which was recommended by an FTC trial examiner on last Sept. 29, became the official decision of the commission when it was neither appealed, stayed, nor placed on the FTC's docket for review.

e-

st,

m-

ta-

et.

its

he

An

he

in-

on-

nt-

ore

on-

to

ade

ent

l to

nil-

tis

ake

om

on-

GM

tial

rp.

de-

the

ing

cut

of

or

hat

will

g is

eut-

not

the

out-

and

ng

ade

ced

am-

eing

eon-

nich

rial

AGE

The final order prohibits nine manufacturers of corn derivatives and seven of their sales subsidjaries from entering into or cooperating in any agreement to fix prices for their products. It forbids the use of basing-point and zone systems of pricing when they are the result of any planned common course of action, agreement, understanding, combination or conspiracy among the firms named.

Farm Equipment Makers See Steel Pinch

Formerly favored free market distribution . . . Faster defense spending changing their minds . . . Sentiment swinging toward protection by formal allocation system—By Gene Beaudet.

Chicago — Reverses in Korea and the President's recent request for an additional \$17.8 billion for defense purposes are causing a change of sentiment among farm equipment manufacturers. Prior to the Korean setback the Farm Equipment Institute presented a report to Commerce Secretary Sawyer and William Harrison, NPA administrator, stating that it favored free market distribution of materials to all manufacturers in the industry.

Informed observers state that the report was based on the expectation of a slow mobilization program taking several years to reach its peak. While it was hedged with the request that the industry be assured an adequate supply of material if military requirements reached a point where they would seriously affect the civilian economy, it did not ask to be put under a system of allocations to receive needed materials. It was one of the few basic industries willing to stick it out in a free market and take its chances.

Bigger Farm Program

Now, however, with mobilization in all likelihood to be greatly accelerated, the feeling is growing that an allocation program similar to those for freight cars, lake carriers and the warehouse industry, should be set up to insure farm equipment manufacturers of an adequate supply of steel products.

Increased domestic crop requirements along with urgent foreign needs is expected by informed sources to result in a farm program for 1951 which will exceed that of 1950. In order that such a program can be carried out, farm implement production during the coming year must continue at least at the same rate as that of this past year.

Furthermore, as the defense program gains momentum, more and more workers will be leaving the farms for higher paying jobs



"Since you do mental work at the office all day, a little physical work will relax you."

in industrial areas. Farm labor supply will also be affected by the expansion of the armed forces. This will result in a greater need for labor saving farm machinery.

According to figures compiled by the Institute, 2.76 million tons of steel will be needed during 1951 by farm implement makers and their suppliers to operate at the same level as this past year. This comes to around 230,000 tons a month. By way of comparison, current allocations to freight car builders provide a tonnage of about 310,000 tons a month for the first quarter of 1951, or about 80,000 tons a month more than that needed by farm equipment manufacturers and suppliers to maintain current rates of production. There is little doubt that farm implements are as vital to the national defense and economy as other industries already on an allocation basis.

Getting Less Steel

Without formal allocation, it doesn't seem likely that farm equipment manufacturers will receive the steel tonnages needed to maintain the 1950 level of production during the coming year. Like most other civilian consumers of steel they are suffering cutbacks due to demands of the allocation programs and rated DO orders.

Many companies were dropped out of January mill delivery schedules entirely. A number of smaller companies are reported faced with the possibility of shutdowns due to lack of steel. Others have been informed that they will receive further cutbacks in the second quarter of next year. With more government funds slated to go into defense supporting industries and DO ratings the amount of free steel will become smaller and smaller.

For these reasons those close to the situation are of the opinion that members of the farm equipment industry are revising their present sentiments concerning free distribution of materials and are becoming more desirous of the protection offered by an allocation program.



MIGHTY MITE: Reportedly the world's most powerful, an electrically powered industrial tractor pulls two Diesel locomotives weighing half a million pounds. Only 10 ft long and tipping the scales at a mere 6 tons, the tractor was made by Automatic Transportation Co.

Wage-Price Control Orders Readied for Quick Application

Washington—Way was cleared last week for fast imposition of price-wage controls if sudden action on the part of the government became necessary.

Price Administrator DiSalle said that while orders are in preparation for necessary use, the government did not plan to impose any price-wage freezes in the immediate future.

He also warned that manufacturers should not boost prices in order to get set for a possible price freeze. If they do, he said, they should be prepared for a rollback when and if price ceilings are proposed.

Dangers of Controls

The new price administrator's statements came on the heels of a 10,000-word report to the White House and Congress in which Attorney General McGrath warned the government to go easy in the matter of controls. Too many, he said, would tend to kill off a free and competitive economy.

The Justice Dept. head recommended that blanket controls should be avoided if possible and that any price controls should be limited to shortage areas if possible. He also recommended that the government should try to spread its defense contracts among as many manufacturers as possible to lighten the impact of defense orders on small business.

At the same time, he advised the

government to go slow in approving voluntary agreements between producers—on the grounds that these tended to encourage monopolies. Another recommendation was that the government should avoid as much as possible the employment of people on a dollar-ayear basis lest "special interests" receive undue preference.

Ireland's Sole Steelmaking Plant Now Plans Sheet Output

Cork, Ireland — Irish industry now has a steel backbone that is getting stiffer. The government-sponsored Irish Steel Holdings Ltd. steel works on the island of Haulbowline, in Cork harbor, the only steelmaker and roller in Ireland, has had a flying start during the current world-wide shortage of steel. It now plans expansion to produce steel sheets.

Trains Local Men

In the few years of its operation it has trained local men to become steelworkers and now "quality" is a company slogan. Its 35-ton openhearth and rolling mills produce merchant bars to British Standard Specifications and output has been boosted to meet Ireland's full demand—while competing with foreign steel.

The plant uses 100 pct cold scrap charges, obtaining limestone, dolomite, fluorspar and coke from domestic sources. It has eliminated cogging and blooming mills by teeming small ingots for direct rolling into merchant bars.

National Steel to Put Largest Iron Ore Carrier on Great Lakes

Pittsburgh—National Steel Corp. will build the largest ore-carrying ship ever to ply the Great Lakes—capable of transporting 21,000 gross tons—to help meet increased iron ore requirements caused by the company's expansion of steel-making capacity.

co

m

m

mi

70

su

th

W

an

in

ex

ge

of

he

ca

88

or

To

m

W

pr

Tr

mi

Ri

st

ra

tr

th

pl

80

ea

on

su

th

re

B

du

at

ur

co

CO

D

The company said the ore carrier will be almost twice the average size of the American iron ore ships now operating on the Lakes. National has seven ore ships.

National Steel has increased its ingot capacity by 600,000 tons since the war ended, and has plans under way to add another 750,000 tons by early 1952, when its capacity will total 5,250,000 tons.

This expansion program includes a new 480,000 ton per year blast furnace at Great Lakes Steel Corp., additional pig iron facilities at Weirton Steel Co., and construction and enlargement of openhearth furnaces at both plants.

Launching-Summer, '51

Construction of the big ship will begin in August, 1951, at the Lorain, Ohio, yard of the American Shipbuilding Co. Launching is scheduled for the summer of 1952. Overall length of the vessel will be 690 ft with a beam of 70 ft and a molded depth of 37 ft.

Displacement at a draft of 24 ft, the maximum now available in existing channels, will be 20,340 gross tons, including cargo, fuel and stores. Approximately 19,500 gross tons will be iron ore cargo. Should the available draft be increased to 25 ft 6 in. or more, the ship's cargo capacity would be increased to approximately 21,000 gross tons.

Two coal-fired water tube boilers equipped with spreader-type stokers and a geared steam turbine will generate more than 7000 horsepower. At maximum draft the ship's speed will be more than 16 mph. In an average season the ore carrier would make 46 round trips. About 7500 tons of steel will be required to build the boat.

Cobalt Cutback May Turn U.S. to Remote Fields of Brazil

es

orp.

ying es—

,000

ased

l by

teel-

car-

ver-

ore

kes.

d its

tons

lans

,000

ca-

in-

year

Steel

ities

ruc-

pen-

will

the

neri-

hing

r of

essel

70 ft

4 ft.

ex-

,340

fuel

,500

rgo.

e in-

, the

be

1,000

boil-

type

tur-

7000

Iraft

than

the

ound

will

AGE

8.

Transport problems stall exploitation . . . Plans dropped after war.

Sao Paulo—The rich but remote cobalt fields of Brazil may be remembered once again by American makers of high-speed steels. Their memory has been nudged by the 70 pct cutback in the civilian consumption of cobalt. Talk of using these deposits developed during World War II but with war's end and availability of more easily transported Belgian Congo cobalt interest went flat.

That the U. S. was thinking of exploiting these fields in emergency is proven by the visit of Morris Llewellyn Cooke, who headed the World War II Technical Mission to this country. He said that the oxidized nickel-cobalt ore deposits at Sao Joao dos Tocantins, in mid-Brazil near the mouth of the Tocantins River, were "among the important known properties of this nature in the world."

Transportation Problems

This is the drawback: A 1000-mile tributary to the Amazon River, the Tocantins is an unruly stream, made unnavigable by sheer rapids. Ore boats cannot make the trip—and no railroad runs into the wild territory. While full exploitation must await another era, some pickings can be gotten to ease the cobalt shortage.

Mr. Cooke, in his book, "Brazil on the March," published in 1944, suggested mule hauling through the jungle and concentration or reduction of the ore at the mine. But mule transport cannot lead to worthwhile exploitation and reduction is difficult because firewood and charcoal fuels available at the site are inadequate.

The state of Minas Gerais has a nickel-cobalt mine—and it has a plant run by electric power. But, unluckily, the ore has a nickel content of a scant 4 to 5 pct. Mr. Cooke reported that 50,000 tons of cobalt ore was available without counting unestimated reserves. If



KING SIZE: That nodular iron castings are getting heavier is shown by this pump case and cover, cast at the Farrel-Birmingham foundry, Derby, Conn. Weight of the two castings is 8314 lb.

crisis presses, said Mr. Cooke, "possibly 20 tons a day" could be mined and flown out by planes.

Also in 1944, William T. Pecora, Dept. of Interior, reported that the size and richness of the ore fields warranted spending large sums to establish a local industry. The squeeze on cobalt is on and the U. S. may be forced into an expensive decision. Right now the ore is so remote that Brazil itself must export all of its cobalt.

Carnegie's South and Gary Works Set Record in November

Chicago—The South and Gary works of Carnegie-Illinois Steel Corp., U. S. Steel subsidiary, broke all production records during November despite unfavorable weather and a 30-day work month. Previous records were all set during 31-day work months.

South Works Leads

South Works led with a new record of 355,909 openhearth ingot tons produced during November compared to 354,246 ingot tons for October. Total steel products shipped in November was 319,531 tons, bettering a previous record of 318,847 tons, set in March, 1949.

No. 1 openhearth at Gary works broke a 24-year record with 124,-263 ingot tons. The old record was set in March, 1926, with 123,705 tons. No. 5 openhearth produced 87,597 tons during November to top its December, 1949, high of 86,674 tons.

RFC Grants \$25 Million Loan To K-F—Complete with Strings

Asks car output cut . . . Hold price line . . . Go after defense orders

Washington — The Reconstruction Finance Corp. has agreed to lend the Kaiser-Frazer Corp. \$25 million for working capital and plant expansion. But the 11-month loan has as many strings as a maypole.

K-F had applied for a loan of \$38 million, RFC officials said. In granting the revamped request for \$25 million, RFC specified that the firm must cut output of autos to 600 units per day by Jan. 1.

Autos Are Security

In addition, the company may not increase its prices above the Dec. 1 level without the government's permission and must also make every effort to obtain war contracts and give those priority over automobile production.

The loan is to be secured by new Kaisers and Henry Js stored in bonded warehouses. RFC officials said about 13,000 Kaisers and about the same number of Henry Js would be security.

As the cars are withdrawn from storage, the entire wholesale price is to be paid to RFC. Of that sum, 90 pct will go toward repayment of the loan and 10 pct will go toward repayment of a \$10 million revolving loan previously granted.

The loan will be used in part to help finance an expansion program which will include a new plant at San Francisco for "the manufacture of products in the military classified list," Henry J. Kaiser, president of the firm, stated. Kaiser said he also plans to reopen two West Coast shipyards and to expand aluminum, cement, steel and gypsum capacity.

The new loan is to be repaid by Nov. 7, 1951.

Carnegie Steel to Install New Ferromanganese Gas Cleaner

Pittsburgh — Carnegie-Illinois Steel Corp. will install a new ferromanganese gas-cleaning system at its Duquesne Works to eliminate dust discharged from the furnace stacks and recover important ferromanganese ore.

A 220-foot bleeder stack to regulate pressure of ferromanganese gas from the furnaces will be placed in operation soon. It will automatically control and burn ferromanganese gas not burned in the plant's boiler houses.

The gas-cleaning system, designed by U. S. Steel engineers, will be the first of its kind ever built. Smoke and dust will be removed from the ferromanganese gas. The facilities will occupy a half-acre of ground near the plant's blast furnaces.

Major \$228 Million Expansion Set by J&L

Will add 1.5 million tons to ingot capacity . . . Most goes to Pittsburgh works, balance to Otis, Cleveland . . . Program to be completed by Jan. 1952 . . . GM lends \$28 million.

Pittsburgh—Jones & Laughlin Steel Corp. will spend \$228 million in the next 2 years to complete its postwar expansion program. It will bring total expenditures since 1946 to \$375 million.

Enlarged and accelerated for defense reasons, the program will increase the company's ingot capacity by 1,550,000 tons to 6,400,000 tons by January, 1952. Finished steel capacity will go up in proportion—from 3,500,000 tons to 4,600,000 tons

Finish by Early '52

At the Pittsburgh works, where 11 openhearth furnaces are now being installed (original plans called for six) steelmaking capacity will increase by approximately 1,200,000 tons. This takes into consideration the 780,000 tons of obsolete openhearth, bessemer and duplex steelmaking capacity being replaced. Balance of the ingot capacity increase will be installed at the Otis works, Cleveland.

Approximately one-third of the new Pittsburgh works capacity

will be available by next August, the balance in January 1952. The Otis program is scheduled for completion by January 1952.

A

n

h

p

n

is

G

0

N

2

8

u

N

b

b

c

f

5

У

q

b

E

8

E

t

t

The company has received a certificate of necessity from the government permitting amortization of \$75 million of the proposed expenditures over the next 5 years, and plans to ask for similar accelerated depreciation to cover balance of the program.

Besides the new steelmaking capacity at Pittsburgh, J & L plans to install a new blooming mill to replace one of two present mills. A new bar mill will be installed to replace the last remaining pre1930 mill, which is being dismantled to make room for scrap preparation and storage facilities. Three other obsolete bar mills already have been dismantled.


Two Openhearths for Otis

Addition of the new openhearth capacity here will aggravate an already tight scrap market in the Pittsburgh district.

At the Aliquippa plant, a second electrolytic tinning line with auxiliary equipment, a cleaning unit and a temper mill will be installed, as previously announced. This will enable the company to make full use of its cold-reducing capacity there. When this program is completed in mid-1951, tin mill capacity will be increased 50 pct. A modern high speed rod mill will replace two obsolete mills at Aliquippa. Capacity of the tube round mill will be increased about 58 pct, providing additional steel for the seamless pipe mills and making available round bars for shell or other forgings. A new battery of 59 byproduct coke ovens now being installed will be producing early next year.

At the Otis works, ingot capacity will be increased by about 360,000 tons per year with the ad-

CHASSIS LINEUP: DeSoto bodies move automatically on overhead conveyers to the entrance of the paint department. They have just been welded in the new body-building operation installed in DeSoto's Warren Ave. plant, Detroit. The conveyer attachment rotates the bodies for painting ease.



dition of two openhearth furnaces, making a total of 11 at the plant. Additional soaking pits, and replacement of a 650-ton blast furnace with a larger unit with a hearth diameter of about 26 ft will provide more hot metal. Equipment will also be installed for the handling of larger coils and finishing equipment will be improved and expanded.

GM Loans \$28 Million

es to

im to

gust.

The

for

ed a

a the

rtiza-

posed

xt 5

milar

cover

ig ca-

plans

ill to

mills.

led to

pre-

dis-

scrap

lities.

mills

earth

te an

in the

econd

aux-

z unit

talled,

is will

e full

pacity

s com-

ll ca-

pet. A

vill re-

t Ali-

round

out 58

eel for

mak-

r shell

attery

s now

ducing

capac-

about

he ad-

AGE

ed.

The \$28 million to be spent at Otis will be loaned by General Motors Corp., to be repaid by Jan. 20, 1966 in monthly installments, size of which will depend on volume of sales to GM and others. Maximum monthly payment will be \$325,000. In return, GM will buy just about all the additional capacity at Otis, except for what may be diverted to others for defense purposes GM also will get 50,000 tons of finished steel per year from the Pittsburgh and Aliquippa plants to replace an equivalent tonnage now being produced by J. & L. for GM on a conversion basis.

J. & L. also has arranged to borrow \$40 million from 11 banks. Before the GM loan can be made. stockholders must authorize an increase in indebtedness of J. & L. By \$30 million—from \$150 million to \$180 million. A special meeting of shareholders will vote on this next Jan. 17. The stockholders also will vote on whether to increase the number of common shares from 3,500,000 without par value to 7 million \$10 par value, to change each share now authorized and outstanding into two shares of common at \$10 par

Canada May Get Less U. S. Steel

Toronto—Although the United States may allocate steel for essential Canadian programs, tightening of steel shipments to general manufacturing may actually slow down delivery into Canada, said the Canadian Manufacturers' Assn. Supplies in Canada are now growing tighter with no relief in sight.

Riverside Metals Asks Copper Order Delay; Sees Labor Leaving

Riverside, N. J.—A 30-day postponement of National Production Authority's order cutting back copper allocations by 15 pct was asked by the Riverside Metal Co. to forestall serious loss of skilled workers "irreplaceable in a wartime labor market and vital to defense production."

James T. Duffy, Jr., president of the nonferrous alloy firm, said that only 10 pct of output is for defense and the remaining 90 pct hinges on the copper supply. Since it was unlikely that issuance of defense orders could be speeded to make a satisfactory transition to defense tempo, Mr. Duffy said, a more realistic base than the January to June period should be chosen to avoid a production lag that means departing help.

Riverside argued in Washington that the present base provides for output 400,000 lb per month less than current production and that the period from August through November is a much fairer base.

Manganese Ore from Brazil

Sao Paulo—About 500,000 tons of needed manganese ore for American use after 1952 will be produced in Brazil's Amapa Territory mines which are now being constructed with a \$35 million loan from the World Bank.

Bethlehem Steel Corp., in partnership with Brazil's ICOMI, has pledged a market for full mine output. World Bank funds will build a railway from the mines to the Amazon River, near Macapa, and an unloading system for vessels.

Bendix Aviation Buys Plant

Davenport, Iowa—To increase production of aircraft instruments and accessories, Bendix Aviation Corp. has purchased property and a factory building of the Victor Animatograph Corp., here. Malcolm P. Gerguson said the purchase was prompted by increasing military demands. The plant, built in 1947, contains 154,000 sq ft of manufacturing space.

Valves and Fittings Bottleneck?

Washington—National Production Authority officials this week were wrestling with the problem of how to provide enough composition ingot brass to meet the demand for valves and fittings.

This was a bottleneck during World War II. Industry spokesmen are asking that more composition ingot brass be allotted under M-12, permitting the industry to hold onto its skilled manpower while material supplies build up.

SHIPPING PROB-LEM: Because of its size, shipment of this huge one-piece cast steel turbine runner necessitated use of two flat cars with a structural steel cradle. Made by the Erie Forge Co., Erie, Pa., the casting moved on a special train during daylight at a top speed of 15 mph. It had a diameter of 17 ft. 4 in. and weighed 165.000 lb. It is for a hydroelectric power plant unit.



Steel's Modest Price Boost Causes Little Fuss in Capital

Washington—Economic Stabilization Agency officials are watching developments closely as steel companies attempt to pull their prices into line to offset increased costs resulting from recent wage agreements with labor.

The officials say they are studying the steel price increases on a company-by-company basis and say further that they would have no hesitancy about taking action where the price boosts seem unjustified or out of line.

Amounts to Token Approval

In effect, this gives token approval to the 5½ pct pattern set last week by United States Steel Corp., particularly since no overt notice was taken by Stabilization Director Valentine such as in the case of the automobile price boosts.

"In the best judgment of the agency," Administrator Valentine said, "it did not seem necessary to take any action (relating to steel increases) at this time."

At the same time, Wage Administrator Cyrus W. Ching made it clear that he would attempt to carry out the intent of Congress with respect to price-wage stabilization. When selective price controls are imposed, he said, the ESA would also impose selective wage controls

Meanwhile, ESA is planning industry advisory committees to help it work out a practical policy.

Mobile Customs Imports Rise

Mobile, Ala.—Iron ore and crude rubber imports through the Mobile Customs District, Mobile and Gulfport, Miss., were \$300,000 higher in September 1950 than in September 1949, reports the Dept. of Commerce.

Total monthly imports of \$2,-864,796 included: \$700,000 in bauxite ore from Surinam; \$540,-321 in manganese ore from India and other countries; and \$157,792 in iron ore from Sweden and Brazil.

U. N. Unit to Stimulate Scrap Collections to Reach Output Goal

London — Scrap collections in Europe must be at their maximum to ensure planned record production of 52 million metric tons of pig iron and 69 million metric tons of crude steel in 1951, decided the United Nations Economic Committee's steel branch at its Geneva session.

The committee decided to initiate a new drive to collect steel-making scrap and to revive its panel of scrap experts. It believes that 1951 production goals can be attained providing scrap collections are high and capacity production of coke and iron ore is maintained. More serious shortages of iron ore in 1953 are foreseen.

Fairless Wins Bessemer Medal

London — Ben Fairless, president of U. S. Steel Corp., has been awarded the Bessemer Medal for



Ben Fairless

1951 by The Iron and Steel Institute, London, in "recognition of his distinguished service to the iron and steel industry."

The medal

will be presented to Mr. Fairless at the Institute's annual

general meeting in London on May 30, 1951.

William Barr, of Colvilles, Ltd., president of the West of Scotland Iron and Steel Institute, was awarded the Sir Robert Hadfield Medal for 1951 for his contributions to steelmaking research.

McGraw Co. Gets Ford Contract

New York—A \$500,000 contract for installation of machinery and equipment at Ford Motor Co.'s new Cleveland engine plant has been awarded to F. H. McGraw Co., this city.

Three-Range Glasses Focus On Efficiency of Myopic Middle-Aged

New York—Eyeglasses with Continuous Vision lenses are adding to the usefulness of middle-aged workers in industry by going bifocals one better. They provide a third seeing range for the employee whose sight is going blurry.

C

V

th

di

ch

fle

fo

ha

si

du

T

Re

3.

Re

en

Br

fo

ma

ne

en

ha

B.

res

ter

ha

we

De

ear

the

mo

fee

not

rec

ma

cou

in

wil

for

pro

alu

De

7

Tests held at the Northern Illinois College of Optometry since 1948 indicate that the three-range spectacles will be of special benefit to middle-aged workers in metal trades, shipping and materials handling industries, and other fields.

Overcomes Fatigue

The lenses bring into focus objects within the important arm's length area, 18 to 50 in. from the eyes. Three segments permit the wearer to see near and far and restore clear vision for vital closer work. Poor sight in the closeup zone lowers working efficiency and leads to fatigue.

Metalworkers and industrial machine operators who wore single vision or bifocal lenses complained to the research clinic's eye doctors that they were unable to see fixtures clearly or to see well enough to insert metal stock into their machines efficiently.

Their eyes were being strained and they found themselves squinting at the micrometer or while reading blueprints. When they were equipped with Continuous Vision lenses, their troubles were over.

British Workers Slated for Raise

London—After negotiations lasting over a year, 2 million engineering workers in Britain's factories and shippards will get pay increases of up to \$1.54 for skilled workers, with a maximum basic time rate of \$17.94. Raises will follow talks between the Confederation of Shipbuilding and Engineering Unions and employers. The 37 unions had originally asked for \$2.80 per week.

Heppenstall Co. Develops "Prestem", Hot-Working Die Steel

n

Aged

Con-

lding

aged

g bi-

ide a

emurry.

Illi-

since

ange

bene-

metal

erials

other

s ob-

arm's

n the

t the

and

closer

oseup

y and

al ma-

single

ained

octors

e fix-

nough

their

ained

quint-

while

they nuous

were

laise

s last-

engi-

s fac-

et pay

basic s will

onfed-

Engi-

oyers.

asked

AGE

Pittsburgh — The Heppenstall Co. is now marketing a newly developed hot-working die steel in the form of solid press dies, insert dies, upsetter dies, and punches.

Called "Prestem," the new steel will develop a minimum of heat checking and yet resist the plastic flow of hot metal during press forging operations. It is readily machineable at comparatively high hardness, has a high impact resistance, and may be water cooled during press forging operations.

Three Hardness Ranges

Heppenstall Co. is marketing "Prestem" in three general hardness ranges—"A" hardness of 2.95-3.10 Brinell B. D. with a 41-45 Rockwell "C"; "B" hardness of 3.15-3.30 Brinell B. D. and a 36-40 Rockwell "C," and in a prehardned, untempered condition, having a hardness range of 3.10-3.25 Brinell B. D. (38-42 Rockwell "C") for customers' tempering after machining to a precipitation hardness beyond machinability.

When dies are tempered by the customer, says Heppenstall, a hardness range of 2.90-3.00 Brinell B. D. or 45-48 Rockwell "C" will result when tempered at 950°F. If tempering is done at 1050°F the hardness range will be 2.70-2.85 Brinell B. D. and 49-52 Rockwell "C."

Detroit Weighs Copper Cutback

Detroit—While it is still too early to predict the full effects of the 15 pct copper cutback on automobile production, the trade here feels that the slash in copper will not necessarily mean a parallel reduction in auto output. Very limited substitutions could be made and if lighter gage copper could be used, appreciable savings in radiators, wiring and car radios will result.

The possibility of substituting for copper is undoubtedly less promising than switching from aluminum or even steel.





Chicago Will Be Greater User And Producer of Steel, Says Sykes

NS

Fas

cur

issu

for

defe

pan

firm

estin

estin

wou

of n

2,50

2.75

with

Refr

mate

clud

and

town

Arm

nors

ufac

Iron,

Haze

Rive

Steel

C-I T

Pit

of in

Steel

plate.

and e

Jan.

nound

base

likely

on w

with

28 in.

extras

above

specti

Quant

lb. Re

ends o

ename are 10

gage.

tras a

25¢ ov

Decen

Carr

U.

Co

T

Chicago—This section will become a greater steel producing center and steel consumption might continue to grow here at an even faster rate than production, said Wilfred Sykes, executive committee chairman of Inland Steel Co., in an address before the Chicago section of the American Institute of Mining and Metallurgical Engineers.

"It will be seen that the supply of ore available for use in the Chicago district is ample for generations to come, and will allow expansion of the steel industry to cope with the demands of this great manufacturing center," Sykes said.

Mr. Sykes stated that steel consumption of the Illinois-Wisconsin-Michigan area is about 45 pct of the total national consumption and steel production is about 25 pct of the total. He contrasted this with the Pennsylvania-Ohio area which has 25 pct of the national consumption and 50 pct of the steel production. Mr. Sykes declared that Chicago's advantages are proximity to consuming industries and ready access to essential raw materials.

Form New Civil Engineers Unit

New York—A new Engineering Mechanics Div. has been added to the American Society of Civil Engineers with the appointment of an executive committee. Goal of the new unit is to foster "activity and development in applied mechanics and other basic branches of knowledge which form the background and foundation" of the field.

Orders 100 Diesel Locomotives

Birmingham — Orders for 100 new diesel locomotives have been placed by the Birmingham Div., Southern Railways System, with the American Locomotive Co., Electromotive Div. of General Motors, and the Fairbanks Morse Co. Total cost of the order is estimated at \$17 million.

NSRB Grants 18 Steel Firms Fast Tax Writeoff Certificates

S

g

n

n

n,

n-

el

n-

i-

ly

ni-

a-

W

ry

of

r,"

n-

n-

pet

25

his

rea

nal the

deges

us-

tial

it

ring

d to

En-

t of

of

vity

me-

ches

ack-

the

S

100

been Div.,

with

Co.,

Mo-

e Co.

ated

AGE

Washington—The National Security Resources Board this week issued 48 tax necessity certificates for rapid tax writeoff to expand defense facilities of 18 steel companies and 3 refractory firms.

The certificates issued to steel firms were for expanded facilities estimated at \$469,266,643. NSRB estimated that this expansion would provide additional capacity of more than 5,500,000 ingot tons, 2,500,000 coke tons capacity, and 2,750,000 pig iron tons capacity with related finishing facilities. Refractories expansion is estimated at \$22 million.

Companies granted tax relief include Republic, Northwest Steel and Wire, Great Lakes, Youngstown Sheet and Tube, Crucible, Armco, Sheffield, Lone Star, Connors, West Virginia Steel and Manufacturing Co., Empire, Woodware Iron, Keystone Steel and Wire, Hazelton Steel and Tubing, Green River Steel, National, McClouth Steel, Sharon Tube.

C-I Tinplate Prices

Pittsburgh—Chiefly for reasons of inventory adjustments, U. S. Steel Co.'s new tinplate, blackplate, and terneplate base prices and extras are not effective until Jan. 16. Other producers have announced Jan. 1 effective dates on base prices, and extra charges are likely to be effective Jan. 1 also.

U. S. Steel width extras apply on widths of 26 in. and under, with deductions for widths over 28 in. Basis weight is 100 lb, with extras and deductions applicable above and below this weight, respectively. Length extras vary with basis weight and length. Quantity extras apply under 7500 lb. Resquaring extras are 40¢ for ends or sides, 60¢ for ends and sides.

Carnegie - Illinois hollowware enameling extras, effective Dec. 1, are 10¢ for 30 gage, 30¢ for 31 gage. Width extras and deductions apply as above. Length extras are 5¢ over 40½ to 48 in., 25¢ over 48 to 124 in.



National Emergency Would Permit Negotiation of Contracts

Washington—Declaration of a National Emergency by President Truman would give the administration one major power of prime importance to industry. This would permit the negotiation of any or all government contracts. Existing law is broader than that in effect at the outset of World War II, but it still limits negotiated contracts to 17 specific cases.

Refusal Means Recapture

No additional power is needed to get surplus war plants, sold under the security clause, back into war production. The procedure would be for the government to offer such plants military contracts. If refused, the government could recapture the plant immediately.

A national emergency would also give the President authority to seize railroads and other communications facilities.

However, these powers are still effective under World War II emergency proclamations. The government is still nominally running the railroads as a result of last summer's strike threat.

It is generally agreed that proclamation of a national emergency would be of value principally from the psychological standpoint of convincing the people of the threat to the country. It would also spur Congress to act on future requests for emergency legislation.

Life for Old Laws

Actually, the emergency would bring to life numerous old statutes, but most of these have been superseded by laws such as the Defense Production Act. Several minor laws, however, could be brought into effect, including those authorizing placement of the Coast Guard under the Navy, terminating ship charters, restricting explosives manufacture, and terminating the 8-hour day and some minimum wage laws in defense industries.



For full information, write today for free booklet SB 2039 and a current price quotation. You'll find Edisons cost little more than other makes of batteries . . . and they pay this back over and over in terms of low upkeep and long, long life. Edison Storage Battery Division of Thomas A. Edison, Incorporated, West Orange, New Jersey. In Canada, International Equipment Company, Ltd., Montreal and Toronto.



EDISON

Nickel · Iron · Alkaline STORAGE BATTERIES



Typical Truck Battery

Dece



8ne ld

or

ng

ts

old ck

ce-

ent n-

ent ne-

uld

ity m-

till

II

The

unof

oc-

ncy

rom

of

the

also

re-

ion.

ould tat-

een

the eral

be

ding

the terrict-

and

and

GE

1505 EAST BROADWAY HAWTHORNE, CALIF.



Fabricated steel awards this week included the following:
1300 Tons, Wynnewood, Pa., three additional apartment units, Wynnewood Apartments, to Bethlehem Steel Co., Bethlehem, Pa.

Bethlehem, Pa.

1000 Tons, Pottstown, Pa., new plant.
Doehler-Jarvis Corp., to Frank M.
Weaver & Co., Lansdale, Pa.

470 Tons, Wilmington, Del., RR bridge
on Cristiana River for Pennsylvania
Railroad, to Morris Wheeler Co.,
Philadelphia.

410 Tons, Luzerne County, Pa., bridge
for Pennsylvania Dept. of Highways,
to Pinebrook Iron Works.

240 Tons, Lansdale, Pa., addition to
warehouse for Lansdale Tube Co., to
Lehigh Structural Steel Co., Easton,
Pa.

Pa.

175 Tons, Fredericksburg, Va., American Viscose Co. acid recovery building No. 2, to Belmont Iron Works.

133 Tons, Putnam, Conn., clear span composite steel girder bridge and bituminous concrete approaches. H. S. Ives, Norwich, Conn., district engineer. Jones Construction Co., Columbia, Conn., low bidder.

Fabricated steel inquiries this week included the following:
870 Tons, Berks County, Pa., bridge, Pennsylvania Dept. of Highways, bids due Dec. 28.
600 Tons, Chicago, 23rd Street viaduct for Chicago park district Carroll

Tons, Chicago, 23rd Street Carroll for Chicago park district. Carroll Construction Co., Chicago, low bid-

Construction Co., Chicago, low bidder.

255 Tons, Waukesha County, Wis., bridge F 06-/24/.

230 Tons, Ft. Meade, Md., bridges on Baltimore-Washington Parkway, bids due Dec. 14.

170 Tons, Indiana County, Pa., bridge, Pennsylvania Dept. of Highways, bids due Dec. 27.

150 Tons, Boston, freight terminal, bids due Dec. 18.

135 Tons, Iroquois County, Ill. 7, bridge section 141 B. Bids due Dec. 15.

110 Tons, Marionette County, Wis., bridge project S10544/1/.

109 Tons, Beaver Falls, Pa., bridge reconstruction, Pennsylvania Dept. of Highways, bids due Dec. 28.

Reinforcing bar awards this week in-

Reinforcing bar awards this week included the following:
1500 Tons, Sunbury, Pa., Pennsylvania
Power & Light Co., power station
unit No. 4, to Bethlehem Steel Co.,

Power & Light Co., power station unit No. 4, to Bethlehem Steel Co., Bethlehem.

Tons, Newtown and Southbury, Conn., Housatonic River Bridge. Relocation H. S. Route I. Mariana Construction Co., New Haven, Conn., low bidder.


Tons, Auburn, Ala., dormitory for Alabama Polytechnic Institute, to Truscon Steel Co., Birmingham, Ala.

Tons, Luzerne County, Pa., Pennsylvania State Highway Route 40033, Sections 5 and 7, B. G. Koon Construction Co., general contractor, to Bethlehem Steel Co., Bethlehem.

Reinforcing bar inquiries this week included the following:
468 Tons, Chicago, Racine Ave. pumping station for sanitary district.
200 Tons, Barrington, Ill., building for Jewel Tea Co. A. L. Jackson Co. low bidder.


Steel piling awards this week included


following:
Down, Newtown and Southbury,
Conn., Housatonic River Bridge, relocation H. S. Route 1. Mariana
Construction Co., New Haven, Conn.,
low bidder.



To serve well, a machine part-even when made of good steel, properly treated-must be properly designed.

A new 72 page booklet, sent free on request, discusses the vital relation between design, good steel and its satisfactory treatment.





NPA Puts Tight Controls On Copper Scrap Stocks, Distribution

Washington — Tight controls were imposed on copper scrap this week by the National Production Authority. It issued order M-16 providing inventory ceilings and procedures for distribution.

A safeguard against gray marketeers is set up by confining acceptance and delivery to scrap dealers, refiners, brass mills, brass and bronze foundries, ingot makers, and miscellaneous producers who regularly use copper scrap in normal operations.

Inventories of scrap dealers are limited by the order to one-third of the delivery by weight of first half 1950 total delivery. Mills are directed to guard against accumulation of "excess" stocks of mill scrap.

Melting and other processing of mill scrap is limited to the mills themselves except by specific NPA approval. Sale of mill scrap is also forbidden except to regular scrappies, refineries, and other producers such as foundries which require such scrap for normal operation.

"Got

what

of me

T&L

possil

we p

arefu

Steel

might "So Steel :

Auton

had us

been p

oon r

with '

peed

of 600

01

nd JALI

Dece

Likewise, conversion or toll agreements where the scrap owner retains the title are made unlawful unless they are first cleared or approved by NPA. The order applies to all copper and copper-base alloy scrap containing 40 pct copper by weight and includes brass mill scrap, artillery cases, and fired or demilitarized cartridges.

Lists Use of Gray Iron Coatings

Indianapolis, Ind.—Use of metallic or non-metallic coatings for gray iron to increase resistance to corrosion, wear and oxidation and improve appearance standards was outlined by C. O. Burgess, technical director of Gray Iron Founders' Society, Cleveland, before the local chapter of the American Foundrymen's Society here.

Mr. Burgess said the use of such coatings is of vital significance as a means of conserving essential alloying elements which are now in short supply.



From receiving of raw materials to shipping of finished washers BAKER FORK TRUCKS play a vital role in keeping costs to a minimum

The new Maytag Automatic Washer plant at Newton, Iowa was designed to provide the most efficient movement and handling of materials. 14 Baker Fork Trucks play an important role.

For Example:

Handling coils of steel strip weighing from 7,000 to 10,000 pounds (top illustration) with a Baker Heavy Duty Fork Truck has made it practical to buy steel in full-width coils and slit them to required widths in their own plant.

Machined parts are received and stored in special parts bins—designed for easy access and visibility, and for safe high tiering due to built-in skids for handling with fork trucks. (See left, below).

Diecast metal is received in bundles of pigs, bound with steel strap in a manner to permit unloading and tiering with Baker 4,000 pound fork trucks without the use of skid platforms or pallets.

One operator with a Baker (light-weight, low-cost) Fork Truck loads cars with 80 to 100 finished machines in the time it would take four men with hand trucks to do the job. (See right, below).

Our material handling engineers are available for planning comparable savings in your plant.



BAKER INDUSTRIAL TRUCK DIVISION

of The Baker-Raulang Company


1227 West 80th Street

Cleveland 2, Ohio

In Canada: Railway & Power Engineering Corporation, Ltd.

Baker INDUSTRIAL TRUCKS

WE INCREASED PRODUCTION 71% WITH J&L "E" STEEL



(a story* about how to win customers and influence prospects)

"Got a minute? Well, let me tell you about what happened at our machine shop a couple of months ago when we first tried that new I&L "E" Steel. You wouldn't believe it was possible! (Confidentially, neither did we until we proved it to ourselves.) Here's what

happened.

ion

ols his ion -16 and

aracrap 1888 akers p in

are hird first are mu-

mill

g of

nills

NPA

also

erap-

pro-

hich

rmal

toll

wner

wful

ed or

r ap-

-base

t cop-

brass

and

idges.

ngs

f me-

gs for

nce to

n and

ls was

echni-

oundre the

erican

f such

nce as

ential

e now

AGE

"We got an order to produce a big lot of plunger stops for solenoid starter switches. They're tricky to run, and you've got to be pretty

careful every second. We'd read about "E" Steel in some of J&L's ads, and decided we

might try some on this job.

"So we ordered some 17/32" E-33 "E" Steel stock, set up our B&S #2 and B&S #0 Automatics and began to turn out parts. We had used B-1113 for this job before and had been getting 350 pieces per hour. But we soon realized we could machine much faster with "E" Steel, and we kept increasing peed until we were getting an average of 600 parts per hour. That's a 71%



production increase!

"Next thing we discovered was that our tools were lasting twice as long and the chips were coming off better

with "E" Steel than they did with B-1113. We also found that the finish on the parts had improved from 20% to 25%.

"That's why we've been using "E" Steel.

We turn out work much faster and can take on more jobs. Our men like the way "E" Steel machines and our customers get better parts and better service. Everybody benefits!"

Get your copy of the booklet titled "A Progress Report on 'E' Steel." It outlines a series of 11 case histories from machine shops that have used "E" Steel with excellent results. Write for your copy.

* Based on an actual case history.

"E" Steel (U.S. Pat. No. 2,484,231) is easily identified by the distinctive blue color on the end of every bar.

ONES & LAUGHLIN STEEL CORPORATION

om its own raw materials, &L manufactures a full line of arbon steel products, as well as ertain products in OTISCOLOY nd JALLOY (hi-tensile steels).

PRINCIPAL PRODUCTS: HOT ROLLED AND COLD FINISHED BARS AND SHAPES . STRUCTURAL SHAPES . HOT AND COLD ROLLED STRIP AND SHEETS . TUBULAR, WIRE AND TIN MILL PRODUCTS . "PRECISIONBILT" WIRE ROPE . COAL CHEMICALS



Jones & Laughlin Steel Corporation 403 Jones & Laughlin Building Pittsburgh 30, Penna.

Please send me a free copy of "A Progress Report on 'E' Steel."

Title

Company

Address

December 14, 1950




"It's the THOMAS TWO-STEP, Plunkett!"

The Thomas "two-step"? It's mighty popular with many a light metals fabricator these days. It's so easy to learn . . . and profitable to know. You start with pre-coated THOMAS STRIP. Then take just two steps—fabricate . . . assemble—and, in many cases, you'll have produced a finished, saleable product.

Try "two-step" production using Brass Coated THOMAS STRIP, for example. No need for costly surface preparation. This pre-coated strip steel comes to you all ready for immediate fabrication. Cleaning, plating, buffing after fabrication all may be eliminated. Your finished parts have a uniform brass coating, inside and out. And, the brass coating protects parts in process against corrosion.

Work it as you will. The tight brass pre-coat—unitized with its strip steel base of controlled metallurgy under The Thomas Process—now is more generous than ever . . . better able to stand severe fabrication without cracking, peeling or flaking.

To offer "two-step" production for a wider range of products, Brass Coated THOMAS STRIP now can be furnished up to 20-inches wide, in gauges .010" to .035". Write us for test samples and complete information.



Uniform Inspection Standards

Washington—Under a new regulation just issued, Sec. XIV of the Armed Services Procurement Regulation, all inspection of supplies and services contracted for by the military will be in accordance with the uniform standards established by the Defense Dept.

These include standards as to sampling procedure, statistical quality control needs, gage design, use and care, policies as to exchange of services, methods of interpreting specifications, and standardized forms.

If goods do not pass inspection and if an urgent need exists, such supplies may be accepted and an adjusted price worked out with the contractor. The new regulation will apply to all contracts made on and after Jan. 1, 1951.

Detroit SAE Hears Metallurgists

Detroit—John L. Ham, Climax Molybdenum Co., and Dr. R. 1. Jaffee, Battelle Memorial Institute, spoke at the Dec. 4 meeting of the Detroit Section. Engineering Materials Activity meeting of the Society of Automotive Engineers.

Mr. Ham described the arc-cast process for making pure molybdenum billets. This process converts raw metal powder into usable cast material and is one of the most promising methods for increasing the production of pure molybdenum.

The subject of Dr. Jaffee's talk, "Titanium — An Interim Appraisal," was aimed at acquainting materials people and designers with the swiftly moving technology of titanium and titanium alloys.

Locomotives Tour Railroads

Schenectady — A nation-wide demonstration tour by two 4-unit 6400 hp dual-purpose locomotives has been started by Americas Locomotive and General Electric. One of the 1600 hp, 240,000 lb locomotives will visit Eastern railroads, the other Western railroads.

Dece



Hush Before Christmas

The mysterious season of Cnristmas approaches.

A hush of anticipation silences all else while the children wait, full of confidence, for the sound of sleighbells and the hearty laughter of their all-knowing friend.

What more appropriate a time to pause a moment and wish each other well! Even in these days of uncertain peace, we, too, look ahead not without hope that life may become more secure and joyous for all.

In this Christmas season, may you—our customers and friends—be again assured of the blessings of peace and prosperity. And be assured, also, that we, at Wisconsin Steel, shall do our very best to merit your continued good will and friendship.



regof nent
supfor
ordards
dept.
s to
tical
sign,
exs of
and

etion such d an with gularacts 51.

ists limax R. I.

Instiec. 4 etion. etivity

Auto-

c-cast

nolyb-

con-

one of

s for pure

s talk,

igners

tech-

anium

n-wide 4-unit

notives

erican lectric. b loco

rail-

AGE

Apuaint-

WISCONSIN STEEL COMPANY, Affiliate of INTERNATIONAL HARVESTER COMPANY 180 North Michigan Avenue • Chicago 1, Illinois

WISCONSIN STEEL

December 14, 1950

133



END MIXTURE PROBLEMS. PRODUCE SAME
ANALYSIS GAS REGARDLESS OF DEMAND . . .
HAVE EXCLUSIVE SINGLE AIR-GAS CONTROL!

You need the correct protective atmospheres for heat-treating operations! Here's how Kemp Atmosphere Generators solve your problems once and for all! One single knob sets the air-gas mixture accurately, permanently. No matter what the demand, you get the same analysis inert gas from 1% to 100% of capacity. With Kemp there is no need for tinkering!

ABSOLUTELY DEPENDABLE

Kemp Generators burn ordinary gas just as it comes from the mains. A famous Kemp Carburetor, part of each installation, assures complete combustion... producing a clean, chemically

inert gas containing 88% nitrogen, 12% $CO_2\ldots$ a gas so pure it is used without further processing in the manufacture of aspirin and laboratory chemicals, fine paints and a host of other products.

SEND FOR PROOF!

Whether you need special atmospheres for purging, fire protection, blanketing or any steel process . . . specify Kemp. For technical information write for special bulletin. To find out how much you can benefit: tell us how you produce inerts now; we'll show you how Kemp can solve your problem! Mail coupon today!

KRM	ATMOSPHERE GAS GENERATORS
	THE C. M. KEMP MFG. CO., Dept. C-12 405 E. Oliver St., Baltimore 2, Md.
OF BALTIMOR	Gentlemen: Send me information. Also, show me how much we can save an inerts. We now spend
CARBURETORS	per micr for ment used in(process.)
BURNERS FIRE CHECKS	Name
ATMOSPHERE GENERATORS	Company
ADSORPTIVE DRYERS METAL MELTING UNITS	Address
SINGEING EQUIPMENT	City Zene State



PUBLICATIONS

Continued from Page 34

mounting data are contained; a few typical applications taken from hundreds of installations of Commercial cylinders in use are shown. Several types of pumps, motors and valves are also described. Commercial Shearing & Stamping Co.

For free copy insert No. 8 on postcard, p. 35,

Steel Strapping

Tools and materials for the Brainard strapping system are described in a new 18-p. booklet. Various types of regular and heavy duty strapping in a number of styles and finishes, strapping tools and accessories, electro galvanized strip steel, electric welded steel tubing, cold rolled strip steel and beaded hoops are shown. Brainard Steel Co.

For free copy insert No. 9 on postcard, p. 3i.

Bulldozers

Various models of Williams-White bulldozers, with long stroke and accessible die space, requiring low initial cost and minimum maintenance, are described in a new 4-p. bulletin. The folder lists general and alternate specifications, and contains a bulldozer detail table covering the double and single geared series. Special features are also described and illustrated. Williams-White & Co.

d

b

Dec

For free copy insert No. 10 on postcard, p. 35.


Precious Metal Products

Baker precious metal products for industry are described in a new 8-p. booklet showing a variety of platinum laboratory ware, spinnerets, mass catalysts, fine wires and electrical contacts and contact materials. Also shown are Deoxo gas indicators and purifiers and industrial gas-fired furnaces. Baker & Co., Inc. For free copy insert No. 11 on posteard, p. 15

Close-Coupled Pumps

Outstanding features of Alta close-coupled centrifugal pumps are listed in a new 12-p. catalog. The booklet shows how these pumps op

LOST: \$6,000,000,000 FROM RUST!



MAINTENANCE USES

S

i; a from Comown. otors ibed. ping p. 35.

the e deoklet. neavy

er of

tools

nized

steel

l and

inard

p. 25.

iamsstroke iring imum

in a

r lists

tions.

table

single

es are

rated.

p. 35.

ets for

w 8-p.

plat-

nerets,

d elec-

nateri-

as in-

ustrial

o., Inc. d, p. 1i.

Alta ips are

The ps op

AGE

ts

- Products display
- Sprinkler system Water tank Exterior
- Interior Interior
 Riser and Tower 11. Stored metal
- Window sash Piping
- 7. Fire escape 8. Boiler room
- 9. Boiler setting
- 10. Gutters and down spouts Exterior
- 12. Various tanks and 16. Chains and cables air reservoirs Exterior Interior
- 13. Electrical control panel, bus bars battery terminals,

conduit

- 14. Valves, bonnets, stems
- 15. Structural steel
- 17. Piping-Insulation on piping
- 18. Conveyors
- 19. Templates, dies, and gauges in storage 20. Stored machinery
- 21. Cooling tower
- 22. Drying ovens
- 23. Acid tank and ventilator hood 24. Ventilators
- 25. Railroad'track.
- 26. Steel overhead doors 33. Export shipments

PRODUCTION USES

- 27. Parts in storage
- 28. Metal stampings
- 29. Stock metal in storage
- 30. Production parts
- 31. Dipping production items
- 32. Finished production items

HOW MUCH IS YOUR PLANT CONTRIBUTING?

This year-every year, rust takes its tremendous toll in industrial plants throughout the country. In dozens of places throughout your building, from water tower to boiler room, in structural metal as well as during the fabrication of metal products, rust is silently at work, destroying valuable equipment, lowering profits, increasing maintenance costs.

Regardless of the cause of corrosion in your plant, or the extent of protection necessary, there is a correct NO-OX-ID rust preventive designed specifically to give you positive protection-chemically, by stopping corrosive action, mechanically by sealing off corrosive elements.

Check your plant for the typically vulnerable areas illustrated. Let the Dearborn sales engineer make a complete Plant Inspection Survey and then recommend the . correct NO-OX-ID.

There is a correct Dearborn NO-OX-ID to combat and protect against rust wherever it threatens.

DEARBORN CHEMICAL COMPANY General Offices: 310 S. Michigan Ave. . Chicago 4, Illinois

THE ORIGINAL RUST PREVENTIVE

Dearborn Chemical Company 310 S. Michigan Ave., Dept. IA Chicago 4, Illinois

Gentlemen:

Please send me a copy of your introduction to NO-OX-ID rust preventives.

Name.....

Address.....

City..... Zone.... State.....

ROTARY GAS CARBURIZERS

A "First" by A.G.F.

A.G.F. Rotary Carburizers afford economies of operation that permit a substantial reduction in the cost of your heat treating.

WORK HANDLING IS MINI-MIZED. A.G.F. Rotary Carburizers are easily charged and discharged by means of a tilting mechanism, which is power driven on the larger models.

UNIFORMITY OF PRODUCT is assured by:

- I. Retort rotation thoroughly mixing the work.
- Positive control and maintenance of atmosphere in the retort.



LONG ALLOY LIFE is obtained because the retort remains in the heat at all times.

VERSATILITY. A.G.F. Rotary Carburizers can be used without modification for clean hardening, annealing, normalizing, etc.

Write for Catalog C-1304 describing Rotary Carburizers and other A.G.F. equipment.


AMERICAN GAS

Elizabeth




FURNACE CO.

New Jersey



We build any Craneto suit your <u>exact</u> needs



Write for new catalog.

BEDFORD FOUNDRY & MACHINE CO.

Bedford, Indiana
New York Office — 280 Medison Ave. — Murray Hill 5-0233

BEDFORD CRANES

FREE PUBLICATIONS

Continued

erate in any mounting position at high efficiencies, and practically eliminate end thrust on the ball bearings through special design of single suction impellers. Selection tables for 50 and 60 cycle speeds are contained, along with dimensional and other data on pedestal pumps. Gorman-Rupp Co.

For free copy insert No. 12 on postcard, p. 1i.

Temperature Controls

What you get in Crise temperature controls for gas, oil, stoker or hand fired heating equipment is shown in a new 8-p. catalog. Combination furnace fan and limit controls, hot water temperature controls and automatic damper controls are among the items described. Horse power ampere ratings are listed. Crise Controls Div., Acro Mfg. Co.

For free copy insert No. 13 on postcard, p. 3i.

Mill Crane Bulletin

A new 12-p. booklet describes and illustrates the many features of P&H Mill Cranes. Photographs showing typical installations in various mill departments are included. Crane Div., Harnischfeger Corp.

For free copy insert No. 14 on posteard, p. 15.

Pallet Handling

Features of the Lyon-Raymond hydraulic pallet lift truck that result in time and storage space savings are detailed on a new data sheet listing specifications and showing typical uses. Particularly adapted to handling double-face pallets, the unit has standard 4-in. lift and is available in capacities of 4000 and 6000 lb, as shown in the bulletin. Lyon-Raymond Corp.

For free copy insert No. 40 on posteard, p. 35.

Additives Formula

Formulas for using Alox additives in rust preventives, lubricants, motor fuels and fuel oils are presented in a new 6-p. folder. Examples of the many uses for these oxygenated hydrocarbons are detailed in the bulletin, with suggested formulas for use. Physical and chemical properties are listed Alox Corp.

For free copy insert No. 41 on postcard, p. 35. (Resume Your Reading on Page 35)

Lower cost Jig Grinding

proved by Vulcanaire for over

/ year

HOW? You place the Vulcanaire quickly in the spindle of your jig borer or mill.

NS

on at ically ball

gn of ection peeds imendestal

l, p. 11,

npera-

ent is Com-

t con-

e con-

con-

s de

pere mtrols

d, p. 31.

cribes

atures

graphs

ns in re in-

hfeger

d, p. 35.

ymond

nat re-

v data

and and

cularly

in. lift

ties of

in the

ox ad-

lubri-

oils are er. Ex-

r these

are de

h sug-

listed. ard, p. 36 age 35)

N AGE

rp. rd, p. 1i. NOW! You can locate—finish grind holes in hardened steel to "tenths" at controlled speeds up to 65,000 R.P.M... grind dowel holes—square with a ground base... move location of holes in hardened steel blocks... grind interchangeable holes in hardened sections... grind .032 to \%" holes with diamond impregnated laps... grind contours and relief with tungsten carbide burrs... grind radii in die sections... grind contours in gages... jig grind large and awkwardly shaped components... eliminate jig bushings in tools where close spacing is essential.

PRECISION! Jig ground requirements are being designed into tools by the most enlightened engineering departments... Jig ground the hardened die, stripper plate, and die holder all fit together... uniform clearance means longer runs.


ADVANTAGES! The investment is less than for many Jig Boring accessories such as a rotary table... the Vulcanaire can be put on and taken from the machine in a few seconds... the Vulcanaire is completely portable (all accessories are platform mounted)... the system can be used between several machines of various capacities... employing both the 10,000 and 20,000 series, components with various sized holes from the very smallest to 4" in diameter can be Jig Ground... the average Jig Borer operator becomes proficient at Jig Grinding after very little experience.

TOPS IN PRECISION!... the Vulcanaire is precision built throughout and is constructed of alloy and tool steel. Super precision bearings, preloaded with our special fixtures are used, with all traces of radial and end clearances removed, resulting in Vulcanaire Jig Grinding to "tenths".

For quotation and literature please mention machine tool application.



FOR JIG BORERS OR MILLS



DUST ELIMINATION




VULCAN TOOL CO., LORAIN STREET, DAYTON, OHIO



Where porosity problems must be met in handling liquids or gases many concerns find the trouble-saving answer in Non-Gran Centrifugal Castings. They are leak-proof—assure greater strength, take more punishment, last longer.

If you use liners, sleeves, rings, rolls, bushings, etc., in bronze alloys—rough or machined—check with Non-Gran. Request booklet—"Our Story In Pictures." American Non-Gran Bronze Co., Berwyn, Pa.





PUNCHES · SHEARS · PRESSES · BENDERS · SPACING TABLES =

NEW

PRODUCTION IDEAS

Continued from Page 38

tend the range of cross sectional areas that any flash welder can accommodate. Kingsley A. Doutt.
For more data insert No. 28 on postcard, p. 35.

Marking Machines

All-pneumatic model will mark up to 1200 pieces per hour.

A new line of general purpose marking machines, known as the Noblewest 50 series, consists of allpneumatic, semi-pneumatic and hand operated models. All are suited for trade marking, part numbering, codifying and serial number-



ing on metal, wood, and plastics. The machines use the Noblewest roll-marking process for trouble-free marking and lifelong impressions on flat or round surfaces, including precision graduating, serial numbering and knurling. This roll-marking process avoids shock to marking die or the piece being marked and is used to mark such close-tolerance parts as piston rings without straining or distorting them. Noble & Westbrook Mfg. Co.

For more data insert No. 29 on postcard, p. 3k

Universal Wheel Dresser

Capable of dressing a series of angles with all locations held.

The new universal dresser dresses a complete form rather than a single radius and angle tangent

De



EAS

ige 38

tional

an ac-

i, p. 35.

rpose

s the

of all-

suited

mber-

mber-

lastics.

blewest

rouble mpres-

ces, inc, serial
This
s shock
being
k such
piston
distortstbrook

ard, p. 35.

ser

dresses

than angent

N AGE

A WAY TO SAVE DOLLARS in the foundry is reported by T. Shriver & Co., Inc., Harrison, N.J., one of the world's largest makers of filter presses. They once made green sand molds which produced castings requiring much cleaning and considerable finishing. Now, these labor costs are reduced by making molds and cores dried in a Gas-fired oven. They produce far cleaner castings, requiring less finishing. Moreover, with a greater moisture content in the products of gas combustion, cores and molds are dried in humidified air, which is helpful in eliminating checking.

The Gehnrich mold-drying oven is 15' deep, 12'9" wide and 16' high overall; working space measures 12' x 14'4" x 8'. Heating equipment includes a Rockwell external direct Gas-fired air heater, fired with 530 Btu Gas. Temperature of this oven is controlled by a Bristol indicating thermometer. A high velocity fan provides ten changes of air per minute, delivering the heater air at 500° F. to ceiling distributor ducts. Blown through the process zone, air returns to heater. A ventilating fan, placed forward on the oven roof removes moist air.


Remember—GAS permits precise temperature control. It's dependable, economical, and readily adaptable to serve your particular needs. Your Gas Company Representative can put Gas to work for you—call him today.



December 14, 1950

Continued

This is possible through movements in the column and base with gage block application. The angles



may be set with sine bar in addition to graduations. The dresser may be used under the wheel or at the side and all settings may be made without removing from machine. Universal Form Tool Co.

For more data insert No. 30 on postcard, p. li.

"TOOLED UP"

Whenever you see a lineup of Clearing presses like this one in the Studebaker plant at South Bend, you know the management is going after profits by aggressive production. Indeed, with competitive conditions putting effective restraint on selling price, you've got to hold costs down if you expect to get volume business.

As Studebaker and so many other leading manufacturers know, they'll get top production efficiency from Clearing presses. Accurate stampings, thanks to Clearing precision, will assemble easily and contribute to lower costs all down the line.

Because these are provable facts, you'll find more and more of the world's stamping work—large and small—being done on Clearing presses. Let us show you how a Clearing press, or several of them, can step up production efficiency in your plant. It costs you nothing to consult our engineers.

GLEARING PRESSES

THE WAY TO EFFICIENT MASS PRODUCTION

CLEARING MACHINE CORPORATION
800 WEST 65TH STREET . CHICAGO 38, ILLINOIS



Dust Collector

Exhausts cleaned air to outdoors.

Rated at 885 cfm with 3-in. static suction the model 8N50 dust collector is recommended where outside exhaust of cleaned air is required due to state regulations or

H



to the presence of toxic fumes of vapors. Features are portability, immediate installation and compactness. The dust laden air enter the unit at the 5-in. diam inlet dust is taken out in the cyclost separator and deposited in the storage compartment which comprise

Dec



HERE IS AN OUTSTANDING FAMILY OF insulating fire brick for back-up or exposed use . . . the only family of its kind .. that gives you a complete range . . . a quick beating insulating fire brick for every

inued

movewith angles

addi-

Co.

50 dust

where

ir is re-

ions or

nmes of

tability, ad comir enten m inlet;

cyclone the stormprise

N AGE

By taking advantage of the quick heating characteristics of these insulating fire brick, you'll benefit through important savings in fuel because of the quicker rise to proper operating temperature in the furnace. This is a result of the low heat storage capacity and low thermal conductivity characteristics of the brick. These factors are especially important where furnaces are being intermittently operated.

The same materials can also be obtained in large size units as Johns-Manville Insulating Fireblok. This product has many advantages over the smaller size fire brick, from both a construction and stability standpoint. They can be quickly applied because they are easy to cut and fit. J-M Insulating Fireblok provide additional heat savings because they reduce the number of joints, and require less mortar

Why not have a Johns-Manville insulation expert call to tell you more about ways in which you can save by using these insulations in your furnaces. Write Johns-Manville, Box 290, New York 16, N. Y. for further information.

	JM-1620	JM-20	JM-23	JM-26	JM-28	JM-3000
Densities, Ib per cu ft	29	35	42	48	. 58	63-67
ransverse Strengths, psi	60	80	120	125	120	200
Cold Crushing Strengths, psi	70	115	170	190	150	400
inear Shrinkage,† percent	0.0 at 2000 F	0.0 at 2000 F	0.3 at 2300 F	1.0 at 2600 F	4.0 at 2800 F	0.8 at 3000 F
Reversible Thermal Expansion, percent	0.5-0.6 at 2000 F	0.5-0.6 at 2000 F	0.5-0.6 at 2000 F	0.5—0.6 at 2000 F	0.5-0.6 at 2000 F	0.5—0.6 at 2000 F
Conductivity® at Mean Temperatures			In consideration		CONTRACTOR OF	101
500 F	0.77	0.97	1.51	1.92	2.00	3.10
1000 F	1.02	1.22	1.91	2.22	2.50	3.20
1500 F	1.27	1.47	2.31	2.52	3.00	3.35
2000 F	-	1.72	2.70	2.82	3.50	3.60
Recommended Service						
Back up	2000 F	2000 F	2300 F	2600 F	2800 F	3000 F
Exposed	1600 F	2000 F	2300 F	2600 F	2800 F	3000 F

^{† 24-}hr simulative service panel test for JM-3000; 24-hr soaking period for other brick.



Johns-Manville First in INSULATIONS

^{*} Conductivity is expressed in 8tu in, per sq ft per F per hour at the designated mean temperatures.

Continued

the base of the unit. The cleaned air with any toxic fumes is exhausted to the outdoors through the outlet at the top of the cyclone. Aget-Detroit Co.

For more data insert No. 31 on postcard, p. 31,

Plastics Injection Press

Semi-automatic; 2 oz capacity; moldi thermoplastics including nylon.

For mass production of smaller plastic parts at low cost, a semiautomatic injection press has been developed. It is claimed that a job




can be set up on the press by one man in 20 min. A pushbutton control box mounted near the operator assures maximum accessibility. Simplified controls provide ease in hand setup or semi-automatic use Maximum mold size is 8x10 in.; casting area, 20 sq in. Van Dom Iron Works Co.

For more data insert No. 32 on postcard, p. 35.


Cylinder Cartridge Gland

A self-contained packing gland for hydraulic and air cylinders.

Marketed under the name Pemaco E-Z-Pak gland, and com-



plying with JIC standards, the new gland combines bearing surface, a low friction ram seal, and a seal guard ram scraper into a single



-Fills Swis

IN HIGH PRESSURE SERVICE

THE hydraulic cylinder pictured above gives 2-way assurance of exceptional life—despite repetitive pressures up to 3,000 psi.

Not only is it cast of tougher, stronger Meehanite Metal, but it's also a Shenango-Penn centrifugal casting. This in itself means a measurable gain in tensile strength ... finer, pressure-dense grain ... superior wear resistance ... freedom from defects ... and, very important in pressure work, avoidance of porosity. The net result is exceptional life, dependa-

ble performance, low-cost service.

Shenango-Penn centrifugal casting techniques, the result of specialization for years, offer decided advantages in symmetrical and annular parts of every description. They can be supplied in various metals, ferrous and non-ferrous... rough, semi or finish machined as you wish. You'll be time and money ahead.

SEND FOR FREE BULLETINS SHENANGO-PENN MOLD COMPANY

587 West Third Street Dover, Ohio Executive Offices: Pittsburgh, Pa.



ALL RED BRONZES . MANGANESE BRONZES . ALUMINUM BRONZES MONEL METAL . NI-RESIST . MEEHANITÉ METAL

De



An American MonoRail engineer will gladly give you all the details, or write us about the American MonoRail Constant-Service High-Speed Crane.

THE AMERICAN TO TORA COMPANY


13103 ATHENS AVENUE

CLEVELAND 7, OHIO

December 14, 1950

face, a a seal single

N AGE



AMERICAN CHAIN & CABLE

NEW PRODUCTION IDEAS

Continued

compact unit. No adjustment is necessary after installation. Replacement can be accomplished without dismantling the cylinder, and in most cases, without removing the cylinder from the machine. The cartridge gland is manufactured for both hydraulic and air cylinders. Petch Mfg. Co.

For more data insert No. 33 on postcard, p. 35.

Battery-Powered Trammer

11/2-ton, for mine-haulage work.

Small and compact, but powerful, the trammer is designed for use in metal mines where clearances are restricted. Available in any track gage between 18 and 24 in., the new unit is $71\frac{1}{2}$ in. long over



bumpers and 35 9/16 in. wide. Rated drawbar pull is 400 lb, with speed of 3 mph. A maximum drawbar pull on level tangent track is 750 lb. Any standard make of storage battery may be used for power supply. A folding cab permits loading in limited mine hoist cages. General Electric Co.

For more data insert No. 34 on postcard, p. 35.

Paint Heater

Supplies 24 to 28 gph hot paint to installations using spray guns.

A new double unit paint heater consists of two heating units mounted on a common base with a standard Bede circulating arrangement. The heater heats paint to 160°-200°F to reduce paint and solvent waste, increase the quality of the finish and reduce re-

BAKER'S MAGDOLITE helps you produce

per

dire

con

SHE

ible

con ing from

Ne

con

five

sta

tor

For

De





Dolomite Refractory is 5 WAYS BETTER

- more uniform ingots
- in greater numbers
- at lower fuel costs
- less defective material
- at appreciable savings

Prove these five points of superiority to your own satisfaction. Order a few cars of Baker's Magdolite, and see how maintenance and repair costs come down . . . in open hearth and electric furnace operations. The J. E. Baker Company, York, Pennsylvania.

Plants at Billmeyer, Pa. and Millersville, Ohio.



jects. Constant circulation of the paint is provided to minimize temperature drop in paint lines to the spray guns. Paint can be drawn



directly from the original paint container without the use of a pressure tank. Bede Products, Inc.
For more data insert No. 35 on postcard, p. 35.

Materials Handling Box

Permits rapid, efficient, economical supply of component parts to worker.

This functionally-designed parts box can be used by two workers as well as one, as parts are accessible from either end. Two or more units can be tiered, producing a compact, sturdy parts bin for loading at one end and withdrawing from the other. The standard

ed

or-

der ite, repen

era-

ny,

AGE



Nestier is 17½ x 9¼ x 5½ in. and constructed of 18-gage steel. Fifty-five units can be nested in a 5-ft stack. United Carriers & Fabricators, Inc.

For more data insert No. 36 en postcard, p. 35.

Air Line Respirator

Protects against dusts, fumes, vapors, mists, smokes, gases.

No filters or cartridges are needed for the air line respirator because a continuous flow of fresh



To meet Unitcast's standards, there is more than enough heat treating capacity to handle production. Because of Unitcast's and customer's requirements, these facilities are a necessity.

In heat treating, Unitcastings are grouped according to the grade of metal and thickness of cross section to assure meeting all physical requirements. And all Unitcastings are heat treated in this manner to insure better performance. Here's just one illustration of the many ways Unitcast's adequate plant facilities benefit you.

UNITCAST

QUALITY STEEL CASTINGS



Give us a chance to offer a "cast steel" answer for your parts problem. Our suggestions while your product is in the design stage will pay continuous dividends. Write or call today. Uniteast Corporation, Steel Casting Division, Toledo 9, Ohio. In Canada: Canadian-Uniteast Steel, Ltd., Sherbrooke, Quebec.

UNITCASTINGS ARE FOUNDRY ENGINEERED



NEW PRODUCTION IDEAS

Continued

vation Coppe on all Coppe Ohio. be the day of compa

100 p

satisfi They only 1 As the

the ar

are be

wil

No. 2

which

tons h

aroun

bee coke h

to \$17

at \$14

shi

tomer

the m

be inc

for ti

nuts,

10 pct

annou

Week

Dece

air is directed through the hose. Air flow to the facepiece is regulated by an adjustable valve clipped to the worker's belt or




clothing. The valve locks in position and cannot be accidentally changed. A detachable hose coupling at the junction of breathing tube and supply hose automatically shuts off air supply when detached. The assembly operates at air line pressure between 9 and 25 psi. American Optical Co.

For more data insert No. 37 on postcard, p. 35.

Centering Vise

Fast loading and unloading; both jaws open and close simultaneously.

A rugged compactly designed centering vise locates the center of the work at a desired point on the machine table, making the unit useful where outside dimensions of the work vary. The crank can be



used on either end. Jaws are 6 in. wide, 1½ in. high, and open to 6¼ in. V jaws are available to center round work. Graham Mfg. Co.

For more data insert No. 38 on postcard, p. 35.

Resume Your Reading on Page 39

THE IRON AGE

MARKET

FOUNDED 1888 MARKETS & PRICES

Briefs and Bulletins

scrap escalator — A scrap escalator clause, an innovation in steel scrap pricing, has been announced by Copperweld Steel Corp. It will appear as a separate item on all invoices, and be based on a scrap maximum which Copperweld will absorb, of \$38 per gross ton, Warren, Ohio. "The basis of computation for billing purposes will be the average commitments deliverable to us on the first day of each month, adjusted to the nearest dollar," the company said. The customer will pay the difference between \$38 and the cost of scrap, if it exceeds \$38. Purpose of the clause is to protect Copperweld, which uses a 100 pct scrap charge, against a runaway market in scrap.

warehouse sentiment—Some warehouse people aren't satisfied with the present system of warehouse allocations. They believe that a controlled materials plan will be the only means of assuring them an adequate steel supply. As things stand now, allocations and DO orders cut down the amount of free steel left on which their percentages are based.

y

p-

ly

d

1e

si.

35.

ly.

of

he

nit

of

be

in. 61/4 ter

39

GE

wildcats at Gary Works—The wildcat strike in the No. 2 openhearth shop at U. S. Steel Corp.'s Gary Works, which started on Dec. 2 is still in progress. Some 28,000 tons have been lost to date. Average daily loss is running around 3300 tons.

beehive coke—Price of Connellsville foundry beehive coke has advanced 50¢ per ton and is now quotable at \$17 to \$17.50. While some producers are asking higher prices for furnace beehive, the market generally is unchanged at \$14 to \$14.50.

shifting output—One steel producer has advised customers that production of blackplate will be cut out by the middle of next year so that production of tinplate can be increased. This is probably due to an increased demand for tinplate used in canning food.

nuts and bolts—Reflecting the increased cost of steel, nuts, bolts, rivets, and screws advanced approximately 10 pct in price effective Dec. 5.

silvery iron—Globe Iron Co. of Jackson, Ohio, has announced an increase of \$3 a ton for silvery iron, bringing the price to \$62.50 at Jackson.


freight cars—Orders for freight cars may reach 150,000 to 200,000 during 1951. It is expected that these will offset car retirements and raise car ownership to 1,850,000 by the middle of 1953.

eastern coke prices—Last week both Alan Wood Steel Co. and Philadelphia Coke Co. increased prices on all grades of coke 60¢ per ton. New prices for foundry coke are \$22.60 per net ton f.o.b. Swedeland, Pa., and \$22.70 per net ton f.o.b. Philadelphia.

spiegeleisen boost — New Jersey Zinc Co. has increased all grades of spiegeleisen at Palmerton, Pa., \$5 a ton. Price for 16-19 pct Mn at Palmerton is \$74, and for 19-21 pct Mn, \$75. Carnegie-Illinois prices at Pittsburgh and Chicago, are now \$75 for 16-19 pct Mn and \$76 for 19-21 pct Mn.

ferroalloy prices — Electro Metallurgical Co. has price changes in several ferroalloy products. New prices are: Ferro-tungsten, \$2.75; calcium-silicon, carload lots, 19¢ per lb; calcium-manganese-silicon, carload lots, 20¢ per lb; CMSZ, ton lots, 20.75¢ per lb.

Steel Operations**



District Operating Rates—Per Cent of Capacity**

-														
Week of	Pittsburgh	Chicago	Youngstown	Philadelphia	West	Buffale	Cleveland	Detroit	Wheeling	South	Ohio River	St. Louis	East	Aggregate
Dec. 3	98.0* 100.0	100.0° 104.0	85.0° 85.5	98.0	104.5 104.5	104.0 104.0	101.0*	106.0 106.0	101.0 101.0	106.0 104.0	95.0 67.0	90.5 98.5	100.5 103.5	109.5 101.5

^{-*} Revised.

** Steel operations for the first half of 1950 are based on annual capacity of 99,392,800 net tons. Beginning July 1, 1950, operations are based on new annual capacity of 310,563,800 net tons.

Nonferrous Metals outlook

Market Activities

New York—Producers and users of copper now have some recourse from the National Production Authority's order M-12 on copper consumption.

The Commerce Dept. now has on hand application forms for exemption or adjustment of this order. Order M-12 provides that any producer (under Form 11) or consumer (under Form 12) affected by any provision of the order may file on the grounds that: (1) His business operation was begun during or after the base period, (2) any provision of the order works an undue hardship on him not generally suffered by others in the same industry, or (3) enforcement against him would not be in the interest of national defense or in the public interest.

The copper import tariff is once again in the news. Representative James T. Patterson (R., Conn.) last week wrote a letter to Senate Finance Committee chairman Walter F. George (D., Ga.) calling for immediate consideration of the bill to suspend the copper tax until June 30, 1951.

Will Have to Be Re-introduced

He pointed out that if this is not done before the current session ends, the bill will have to be reintroduced at the next session and will again have to be passed by the House of Representatives.

Representative Patterson also indicated the paradoxical nature of the tax insofar as civilian consumption of copper has been restricted for next year and the metal is vital to the defense effort. Discrimination against Chile was also mentioned in the letter as being against our good neighbor policy.

Representative Patterson requests Senate consideration on copper tariff suspension . . . October aluminum output higher . . . NPA issues scrap copper restrictions.

Senator McFarland (D., Ariz.) has indicated that his stand against the suspension of the copper import tariff is unchanged and that he will continue to oppose the bill.

Domestic primary aluminum production during October totaled 125,830,495 lb, almost 6 pct ahead of the September output and about 2 million lb more than the third quarter average. Sheet and plate shipments during the month were 108,170,099 lb, according to the Aluminum Association. This total is somewhat under September shipments but it is some 3.5 million lb ahead of the third quarter average. Castings shipments were ahead of both September and third quarter averages.

Secondary brass and bronze ingot prices have not yet followed scrap prices in their nose-dive because the ingot makers are still getting material under contracts at the old prices. When they do start getting lower priced scrap, there is a chance that prices will not go down much because DO orders so far have hardly been felt by the ingot makers, and the civilian cutback order affects their customers' orders.

NPA early this week issued order M-16 which outlaws conversion of copper scrap without specific NPA approval. Inventories are also tightly restricted. (See page 130 for complete details of M-16.) It was anticipation of this order which caused copper and brass scrap prices to drop sharply last week.

65¢ 14, 24, 30,00 E1 11. Basse in., E2 weigh indicto 0 in., weigh indicto 0 E1 12. Constant of 15 33¢: 30,00 E1 11. Constant of 15 33¢: 31 in.

Stocks Show Increase

November statistics released by the American Zinc Institute show only slight changes from the previous month. Production totaled 79,226 tons, off slightly from October, and shipments were 79,079 tons, also a slight reduction from October. Stocks at hand at the end of the month showed an increase of 147 tons to a total of 9255 tons.

Daily average production of the zinc smelters was 2640 tons, the highest daily average in several years.

Lead users will be asking for a higher tonnage of that metal in January than December. It is anticipated that less lead will be available and suppliers will have to cut their customers again next month.

NONFERROUS METALS PRICES

Copper, electro, Conn. 24.50 Copper, Lake, delivered 24.62 Tin, Straits, New York 81.42 Zinc, East St. Louis 17.50 Lend, St. Louis 16.80 Note: Quotations are going prices.	24.50 3 24.625 81.40 17.50 16.80	Dec. 8 24.50 24.625 81.41 17.50 16.80	Dec. 9 24.50 24.625 17.50 16.80	Dec. 11 24.50 24.625 81.40 17.50 16.80	Dec. 15 24.50 24.02 81.43 17.50 16.50
---	--	--	---	---	--

^{*}Tentative.

Dec

sued ver-

ories

(See

s of this

and rply

d by show pretaled

1 Oc-9.079 from e end

rease

tons.

f the , the everal

for a al in s an-11 be

have next

Dec. 12 24.50 24.625 81.43 17.50 14.50

AGE

MILL PRODUCTS

(Cents per Ib, unless otherwise noted)

Aluminum

Aluminum

(Base 30,000 lb, f.o.b. ship. pt. frt. allowed)

Flat Sheet: 0.188 in., 25, 35, 30.1¢; 48, 618-0, 22¢; 528, 34.1¢; 248-0, 248-0AL, 32.9¢; 758-0, 758-0AL, 39.9¢; 0.081 in., 28, 38, 31.2¢; 48, 618-0, 23.5¢; 528, 35.6¢; 248-0 2.42-0AL, 34.1¢; 758-0, 758-0AL, 41.8¢; 0.32 in., 28, 38, 32.9¢; 48, 618-0, 37.1¢; 528, 39.8¢; 248-0, 248-0AL, 41.7¢; 758-0, 758-0AL, 52.2¢.

Plate: ¼ in. and heavier: 28, 38-F, 28.3¢; 48-7, 30.2¢; 538-F, 31.8¢; 618-0, 30.3¢; 248-0, 248-0AL, 32.4¢; 758-0, 758-0AL, 33.8¢.

Extruded Solid Shapes: Shape factors 1 to 5, 36.2¢ to 74.5¢; 12 to 14, 36.9¢ to 89¢; 24 to 26, 39.6¢ to 51.16; 36 to 38, 47.2¢ to 31.70.

Rod, Rolled: 1.5 to 4.5 in., 28-F, 38-F, 37.5¢ to 35.5¢; cold-finished, 0.375 to 3 in., 28-F, 38-F, 40.5¢ to 35¢.

Serew Machine Steck: Rounds, 118-T3, ½ to 11/32 in., 53.5¢ to 42¢; 75 to 1½ in., 41.5¢ to 39¢; 19/16 to 3 in., 38.5¢ to 36¢; 173-T4 lower by 1.5¢ per lb. Base 5000 lb.

Drawn Wire: Colled, 0.051 to 0.374 in., 28, 29.5¢ to 29¢; 528, 48¢ to 35¢; 868, 51¢ to 42¢; 178-T4, 54¢ to 57¢; 758-T6, 84¢ to 67.5¢.

Extruded Tubing, Rounds: 638-T5, OD in in: 1½ to 2, 87¢ to 54¢; 2 to 4, 33.5¢ to 45.5¢; 4 to 6.4¢ to 1.6¢; 6 to 9, 24.5¢ to 48.5¢.

Roeding Sheet, Flat: 0.019 in. x 28 in., per sheet, 72 in., \$1.142; 96 in., \$1.522; 120 in., \$1.902; 144 in., \$2.284. Gage 0.024 in. x 28 in., 22.9¢; 144 in., \$2.760. Colled Sheet: 0.019 in. x 28 in., 28.2¢ per lb.; 0.024 in. x 28 in., 26.9¢ per lb. (Base 30,000 lb, f.o.b. ship. pt. frt. allowed)

Magnesium

Magnesium

(F.o.b. mill, freight allowed)

Sheet and Plate: FS1-0, ¼ in. 63¢; 3/16 in. 65¢; ¼ in. 67¢; B & S Gage 10, 68¢; 12, 72¢; 14, 78¢; 16, 85¢; 18, 93¢; 20, \$1.05; 22, \$1.27; 24, \$1.67. Specification grade higher. Base: 30,000 lb.

Extruded Round Rod: M, diam in., ¼ to 0.811 in., 74¢; ½ to ¾ in., 87.5¢; 1¼ to 1.749 in., 53¢; 2½ to 5 in., 48.5¢. Other alloys higher. Base: Up to ¾ in. diam, 10,000 lb; ¾ to 2 in., 20,000 lb; 2 in. and larger, 30,000 lb.

Extruded Solid Shapes, Rectangles: M. In weight per ft, for perimeters less than size indicated, 0.10 to 0.11 lb. 3.5 in., 62.3¢; 0.22 to 0.25 lb, 5.9 in., 59.3¢; 0.50 to 0.59 lb, 8.6 in., 56.7¢; 1.8 to 2.59 lb, 19.5 in., 53.8¢; 4 to 6 lb, 28 in., 40¢. Other alloys higher. Base, in weight per ft of shape: Up to ½ lb, 10,000 lb; ½ to 1.80 lb, 20,000 lb; 1.80 lb and heavier, 20,000 lb.

Extruded Round Tubing: M, wall thickness, outside diam, in., 0.049 to 0.057, ¾ in. to 5/16, \$1.40; 5/16 to ¾, \$1.26; ¾ to ¾, 61¢; 1 to 2 in., 57¢; 3 to 4 in., 56¢. Other alloys higher. Base, OD in in.; Up to 1¼ in., 10,000 lb; 1½ in. to 3 in., 20,000 lb; 3 in. and larger, 30,000 lb.

Titanium

(10,000 lb. base, f.o.b. mill)

Commercially pure and alloy grades: Sheet and strip, HR or CR, \$15; Plate, HR, \$12; Wire, rolled and/or drawn, \$10; Bar, HR or forged, \$6; Forgings, \$6.

Nickel and Monel

(Base prices, f.o.b. mill)

										'A"	Nickel	Mone
Sheets,	cold-rolle	ьd	ı								69	53
Strip, c	old-rolled							Ì			75	56
Rods at	nd bars										65	51
Angles.	hot-rolled	1		1	•	•	•	*			65	51
Plates					•		۰	•	۰		67	52
Seamle	s tubes .			*	0	0	0	٥	0		98	9.6
Shot an	d blocks	4	0.	0		0	9	0	0	9	90	4.0

Copper, Brass, Bronze

(Freight prepaid on 200 lb includes duty)

			SANCE CHARGE
Commence of the second	Sheets	Rods	Shapes
Copper	41.03		40.63
Conner t -			
Copper, h-r		36.88	
Copper, drawn.		38.18	
Low brass	39.15	38.84	
Vellow harm			
Yellow brass	38.28	37.97	
Red brass	40.14	39.83	
Naval brass	43.08	38.61	38.07
THE TOTAL OF MANY	30.00		
Leaded brass		32.63	36,70
Com'l bronze	41.13	40.82	
Me Diviline			
Mang. bronze	45.96	40.65	41.41
Phos. bronze	60.20	60.45	
Munte matel			20.00
Munts metal	40.43	36.74	37.99
Ni silver, 10 net	49.27	51.49	
Arch. bronze			35.11
Dronze			35.11

PRIMARY METALS

REMELTED METALS

Brass Ingot

	115 .												0	4							29.00
																					28.5
	123						0				٠	0	0		0		0				28.00
80-10-	10 in	2	0	ŧ.																	
No.	305	-						0		0	0										35.00
No.	315			a																	32.0
88-10-	2 ins	0	t																		
No.	210															0					47.5
No.	215																				44.5
	245																				37.0
Yellov	v ing	ot							-			-			_	-		-	-	-	
	405							9													25.50
Manga											_	Î					-		-		
	421																				32.7

95-5 alun																		b	lots)
	p	p4	91		1	n	18	L	K.				0						33.75-34.25
Piston all No. 12 all	0	y	8	1		N	0		1	2	22		t	y	p	e)		
108 alloy			9				0	0											31.25-31.75
195 alloy												*	,	*	*				32.75-33.25
ASX-679						0													31.25-31.75

Steel deoxidizing aluminum, notch-bar granulated or shot

Grade	1-95-971/4	96									32.50-33.00
Grade	2-92-95%					0					30.75-31.50
	3-90-92%										30.00-30.50
Grade	4-85-90%	0	0	2		۰	0	0	0	0	29.50-30.00

ELECTROPLATING SUPPLIES

Anodes
(Cents per lb, freight allowed, 500 lb lots)

Copper	
Cast, oval, 15 in. or longer	39 1/6
Electrodeposited	33%
Rolled, oval, straight, delivered	38%
Forged ball anodes	43
Brass, 80-20	
Cast, oval, 15 in. or longer	34%
Zinc, oval	26 1/2
Ball anodes	25 1/2
Nickel 99 pct plus	
Cast	68.00
Rolled, depolarized	69.00 \$2.80
Cadmium	\$2.00
Silver 999 fine, rolled, 100 oz lots, per troy oz. f.o.b. Bridgeport.	
Conn	79 16
Comm	1072
Chemicals	
(Cents per lb, f.o.b. shipping point	(4)
Copper cyanide, 100 lb drum	52.15
Copper sulfate, 99.5 crystals, bbl	12.85
Nickel salts, single or double, 4-100	
lb bags, frt allowed	2014
Nickel chloride, 375 lb drum	271/2
Silver cyanide, 100 oz lots, per oz .	67 1/4
Sodium cyanide, 96 pct domestic	
200 lb drums	19.25
Zinc cyanide, 100 lb drums	45.85

SCRAP METALS

Brass Mill Scrap (Cents per pound, add 34¢ per lb for shipments of 20,000 to 40,000 lb; add 1¢ for more than 40,000 lb)

Copper						6		Heavy 23	Turn- ings 22 1/4
Yellow	brass							20 14	18%
Red bra								21 1/4	20%
Comm.								21 %	21
Mang. h								19 34	18%
Brass r								19%	

Dealers' Scrap
(Dealers' buying prices, f.o.b. New York
in cents per pound)

Aluminum crankcases 15 ½ -13

Aluminum crankcases 15 ½ -16

2S aluminum clippings 19 -19

Old sheet and utensils 15 ½ -16

Borlngs and turnings 13

Misc. cast aluminum 15 ½ -16

Dural clips (24S) 15 ½ -16

Nickel and Monel

| Magnesium | 9 -- 10 | Castings | 51/2 -- 61/2 |



SCRAP Iron & Steel

Formula Lid-Lifting Eases Scrap Pressure

Some of the steam that had been building up to a good head in scrap centers could be heard hissing away this week with last week's formula lid-lifting. Formula price bounds of from \$2.50 to \$6 for No. 1 heavy sent The Iron Age's scrap composite to a record high of \$45.08.

Unquestionably, the trade was much happier with the price rises but still a mutter could be heard. Some were wondering if the increases were enough. In Pittsburgh, reports of upgrading are already being heard. Detroit's gap between formula and free market scrap was narrowed, not closed.

Substantial tonnages of steel mill grades were moving in Cleveland and in the Valley and reportedly brokers were satisfied. It was expected that some upgrading will continue. Some judged formula increases as not enough but that they had taken the edge off any reluctance to sell. Birmingham mills refused to meet the new formula. Their area was raided.

PITTSBURGH—General reaction to the new price formula was "same old confusion at a higher level." With higher prices in effect less than a week, reports of upgrading are already being heard. On No. 2 bundles, an all-black bundle is bringing \$44.50, the formula for No. 2 heavy melting; the bundle formula of \$43.50 applies if the bundle contains galvanized. Apart from the mills' desire to compensate fabricators for higher finished steel prices, there is some thought here that the increase in the formula was in anticipation of possible government price controls. Machine shop and short turnings were up \$2.50 on the formula. Low Phos, railroad grades, and cast also rose.

CHICAGO—Scrap price increases were confirmed in the Chicago market last week. A major consumer came into the market for No. 1 heavy melting steel at \$45 per gross ton, No. 2 heavy melting at \$43, No. 2 dealers bundles at \$42, and short shoveling turnings at \$39. Some consumers are applying the new increases to unfilled old orders taken at the previous formula price. No. 1 heavy melting steel is still difficult to pick up at the new price. Low Phos and cast grades continued strong with some increases noted.

PHILADELPHIA—Big news this week is the increase in formula prices. The increase in this district was greater than expected and dealers and brokers are well satisfied with the new formula. No. 1 heavy melting and No. 1 bundles are up \$6, No. 2 heavy is up \$7, and No. 2 bundles registered at \$10 leap to a high of \$42 per gross ton. Blast furnace grades are \$2 to \$5 stronger this week and low phos is practically unchanged. Some of the cast grades also moved higher.

NEW YORK—Formula price increases on steelmaking grades may make collections larger. As one source put it: "There's no reason to hold back on scrap now." Big question is: How much scrap was being held back anyway? New formula prices are: No. 1, \$39.09; 2, \$37.09, No. 2 bundles, \$36.09. Cast grades were showing strength and were due for increases later this week.

DETROIT — Increases in the socalled scrap formula last week of as much as \$5.25 on electric furnace grades and \$2.75 on openhearth have narrowed but have not closed the gap between directed and free market scrap at Detroit. THE IRON AGE is continuing, therefore, the practice of showing both the formula price and a representative quotation for buying the same scrap grade in the open market. The formula is shown first. Under the new formula price structure \$2.50 more will be paid for the same grade of steel going to electric furnace plants. Meanwhile, the demand for scrap remains strong here and reports are increasing that government price controls are coming.

CLEVELAND — Substantial tonnages of steel mill grades are moving at the new formula prices here and in the Valley. Qualitatively, a lot of this tonnage leaves something to be desired, and some upgrading will probably continue. Some mills will probably not pay springboards on No. 2 bundles. Based on comments heard in the trade, the new formula is going to stick. The trade is satisfied.

ST. LOUIS—Two of the leading consumers in the St. Louis industrial district came into the market for sizable tonnages at the formula for delivery within the next 30 days. The movement of scrap has been slowed by cold weather in the producing territory. Some foundry grades are up from \$1 to \$2.

cincinnati—Scrap is being traded freely at new formula prices in a strong and demanding market here. District consumers are trying to build inventory but weather and high water are hampering scrap handling and shipments to some extent. Foundry grades are very strong. Quotations for steel mill grades are based on the formula less \$1 for switching and 75¢ for brokers' commission. Formula price for No. 1 heavy melting 18 446.

BOSTON—New formula prices hit this market on all cylinders. No. 1 heavy melting climbed from \$32.50 to \$35 but dealers were getting \$36 before the new increases. The market is very active. No. 2 heavy went to \$33.67 and No. 1 bundles to \$35. Other scrap showed increases of up to \$2.50.

BIRMINGHAM — The scrap market here is in a state of confusion and no scrap was bought or sold here this week of any consequence. Steel mills here are refusing to raise prices and pay the formula, while those in the North are doing so and drawing scrap from this district. Dealers and brokers say they cannot compete with northern buyers unless they can get a higher price.

BUFFALO—New business aggregating about 35,000 tons was placed by one of the leading mill consumers following the upward revision in the scrap market pricing formula. Price gains throughout the list ranged from \$1 to \$5.75 a ton. No. 1 heavy melting advanced \$3.25; No. 2 heavy melting, \$4.75; No. 1 bundles, \$4.25; No. 2 bundles, \$5.75.

Dec

37.09, Were r incalled

ch as \$2.75 have and IRON actice and a the . The new

ill be going e, the here vernnages

t the eaves e up-Some oards ments ila is sfied.

diswith-nt of ather undry

raded trong y but bering some trong. vitchssion.

elting

t this heavy 5 but new indles es of

arket week e are e for-e do-s disthey uyers

gating ne of g the narket ghout n. No. No. 2 \$4.25;

AGE



when stainless is the question

BUYERS of stainless scrap, straight chromes, nichrome, pure nickel, nickel alloys and Inconel



Iron and Steel

10:				
Pi	TTS	DL	ırq	П

No. 1 hvy. melting	44.00 to 46.00 to	44.50
No. 2 bundles	43.00 to 38.00 to 38.00 to 40.00 to 39.00 to	43.50 38.50 38.50 40.50 39.50
Low phos. plate Heavy turnings No. 1 RR. hvy. melting Scr.p rails, random leth. Rails 2 ft and under RR. steel wheels RR. spring steel RR. couplers and knuckles.	56.00 to 46.50 to 45.75 to 64.50 to 68.00 to 63.00 to 63.00 to	56.50 47.00 46.50 65.00 69.00 64.00 64.00
No. 1 machinery cast Mixed yard cast Heavy breakable cast Malleable	66.50 to 57.50 to 52.50 to 71.00 te	67.00 58.00 53.00 72.00

Chicago

No. 1 hvy. melting \$44.00 to \$45.00 No. 2 hvy. melting 42.00 to 43.00 No. 1 factory bundles 44.00 to 45.00 No. 1 dealers' bundles 44.00 to 45.00 No. 2 dealers' bundles 41.00 to 42.00 Machine shop turn 36.00 to 37.00 Mixed bor. and turn 36.00 to 37.00
Shoveling turnings 38.00 to 39.00
Cast iron car wheels 58.00 to 59.00 Malleable 72.00 to 75.00

Philadelphia

i illiaacipiita	
No. 1 hvy. melting \$44.00 to	\$45.00
No. 2 hvy. melting 42.00 to	43.00
No. 1 bundles 44.00 to	45.00
No. 2 bundles 41.00 to	42.00
Machine shop turn 31.00 to	32.00
Mixed bor. and turn 31.00 to	32.00
Shoveling turnings 36.00 to	
Low phos. punchings, plate 49.00 to	50.00
Low phos. 5 ft and under. 49.00 to	50.00
Low phos, bundles 47.00 to	48.00
Hvy. axle forge turn 44.00 to	45.00
Clean cast chem. borings 41.00 to	42.00
RR. steel wheels 53.00 to	54.00
RR. spring steel 53.00 to	54.00
Rails 18 in. and under 66.00 to	
No. 1 machinery cast 59.00 to	
Mixed yard cast 49.00 to	51.00
Heavy breakable cast 50.00 to	
Cast iron carwheels 67.00 to	
Malleable 69.00 to	

Cleveland

OIC TCIMIN		
No. 1 hvy. melting	45.25 to	\$46.00
No. 2 hvy. melting	43.25 to	44.00
No. 1 busheling	45.25 to	46.00
No. 1 bundles	45,25 to	46.00
No. 2 bundles	42.25 to	43.00
Machine shop turn	37.25 to	38.00
Mixed bor. and turn	39.25 to	40.00
Shoveling turnings	39.25 to	40.00
Cast iron borings	39.25 to	40.00
Low phos. 2 ft and under	47.75 to	48.50
Steel axle turn	44.25 to	45.00
Drop forge flashings	45.25 to	46.00
No. 1 RR. hvy. melting	46.00 to	46.50
Rails 3 ft and under	70.00 to	71.00
Rails 18 in. and under	72.00 to	73.00
No. 1 machinery cast	67.00 to	68.00
RR. cast	69.00 to	70.00
RR. grate bars	49.00 to	50.00
Stove plate	54.00 to	55.00
Malleable	73.00 to	74.00

Youngstown

			-						
No.	1 hvy.	melting					\$45.75	to	\$46.5
No.	2 hvy. n	nelting .		0	0		43.75	to	44.50
TAT -	9 harmal	a de					40 00	4-	40 00

SCRAP PRICES

Going prices as obtained in the trade by THE IRON AGE based on representative tonnages. All prices are per gross fon delivered to consumer unless otherwise noted.

No. 2 bundles							\$42.75	to	\$43.00
Machine shop turn	ı				0		37.75	to	38.50
Shoveling turnings							39.75	to	40.50
Cast iron borings .							39.75	to	40.50
Low phos. plate .		0	9				48.25	to	49.00

Buffalo

No. 1 hvy. melting	44.50 to	\$45.25
No. 2 hvy. melting	42.50 to	43.25
No. 1 busheling	42.50 to	43.25
No. 1 bundles	43.50 to	44.25
No. 2 bundles	41.50 to	42.25
Machine shop turn	36,50 to	37.25
Mixed bor, and turn	36.50 to	37.25
Shoveling turnings	38,50 to	39.25
Cast iron borings	36.50 to	37.25
Low phos. plate	48.25 to	49.00
Scrap rails, random lgth	55.00 to	56.00
Rails 2 ft and under	60.00 to	61.00
RR. steel wheels	60.00 to	61.00
RR. spring steel	60.00 to	61.00
RR. couplers and knuckles	60.00 to	61.00
No. 1 machinery cast	55.00 to	56.00
No. 1 cupola cast	52.00 to	53.00
Small indus. malleable	60.00 to	61.00

Birmingham

Dit illingingin			
No. 1 hvy. melting	39.00	to	\$40.00
No. 2 hvy. melting	35.00	to	36.00
No. 2 bundles	33.00	to	34.00
No. 1 busheling	38.00	to	39.00
Machine shop turn	31.00	to	32.00
Shoveling turnings	32.00	to	33.00
Cast iron borings	27.00	to	28.00
Bar crops and plate	46.00	to	47.00
Structural and plate	46,00	to	47.00
No. 1 RR. hvy. melting	43.00	to	44.00
Scrap rails, random lgth	58.00	to	59.00
Rerolling rails	61.00	to	62.00
Rails 2 ft and under	66.00	to	67.00
Angles & splice bars	59.00	to	60.00
Std. steel axles	61.00	to	62.00
No. 1 cupola cast	59.00	to	60.00
Stove plate	54.00	to	55.00
Cast iron carwheels	46.00	to	47.00

St. Louis

45.00 to	\$47.00
40.00 to	41.00
39.00 to	40.00
28,50 to	29.50
35.00 to	36.00
58.00 to	59.00
63.00 to	65.00
54.00 to	55.00
62.00 to	64.00
90.00 to	95.00
56.00 to	57.00
63.00 to	65.00
53.00 to	55.00
50.00 to	52.00
49.00 to	50.00
62.00 to	64.00
70.00 to	72.00
	45.00 to 40.00 to 39.00 to 28.50 to 35.00 to 58.00 to 63.00 to 54.00 to 62.00 to 90.00 to 56.00 to 56.00 to 56.00 to 60.00 to 60.00 to

New York

Brokers' Buying prices per gross ton,	on cars:
No. 1 hvy. melting	\$39.00
No. 2 hvy. melting	37.00
No. 2 bundles	36.00
Machine shop turn	31.00
Mixed bor, and turn	31.00
Shoveling turnings	
Clean cast chem. bor\$36.00	to 37.00
No. 1 machinery cast 48.00	to 49.00
Mixed yard cast 43.00	to 44.00
Charging box cast 43.00	to 44.00
Heavy breakable cast 43.00	to 44.00
Unstrp. motor blocks 38.00	to 39.00

Boston

Brokers'	Buying	prices	per	gress	ten,	on cars
No. 1 hv	y. melt	ing				\$35.00
No. 2 hv						33.67
No 1 hu	ndles					25 00

No. 2 bundles	\$32.67
Machine shop turn	27.00
Mixed bor. and turn	26.50
Shoveling turnings	29.00
No. 1 busheling	34.92
Clean cast chem. borings\$31.00 to	\$2.00
No. 1 machinery cast 47.00 to	48.00
Mixed cupola cast 44.00 to	45.00
Heavy breakable cast 41.00 to	42.00
Stove plate 42.00 to	43.00

Detroit

Brokers' Buying prices per gro	es ton, on cars:
No. 1 hvy. melting	40.25 to \$41.50
No. 2 hvy. melting	38.25 to 38.75
No. 1 bundles	40.25 to 46.00
New busheling	40.25 to 45.00
Flashings	40.25 to 41.50
Machine shop turn	32.25 to 32.75
Mixed bor. and turn	32.25 to 32.75
Shoveling turnings	34.25 to 34.75
Cast iron borings	34.25 to 34.75
Low phos. plate	42.75 to 46.00
No. 1 cupola cast	58.00 to 60.00
Heavy breakable cast	49.00 to 51.00
Stove plate	48.00 to 50.00
Automotive cast	62.00 to 64.00

Cincinnati

Ter Brone toni trent cars.	
	44.25
No. 2 hvy. melting	42.25
No. 1 bundles	44.25
No. 2 bundles, black	42.25
No. 2 bundles, mixed	41.25
Machine shop turn	33.00
Mixed bor, and turn	34.00
Shoveling turnings	34.00
Cast iron borings	34.00
Low phossteel	46.75
Low phos. 18 in. under	62.00
Rails, random lengths\$62.00 to	63.00
Rails, 18 in. and under 72.00 to	73.00
	66.00
No. 1 cupola cast 65.00 to	
Hvy. breakable cast 59.00 to	60.00
Drop broken cast 71.00 to	72.00

San Francisco

	30.00
No. 2 hvy. melting	28.00
No. 1 bundles	30.00
No. 2 bundles	28.00
	25,00
Machine shop turn	16.00
Elec. fur. 1 ft and under \$40.00 to	42.50
	30.00
Scrap rails random lgth	30.00
No 1 cunola cast 42 00 to	46 00

Los Angeles

No. 1 hvy. 1	nel	ti	ng												\$30.00
No. 2 hvy. r	nel	ti	ng					1							28.00
No. 1 bundle	88						4								30.00
No. 2 bundle	38														28.00
No. 3 bundle	98														25.00
Mach. shop	tur	n.													16.00
Elec. fur. 1	ft	aı	be	u	n	d	e	r.	. 1	84	2	Ô	0	to	45.00
No. 1 RR. h															30.00
Scrap rails,															30.00
No. 1 cupols															52.00

Seattle

No. 1 hvy. melting	\$28,00
No. 2 hvy. melting	22.00
No. 1 bundles	
No. 3 bundles	18.00
Elec. fur. 1 ft and under\$40.00 to	45.00
RR. hvy. melting	29.00
No. 1 cupola cast	45.00

Hamilton, Ont.

Hamilton, O	MY.	
No. 1 hvy. melting		\$30.00
No. 1 bundles		30.00
No. 2 bundles Mechanical bundles		28.00
Mixed steel scrap		26.00
Mixed bor. and turn		23.00
Rails, remelting		30.00
Rails, rerolling		33.00 24.50
Bushelings		29.00
Bush., new fact, unprep'd.		23.00
Short steel turnings		23.00
Cast scrap		45.00

LU


LEB. DI MOD

LE

Dece

For the Purchase or Sale of Iron and Steel Scrap ...

CONSULT OUR NEAREST OFFICE



The energy and integrity of our organization is ready to serve your best interests ... Since 1889, Luria Brothers & Company, Inc. have made fair dealings their constant aim.

CONSULT OUR NEAREST OFFICE FOR THE PURCHASE AND SALE OF SCRAP

LURIA BROTHERS AND COMPANY, INC.

Main Office LINCOLN-LIBERTY BLDG. Philadelphia 7, Pennsylvania

Hands

.00

.00 .00 .00 .00 .00 .00 .00 .00

50

LEBANON, PA. • READING, PA. DETROIT (ECORSE), MICH. MODENA, PA. • PITTSBURGH, PA. ERIE, PA.



Empire Blug. BOSTON, MASS.

Branch Offices BIRMINGHAM, ALA. CHICAGO, ILL. HOUSTON, TEXAS PITTSBURGH, PA. Officer Bidg. 100 W. Monroe St. 1114 Texas Av. Bidg. Officer Bidg. 100 W. Monroe St. 1114 Texas Av. Bidg. Officer Bidg. 2014 Officer Bidg. 334 Colorado Bidg. 334 Colorado Bidg. 334 Colorado Bidg. LEBANON, PA.

NEW YORK, N.Y.

LEADERS IN IRON AND STEEL SCRAP SINCE 1889

December 14, 1950

Comparison of Prices

Steel prices in this page are the average of various f.o.b. quotations of major producing areas: Pittsburgh, Chicago, Gary, Cleveland. Youngstown.

Unicago, Gary, Cleveland,	loungs	town.		
Flat-Rolled Steel: (cents per pound) Hot-rolled sheets Cold-rolled sheets Galvanized sheets (10 ga) Hot-rolled strip Cold-rolled strip Plate Plate Plates wrought iron	Dec. 12, 1950 3.60 4.35 4.80 3.50 4.75 3.70 7.85		Nov. 14, 1950 3.35 4.10 4.40 3.25 4.21 3.50 7.85 34.50	Dec. 13 1949 3.25 4.00 4.40 3.25 4.038 3.40 7.85 33.00
Stains C-R-strip (No. 302) Tin and Terneplate: (dollars per base box) Tinplate (1.50 lb) cokes. Tinplate, electro (0.50 lb) Special coated mfg. ternes	\$7.50 6.60	\$7.50	\$7.50 6.60 6.35	\$7.75 6.70 6.65
Gents per pound) Merchant bars Cold finished bars Alloy bars Structural shapes Stainless bars (No. 302). Wrought iron bars	4.55 4.30 3.65 31.25	3.70 4.55 4.30 3.65 31.25 9.50	3.45 4.15 3.95 3.40 30.00 9.50	3,35 3,995 3,75 3,25 28,50 9,50
Wire: (cents per pound) Bright wire	4.85	4.85	4.50	4.15
Rails: (dollars per 100 lb) Heavy rails Light rails		\$3.60 4.00	\$3.40 3.75	\$3.20 3.55
Semifinished Steel: (dollars per net ton) Rerolling billets Slabs, rerolling Forging billets Alloy blooms billets, slabs	\$56.00 56.00 66.00	\$56.00 56.00 66.00 70.00	\$54.00 54.00 63.00 66.00	\$52.00 52.00 61.00 63.00
Wire Rod and Skelp: (cents per pound) Wire rods	4.10 3.35	4.10	3.85 3.15	3.40 3.25

Price advances over previous week are printed in Heavy Type: declines appear in Italics

Pig Iron:	Dec. 12,	Dec. 5,	Nov. 14,	Dec. 13
(per gross ton)	1950	1950	1950	1949
No. 2, foundry, del'd Phila.	57.77	\$56.27	\$54.77	\$50.42
No. 2, Valley furnace	52.50	51.00	49.50	46.50
No. 2, Southern Cin'ti	55.58	55.58	. 52.58	46.08
No. 2, Birmingham	48.88	48.88	45.88	39.38
No. 2, foundry, Chicagot.	52.50	52.50	49.50	46.50
Basic del'd Philadelphia	56.92	55.42	53.92	49.92
Basic, Valley furnace	52.00	50.50	49.00	46.00
Malleable, Chicagot	52.50	52.50	49.50	46.50
Malleable, Valley	52.50	52.50	49.50	46.50
Charcoal, Chicago	70.56	70.56	70.56	68.56
Ferromanganese‡	181.20	181.20	178.60	173.40

†The switching charge for delivery to foundries in the Chicago district is \$1 per ton.

‡Average of U. S. prices quoted on Ferroalloy page.

In Me lig

ins

Dece

Scrap:

(per gross ton)			
Heavy melt'g steel, P'gh \$46.25	\$43.75	\$43.75	\$30.75
Heavy melt'g steel, Phila. 44.50	38.75	38.75	24.50
Heavy melt'g steel, Ch'go 44.50	39.75	39.75	26.50
No. 1 hy. com. sh't, Det 43.13	41.25	39.75	26.50
Low phos. Young'n 48.63	46.25	46.25	32.75
No. 1 cast, Pittsburgh 66.75	62.75	60.75	39.50
No. 1 cast, Philadelphia 59.50	56.50	55.50	38.00
No. 1 cast, Chicago 65.00	63.00	60.50	39.50

Coke: Connellsville:

		at oven)			
Furnace	coke,	prompt\$14.25	\$14.25	\$14.25	\$14.00
Foundry	coke.	prompt 17.25	16.75	16.75	15.75

Nonferrous Metals:

(cents per pound to lar	ge buye	rs)		
Copper, electro, Conn	24.50	24.50	24.50	18.50
Copper, Lake, Conn	24.625	24.625	24.625	18.625
Tin Straits, New York	\$1.43†	\$1.395*	\$1.375	79.00
Zinc, East St. Louis	17.50	17.50	17.50	9.75
Lead, St. Louis	16.80	16.80	16.80	11.80
Aluminum, virgin	19.00	19.00	19.00	17.00
Nickel, electrolytic	51.22	51.22	51.22	42.97
Magnesium, ingot	24.50	24.50	24.50	20.50
Antimony, Laredo, Tex	32.00	32.00	32.00	32.00
†Tentative. *Revised.		1.50	-	

Starting with the issue of May 12, 1949, the weighted finished steel composite was revised for the years 1941 to date. The weights used are based on the average product shipments for the 7 years 1937 to 1946 inclusive and 1946 to 1948 inclusive. The use of quarterly figures has been eliminated because it was too sensitive. (See p. 130 of May 12, 1949, issue.)

Composite Prices

		Steel B			
Dec.	12, 1950	4.13	1¢ per	lb	
One	week ago	4.13	1¢ per	lb	

High		Low	
One year ago3.705¢	per	lb	L,
One month ago3.837¢	per	lb	
One week ago4.131¢	per	lb	
Dec. 12, 19504.131¢			

	High	Lo	w
1950	4.131¢ Dec.	1 3.837e	Jan. 3
1949	3.837¢ Dec. 2	27 3.3705	May 3
1948	3.721¢ July 2		
1947	3.193¢ July 2	29 2.848€	Jan. 1
1946	2.848¢ Dec. 3	31 2,464¢	
1945	2.464¢ May 2	29 2.396€	
1944	2.396¢	2.396	id.
1943	2.396¢	2.396	é
1942	2.396¢	2.396	é
1941	2.396¢	2.396	ė .
1940	2.30467¢ Jan.	2 2.24107¢	Apr. 16
1939	2.35367¢ Jan.		
1938	2.58414¢ Jan.	4 2.27207¢	Oct. 18
1937	2.58414¢ Mar.	9 2.32263¢	Jan. 4
1936	2.32263¢ Dec. 2	28 2.05200¢	Mar. 10
1935	2.07542¢ Oct.	1 2.06492€	Jan. 8
1932	1.89196¢ July	5 1.83910€	Mar. 1
1929	2.31773¢ May 3	28 2.26498¢	Oct. 29
8.	Weighted index hapes, plates, wir- nd cold-rolled sh- enting major por hipment. Index 8, 1941, issue and	e, rails, black eets and strip rtion of finish recapitulated	pipe, hot bs, repre- hed steel in Aug.

C 100 .	ensitive, (see p.	100 or may 12, 104	o, made.,
Pig I	ron	Scrap	Steel
\$52.69 per	gross ton	\$45.08 per	
51.94 per		40.75 per	gross ton
49.69 per	gross ton	40.75 per	gross ton
45.88 per	gross ton	27.25 per	gross ton
High	Low	High	Low
\$52.69 Dec. 12	\$45.88 Jan. 3	\$45.08 Dec. 12	\$26.25 Jan. 8
46.87 Jan. 18	45.88 Sept. 6	43.00 Jan. 4	19.33 June 28
46.91 Oct. 12	39.58 Jan. 6	43.16 July 27	39.75 Mar. 9
37.98 Dec. 30	30.14 Jan. 7	42.58 Oct. 28	29.50 May 20
30.14 Dec. 10	25.37 Jan. 1	31.17 Dec. 24	19.17 Jan. 1
25.37 Oct. 23	23.61 Jan. 2	19.17 Jan. 2	18.92 May 22
\$23.61	\$23.61	19.17 Jan. 11	15.76 Oct. 24
23.61	23.61	\$19.17	\$19.17
23.61	23.61	19.17	19.17
\$23.61 Mar. 20	\$23.45 Jan. 2	\$22.00 Jan. 7	\$19.17 Apr. 10
23.45 Dec. 23	22.61 Jan. 2	21.83 Dec. 30	16.04 Apr. 9
22.61 Sept. 19	20.61 Sept. 12	22.50 Oct. 3	14.08 May 16
-23.25 June 21	19.61 July 6	15.00 Nov. 22	11.00 June 7
32.25 Mar. 9	20.25 Feb. 16	21.92 Mar. 30	12.67 June 9
19.74 Nov. 24	18.73 Aug. 11	17.75 Dec. 21	12.67 June 8
18.84 Nov. 5	17.83 May 14	13.42 Dec. 10	10.33 Apr. 29
14.81 Jan. 5	13.56 Dec. 6	8.50 Jan. 12	6.43 July 5
18.71 May 14	18.21 Dec. 17	17.58 Jan. 29	. 14.08 Dec. 8
Based on average	s for basic fron	Average of No.	
at Valley furnaces at Chicago, Phila	and foundry iron	at Pittsburgh, Phil	ed to consumers
Valley and Birming	ham.	cago.	and print and Con-
	3 3 5 6 5	The state of the s	and the same of

27.25 per	gross ton
High	Low
\$45.08 Dec. 12	\$26.25 Jan. 8
43.00 Jan. 4	19.33 June 28
43.16 July 27	39.75 Mar. 9
42.58 Oct. 28	29.50 May 20
31.17 Dec. 24	19.17 Jan. 1
19.17 Jan. 2	18.92 May 22
19.17 Jan. 11	15.76 Oct. 24
\$19.17	\$19.17
19.17	19.17
\$22.00 Jan. 7	\$19.17 Apr. 10
21.83 Dec. 30	16.04 Apr. 9
22.50 Oct. 3	14.08 May 16
15.00 Nov. 22	- 11.00 June 7
21.92 Mar. 30	12.67 June 9
17.75 Dec. 21	12.67 June 8
13 42 Dec 10	10 33 Apr 29
8.50 Jan. 12	6.43 July 5
17.58 Jan. 29	. 14.08 Dec. 8
Average of No.	1 heavy melting
steel scrap deliver at Pittsburgh, Phil	red to consumers
cago.	maethurik una Cur.
7	



13

0

0

0

hi-

0

0

00

625

80

00

97

50

00

. . .

. . .

28

20

22

24

10

16

29

750

Indications brought out by Magnaglo, glow under black light to clearly disclose a nonvisible crack in car axle at wheel fit.



Magnaglo brings out a fluorescent indication, to locate typical crack in pinion gear of railroad diesel drive.



Zyglo brilliantly reveals cracks and poor bonding in these cutting tools. This method, like others employed with Magnaflux equipment is non-destructive and fast.



Luminous pattern by Magnaglo outlines forging crack in connecting rods shown above. Visual inspection would have missed this defect.

DEPEND ON ** DEPEND ON ** For Fast, Accurate, Non-Destructive Testing of Metals, Non-Ferrous Materials and Ceramics

PUT MAGNAFLUX* TO

ONE OR MORE OF THESE MANY USES

MAGNETIC METAL PRODUCTS

Use Magnaflux equipment to inspect welded, cast, forged, or rolled parts—Magnaglo where bright fluorescent indications speed inspection.

ULTRASONIC TESTING

Use Magnaflux-Sonizon for thickness measurement and location of defects.

CERAMICS TESTING

Use Statiflux for testing glass and glazed products. Use Partek on porous or unfired materials.

NON-MAGNETIC METALS

Use Zyglo to establish quality control on the production line or during overhaul.

STRESS ANALYSIS

Use Stresscoat where entire parts are tested for strain distribution under load or in use.

PLASTICS TESTING

Use Zyglo to find non-visible cracks that contribute weak-


RAILROAD CARS, DIESELS and STEAM

Use Magnaflux-Magnaglo or Zyglo for checking every critical part.

ENGINEERED INSPECTION

Available for testing at production line speeds.

Magnaflux* equipment in a great
variety of applications, shows up
defects in a wide variety of
materials. Whether cracks are
caused by heat, fatigue, or
corrosion, Magnaflux* locates
and defines each defect clearly
and in its entirety...at lowest
cost and at production line
speed. The result is
immediately visible. Write
for detailed information
on your specific inspection
problem.





Reg. U.S. Pat, Office

Magnaflux, Magnaglo, Zyglo: trademarks (Reg. U.S. Pat. Off.) of the Magnaflux Corporation applied to equipment and materials for use with magnetic particle and fluorescent penetrant inspection methods.

MAGNAFLUX CORPORATION

5902 Northwest Highway

Chicago 31, Illinois

Originators of MAGNAFLUX . MAGNAGLO . ZYGLO . DUOVEC . PARTEK

STEEL	Base prices a	nated. E	utras ap											
PRICES	Pittsburgh	Chicago	Gary	Cleve- land	Canton Mas- aillen	Middle- town	Youngs- town	Bethio- hom	Buffalo	Ganaha- hacken		Spar- rewa Point	Granite City	Detro
INGOTS Carbon forging, net ton	\$82.001				M	911								
Alloy, net ten	\$54.001-17								THE					\$54.00
BILLETS, BLOOMS, SLABS Carbon, rerolling, net ten	\$58.001.5	\$56.001	\$58.00 ¹						\$56.00°		358.001			-
Carbon forging billets, not ten	\$88.001.5	\$66.001.4	\$68.001	\$86.004	\$86.004				\$86.003	\$73.0030	\$86.001			\$89.00
Alloy, net ton	\$70.001 -17	\$70.001-4	\$70.001		\$70.004			\$70.003	\$70.003	\$77.0026	\$70.00*			\$73.00
PIPE SKELP	3.35 ¹ 3.45 ⁵						3.351 -4							
WIRE RODS	4.10 ² 4.30 ¹⁸	4.109.4.83	4.104	4.102			4.106				4.103	4.201		
SHEETS Hot-relied (18 ga. & hvr.)	3.601 · 5 · 9 · 1 6 3.7528	3.6(*-23	3.601.6.8	3.604		3.607	3.601 -4 -8 4.0013		3.603	4.0028		3.803		3.80 ¹² 4.40 ⁴⁷
Cold-rolled	4.381.8.9.18 5.35 ⁶³		4.351 -6.8	4.354		4.357	4.354.4		4.353			4.353		4.5812
Galvanized (10 gage)	4.801.0.18		4.801.6		4.804	4.807	6.00*4					4.80*		
Enameling (12 gage)	4.651		4.881.8			4.857								
Long ternes (10 gage)	5.209.18						6.0064							
Hi str. low alloy, h.r.	5.401 · 5 5.759	5.401	5.401 -s 5.906	5.404			5.401 -4 - 1.3		5.403	5.0530		5.403		
Hi etr. low alloy, c.r.	8.55 ^{1.8} 6.90 ⁹		8.551 -8 7.056	8.554			6.554		6.553			8.553		
Hi str. low alloy, galv.													-	
STRIP Hot-relied	3.809 · 4.0043 3.7528 3.806	3.50**	3.501.6.8			3.507	3.501 · 4 · 6 4.0019		3.502-4	3.9034		3.502		4.4047
Cold-rolled	4.655.0 5.0028 5.35 ^{6.3}	4.964.65	4.9C ⁸	4.652		4.857	4.65 ^{4.4} 5.35 ¹³		4.653			4.653		5.4647 5.80 ⁶⁸ 5.80 ⁸¹
Hi str. low alloy, h.r.	5.789		5.501 5.3085.806				4.954, 5.50 ¹ 5.40 ¹³			5.5524				
Hi str. low alloy, c.r.	7.209			8.705			6.204, 6.5513						-	
TINPLATE† Cokes, 1.50-ib base box 1.28-ib, deduct 20¢	\$7.501 -5 -0 - 15		\$7.801 -6.8				\$7.504					7.803	\$7.7022	
Electrolytic 0.25, 0.50, 0.75 lb bex				Deduct 1	\$1.15, 90¢	and 65¢ r	respectively from	m 1.50-lb	coke base	e box price				
BLACKPLATE, 29 gage Hollowware enameling	5.85 ¹ 6.15 ^{1.5}		5.881				5.304			1			1	
BARS Carbon steel	3.701 · 5 3.85°	3.701 -4.23	3.701 -4-6-8	3.704	3.704		3.701 -4-6		3.702-4		3.70°			3.85 ³¹ 4.70 ⁸⁴
Reinforcing:	3.701 -5	3.704	3.701.4.8	3.704		-	3.701 -4		3.703-4		3.703	3.70*		
Cold-finished	4,552.4.5. 82.49.71	4,552.66.70.	4.5574.73	4.552	4.554									
Alloy, het-relied	4.301-17	4.301 -4 -93	4.301 -6 -8		4.304		4.301 -6	4.300	4.308-4		4.303			4.4521
Alloy, cold-drawn	5.40 ^{17.82} .	5.404-69	5.40 ⁴ 5.90 ^{7 4}		8.404			5.400	5.40 ^a					5.55*
Hi str. lew alloy, h.r.	5.551 -8		5.551 · 6 6.058	5.554			5.881	5.852	8.553		5.553			
PLATE Carbon eteel	3.701-5-15	3.701	3.701.4.8	3.70 ⁴ 4.00°			3.701 · 4 3.951 s		3.708	4.1526	3.702	3.700		
Floor plates			4.768	4.755						4.7826				
Alloy	4.751	4.751	4.751				5.2013			5.0526	4.783	4.753		
Hi str. low alloy	5.651 - 6	8.681	5.651 -6	5.854.5			5.68 ⁴ 8.70 ¹³			5.9024	8.682	5.653		
SHAPES, Structural	3.65 ^{1 - 5} 3.90°	3.851-39	3.051 -8				6.0	3.700	3.703		3.703			
HI str. lew alloy	6.501 -8	8.501	5.501 -8					5.503	5.503	-	5.503			
MANUFACTURERS' WIRE	4,853.4	4,853		4.852				Kokomi	m = 5.8030		4.853	4.851	Duluti	h-4.85
Bright PILING, Steel Sheet	4.451	4.83	4.458			-	-		4.451			-	-	1

De

	Prices	are in cer	Indicate producing companits per ib unless otherwise	noted. Extras apply.	STEEL
Kanasa City	Houston	Birm- ingham	WEST COAST Seattle, San Francisco, Lee Angelee, Fontana		PRICES
			F=\$79.0019		INGOTS carbon forging, net ton
	\$82.0003		F=\$80.0019		Alloy, net ton
		\$56.001	F=\$75.0019		BILLETS, BLOOMS, SLABS
	\$74.0083	388.001			Carbon, rerolling, net ton Carbon forging billets, net
	\$78.00 ⁸³		SF, LA, S=\$85.0019.62 F=\$89.0019		
	***************************************		7 - 400.00		Alloy not ton
	1		SF=4,90 ²⁴ LA=4.90 ^{24.67}		PIPE SKELP
	4.5083	4.104-11		Worcester = 4.40 ²	WIRE RODS
		3.804-11		Niles = 5.25*4, Geneva = 3.70**	SHEETS
		4.3511	SF = 5.3024		Hot-rolled (18 ga, & hvr.) Cold-rolled
			F=5.2819		
		4.804. 11	SF, LA=5.85 ²⁴	Ashland =4.80°	Galvanized (10 gage)
					Enameling (12 gage)
					Long ternes (10 gegs)
			F=6.3519		Hi str. low alloy, h.r.
			F=7.4019		Hi str. low alloy, c.r.
					Hi etr. low alloy, galv.
4.1663	3.900	3.504	8F, LA=4.25 ²⁴⁻⁶² F=4.65 ¹⁹ , S=4.50 ⁶²	Atlanta = 4.05°5 Minnequa = 4.85°4	STRIP Hot-rolled
			F=6.2510 LS=6.40 ²⁷	New Haven = 5.15 ² , 5.85 ^{6.6}	Gold-rolled
					Hi str. low alloy, h.r.
					Hi str. low alloy, c.r.
		7.8011	SF=8.28 ²⁴		TINPLATE Cokes, 1.50-lb base box 1.25 lb, deduct 20¢
ı	Deduct \$1.	16, 90¢ aı	nd 65¢ respectively from 1.5	50-lb coke base box price	Electrolytic 0.25, 0.50, 0.75 ib box
					BLACKPLATE, 29 gage Hollowware enameling
£3083	4.1088	3.704	SF, LA=4.4094	Atlanta = 4.25#5 Minnequa = 4.1514	BARS Carbon steel
1.3061	4.1083	3.704-	SF, S=4.4562 F=4.3519	Atlanta = 4.20°5 Minnegua = 4.50°4	Reinforcing:
				Putnam, Newark = 4,9559	Cold-finished
				Hartford = 5.104 Les Angeles = 6.004	
f.90sz	4.7083		LA=5.3862 F=5.3019		Alloy, hot-rolled
				Newark = 5.70** Worcester = 2 Hartford = 5.85*	Alloy, sold-drawn
			F-8.8019		HI str. low alloy, h.r.
	4.1003	3.704	F=4.3010 S=4.6062 Geneva=3.7016	Claymont = 4.1529 Coatseville = 4.1521	PLATE Carbon steel
					Floor plates
			F=5.7519	Coateoville=5.25 ²¹	Alloy
			F=6.2519		Hi str. low alloy
1,2583	4.0893	3.054.11	SF=4.20*1 LA=4.2524.42	Genova 3.6516 Minnequa 4.1014	SHAPES, Structural
			F=4.2519		Hi etr. low-alley
			3=4.30 ^{6.2}		

KEY TO STEEL PRODUCERS

With Principal Offices

I Carnegia-Illinois Steel Carp., Pittsburgh
American Steel & Wire Co., Cleveland
Bethlehem Steel Corp., Cleveland
Jones & Laughlin Steel Carp., Pittsburgh
Youngstown Sheet & Tube Co., Youngstown
Armco Steel Corp., Middletown, Ohio
Inland Steel Co., Chicage
Weirton Steel Co., Weirton, W. Ya.
National Tube Co., Pittsburgh
Tannessee Coal, Iron & R. R. Co., Birmingham
Graet Lakes Steel Corp., Detroit
Sharon Steel Corp., Sharon, Pa.
Colorado Fuel & Iron Corp., Denver
Weiling Steel Corp., Wheeling, W. Ya.
Geneva Steel Co., Salt Lake City
Crucible Steel Co., Gath Lake City
Crucible Steel Co., Fittsburgh
Kaiser Steel Co., Salt Lake City
Crucible Steel Co., Gatherica, New York
Pittsburgh Steel Co., Fittsburgh
Kaiser Steel Co., Coatesville, Po.
Granite City Steel Co., Granife City, Ill.
Wisconsin Steel Co., South Chicago, Ill.
Columbia Steel Co., South Chicago, Ill.
Columbia Steel Co., Glassport, Pa.
Alan Wood Steel Co., Glassport, Pa.
Alan Wood Steel Co., Conshohocken, Pa.
Calif. Cold Rolled Steel Corp., Les Angeles
Allegheny Ludium Steel Corp., Les Angeles
Allegheny Ludium Steel Corp., Les Angeles
Allegheny Ludium Steel Corp., Hokomo, Ind.
Rotary Electric Steel Co., Petroit
Laclede Steel Co., Claymont, Del.
Continental Steel Corp., Kokomo, Ind.
Rotary Electric Steel Co., Detroit
Carpenter Steel & Wire Co., Peorle, Ill.
Scantral Steel & Wire Co., Peorle, Ill.
Scantral Steel & Wire Co., Peorle, Ill.
Scantral Steel & Wire Co., Baltimore
Washington Steel Corp., Baltimore
Washington Steel Corp., Baltimore
Washington Steel Corp., Carnegie, Pa.
Jessop Steel Co., Washington, Pa.
Jessop Steel Co., Washington, Pa.
Jessop Steel Co., Washington, Pa.
Superior Steel & Tube Div., Canton, Ohio
Babcock & Wilcox Tube Co., Beaver Falls, Pa.
Keysons Steel Corp., Detroit
Cold Metal Products Co., Fitchburg, Mass.
Firth Sterling Steel & Corp., Detroit
Cold Metal Products Co., Chicago
Sweet's Steel Co., Williamsport, Pa.
Singerior Steel Co., Warren, Ohio
Wilson Steel & Wire Co., Chicago
Sephoenis Iron & Steel Co., Phoe With Principal Offices 54 Firth Sterling Steel & Carbide Corp., McKeesport, Pa.
55 Ingersoil Steel Div., Chicago
56 Phoenix Iron & Steel Co., Phoenixville, Pa.
57 Fitzsimmons Steel Co., Youngstown
58 Stanley Works, New Britain, Conn.
59 Universal-Cyclops Steel Corp., Bridgeville, Pa.
40 American Cladmetals Co., Carnegle, Pa.
41 Cuyahoga Steel & Wire Co., Cleveland
42 Bethlehem Pacific Coast Steel Corp., San
Francisco 41 Cuyahoga Steel & Wire Co., Cleveland
42 Bethlehem Pacific Coast Steel Corp., San
Francisco
43 Follansbee Steel Corp., Pittsburgh
44 Niles Rolling Mill Co., Niles, Ohio
45 Atlantic Steel Co., Atlanta
46 Acme Steel Co., Chicago
47 Joslyn Mfg. & Supply Co., Chicago
48 Detroit Steel Corp., Detroit
49 Wyckoff Steel Co., Pittsburgh
70 Bliss & Laughlin, Inc., Harvey, Ill.
71 Columbia Steel & Shafting Co., Pittsburgh
72 Cumberland Steel Co., Chicago
73 La Selle Steel Co., Chicago
74 Monarch Steel Co., Chicago
75 Mohoning Yalley Steel Co., Niles, Ohio
76 Mohoning Yalley Steel Co., Pittsburgh
77 Diliver Iron & Steel Co., Pittsburgh
78 Pittsburgh Screw & Belt Co., Pittsburgh
79 Standard Forging Corp., Chicago
80 Driver Harris Co., Harrison, N. J.
81 Detroit Tube & Steel Div., Detroit
82 Reliance Div., Eaton Mfg. Co., Massilion, Ohio
83 Sheffield Steel Corp., Kanses City
84 Piymeuth Steel Co., Detroit
85 Wickwire Spencer Steel, Buffalo
86 Angell Noll and Chaplet, Cleveland
87 Mid-States Steel & Wire, Crawfordsville, Ind.
88 National Supply, Toledo, Ohie
89 Wheatland Tube Co., Wheatland, Pa.
90 Mercer Tube & Mfg. Co., Sharen, Pa.

1.0001

1.0031

041

147

B1 B4

31

3

STAINLESS STE	FF2							oducing		poune,	
Product	301	302	303	304	316	321	347	410	416	430	
Ingota, rérolling	14.25	15.00	16.50	16.00	24.25	19.75	21.50	12.75	14.75	13.00	
Slabs, billets rerolling	18.50	19.75	21.75	20.75	31.75	26.00	28.25	16.50	20.00	16.75	
Forg. discs, die blocks, rings.	34.00	34.00	38.50	35.50	52.50	40.00	44.50	28.00	28.50	28.50	
Billets, forging	28.25	26.25	28.25	27.50	41.00	31.00	34.75	21.50	22.00	22.00	
Bars, wires, structurals,.	31.25	31.25	33.75	32.75	48.75	36.75	41.25	25.75	26.25	28.25	
Plates	33.00	33.00	35.00	35.00	51.50	40.50	45.00	27.00	27.50	27.50	
Sheets,	41.00	41.00	43.00	43.00	56.50	49.00	53.50	36.50	37.00	39.00	-
Strip, hot-relied	26.50	28.00	32.25	30.00	48.25	36.75	41.00	23.50	30.25	24.00	
Strip, cold-rolled	34.00	36.50	40.00	38.50	58.50	48.00	52.00	30.50	37.00	31.00	

STAINLESS STEEL PRODUCING POINTS—Sheets: Midland, Pa., 17; Brackenridge, Pa., 28; Butler, Pa., 7; McKeesport, Pa., 1; Washington, Pa., 38 (type 316 add 5¢), 39; Baltimore, 37; Middletown, Ohio, 7; Massillon, Ohio, 4; Gary, 1; Bridgeville, Pa., 59; New Castle, Ind., 55; Ft. Wayne, Ind., 67; Lockport, N. Y., 46.

Strip: Midland, Pa., 17; Cleveland, 2; Carnegie, Pa., 41; McKeesport, Pa., 54; Reading, Pa., 36; Washington, Pa., 38 (type 316 add 5¢); W. Leechburg, Pa., 28; Bridgeville, Pa., 59; Detroit, 47; Massillon, Canton, Ohio, 4; Middletown, Ohio, 7; Harrison, N. J., 80; Youngstown, 48; Lockport, N. Y., 46; New Britain, Conn., 58; Sharon, Pa., 13; Butler, Pa., 7.

Burs: Baltimore, 7; Duquesne, Pa., 1; Munhall, Pa., 1; Reading, Pa., 36; Tituspille

Pa., 7.

Bars: Baltimore, 7; Duquesne, Pa. 1; Munhall, Pa., 1; Reading, Pa., 36; Titusville, Pa., 59; Washington, Pa., 38; McKeesport, Pa., 1, 54; Bridgeville, Pa., 59; Dunkirk, N. Y., 28; Massillon, Ohio, 4; Chicago, 1; Syracuse, N. Y., 17; Watervilet, N. Y., 28; Waukegan, Ill., 2; Massillon, Ohio, 4; McKeesport, Pa., 54; Bridgeport, Conn., 44; Ft. Wayne, Ind., 67; Trenton, N. J., 45; Harrison, N. J., 80; Baltimore, 7; Dunkirk, 28. Structurals: Baltimore, 7; Massillon, Ohio, 4; Chicago, 1, 67; Watervilet, N. Y., 28; Bridgeport, Conn., 44.

Plates: Brackenridge, Pa., 28 (type 416 add ½¢); Butler, Pa., 7; Chicago, 1; Munhall, Pa., 1; Midland, Pa., 17; New Castle, Ind., 55; Lockport, N. Y., 46; Middletown, 7; Washington, Pa., 39; Cleveland, Massillon, 4.

Forging billets: Midland, Pa., 17; Baltimore, 7; Washington, Pa., 39; McKeesport, 54; Massillon, Canton, Ohio, 4; Watervilet, 28; Pittsburgh, Chicago, 1.

MERCHANT WIRE PRODUCTS

	Standard & Coated Nails	Woven Wire Fence 9-151/2 ga.	Fence Posts	Single Loop Bale Ties	Twisted Barbless Wire	Gal. Barbed Wire	Merch. Wire Ann'ld.	Merch. Wire
F.o.b. Mill	Gase Col.	Base Col.	Base Col.	Base Col.	Base Col.	Base Col.	¢/lb.	¢/lb
Alabama City-4. Aliquippa, Pa5 Atlanta-65. Bartonville-34	118 118 113 118	126 132 133 130	140	123 126 123	136 126 143	136 140 143 143	5.70 5.70 5.95 5.95	5.9 6.1 6.4 6.1
Buffalo-85 Chicago-4	118	126		123				* * * *
			-	111111111111111111111111111111111111111		-		
Cleveland-85 Cleveland-2 Crawfordsville-87 Donora, Pa2 Duluth-2 Fairfield, Ala11 Houston-83							5.70	5.8
Crawfordsville-87		130						
Donora, Pa2	118	130		123		140	5.70	5.8
Duluth-2. Fairfield, Ala11 Houston-83. Johnstown, Pa-3 Joliet, III2. Kokomo, Ind30 Los Angelos-62. Kansas City-83. Minnequa-14. Monessen-18. Molline, III4. Salmes-8.	118			123		136	5.70	5.8
Fairfield, Ala11	118	126		123		1001	5.70	5.9
Houston-83						1100	5.75	
Johnstown, Pa-3	118	130			140		5.70	6.1
Joliet, 1112	118	130		123	J 4	140	5.70	5.8
Kokomo, Ind30	120	128		125	138	138	605	
Los Angeles-62.				1100	2 .			
Kansas City-83.	118	130		123	.22.	140		
Minnegua-14	123	138	130	128	146	146	5.95	6.4
Monessen-18:	124	135				145	5.95	8.4
Moline, III4			112					
dillier "OO								
Pittsburg,	1			-	200	2 3		
Pittsburg, Cal24 Portsmouth-20 Rankin, Pa-2	137			147	- 158		8.85	6.8
Portsmouth-20.	124	137	F. 100		147	147	6.10	6.8
Rankin, Pa-2	118	130	25.			140	5.70	5.8
San Francisco-14 So. Chicago, III4								
So. Chicago, III4	-118	126	116	123		136	5.70	5.9
so. San						-		-
Francisco-14				147		160	6.65	7.10
Sparrows Pt3	120			125	142	132	5.80	6.2
Sterling, III33	118	130	140	123	140	140		
truthers, Ohio-6						4		
So. San Francisco-14 Sparrows Pt3 Sterling, III33 Struthers, Ohio-6 Forrance, Cal24 Worcester-2 Milliamenors	138						6.65	
Worcester-2	124					9.0	6.00	6.1
Williamsport, Pa51				4	100.00	4	-144	
Pa -81			5-	4	100	8 4	1	- 2

Cut Nalls, carloads, base, \$6.25 per 100 lb. (less 20¢ to jobbers) at Conshehocken, Pa, (25), Wareham, Mass. (53) Wheeling, W. Va., (15).

RAILS, TRACK SUPPLIES

W

Balti Birm Bash Buffs Chic Cinci Cleve Detre

Hour India Kans

Mem

Milw

Norfe Phila Pittel Portio Salt L

San F Seatt

St. Le St. P

BAS tura to 9 1999

All brac galv

F

Swede Toledo Trey,

Pi

ject diffe ton in ex to 2, phor 38e 1 0.70 entis

Dec

F.o.b. Mill Cents Per Lb.	No. 1 Std.	Light Raile	Joint Bars	Track Spikes	Axies	Screw Spikes	Tie Plates	Track Boits
Bessemer-1	2 60	4 00	4 70					
Chicago 4	00	7.00	7.10	g 15				
Chicago-4 Ensley-11 Fairfield-11	3 60	4 00		0.10				
Fairfield-11	0.00	4 00	4 40			8 80	4 50	
Gary-1 Ind. Harber-8 Johnstown-3	3 60	4 00	7.70			0.00	4 50	
Ind Harbor-R	3 60	7.00	4 70	6 16	5 25	8 60	4 50	
Inhaetowa-3	0.00	2 78	4.10	0.10	5 60	8 60	4.00	
Joliet-1	1	3 75	4.70		9.00	5.50	****	
Kansas City-83.		0.10	7.10	8 88				
Lackawanna-3.		4 00	4 70	0.00		8.60	4.50	
ebanon-3	0.00	1.00	7	6 15			1.00	9 8
Lebanen-3 Minnegua-14	3.60	4 50	4 70	6 15		8.60	4.50	9 80
Pittaburgh-77								
Mistahumah 90								0 00
Pittaburgh-5 Pittaburgh-5 Pittaburg-24				6 15				
Pittahurg-24							4 85	
Seattle-62				8 10			4.35	
Steelton-3	3.60		4.70				4.50	
Struthers-6	0.00			8 80				
Forrance-24								
				6.15			1.00	

Track Bolts, heat treated, to railroads, 9,85¢ per lb.

BOILER TUBES

Seamless steel, electric welded commercial boiler tubes, locomotive tubes, minimum wall, per 100 ft at mill, c.l. lots, cut lengths 10 to 24 ft.

OD	gage	Sear	nless	Electric	Weld
n in.	BWG	H.R.	C.D.	H.R.	C.D.
2	13	\$22.67	\$26.66	\$21.99	\$25.86
2 1/4	12	30.48	35.84	29.57	34.76
3	12	33.90	39.90	32.89	34.80
3 1/2	11	42.37	49.89	41.10	48.39
4	10	52.60	61.88	51.03	60.02

Pittsburgh Steel add, H-R; 2 in., 62¢; 2½ in., 84¢; 3 in., 92¢; 3½ in., \$1.17; 4 in., \$1.45. Add, C-R; 2 in., 74¢; 2½ in., 99¢; 3 in., \$1.37; 4 in., \$1.70.

FLUORSPAR

W	ash	ed	g	r	a	v	e	ı		f	u	10	1	8	m	a	r			f	0.	b.		cars.	
Rosi														i	Č(θ,		I)(1	1	to	n	net:	
Effective 70%	or	moi	re	Ť.																					
60%	or	less			0	0		0	0				0			0					0			38.00	

PIPE AND TUBING

CAST IRON WATER PIPE

6 to 24-in., del'd Chicago \$105.30 to \$108.80 6 to 24-in., del'd N. Y. . . . 104.50 to 105.50 6 to 24-in., Birmingham . 91.50 to 96.00 6-in. and larger, f.o.b. cars, San Francisco, Los Angeles, for all rail shipment; rail and water shipment less \$108.50 to \$113.00 Class "A" and gas pipe, \$5 extra; 4-in. pipe is \$5 a ton above 6-in.

Base discounts, f.o.b. milis. Base price about \$200 per net ton.

			4.0				UTT	WEL	D								SEAN	ILES	S	
	½ in. ¾ in.		1	ln.	11/4	In.	13/	in.	2 In.		21/2-3 In.		2	In.	21/2	-3 In.	31/2	4 in.		
STANDARD	Blk.	Gal.	Blk.	Gal.	Bik.	Gal.	Blk.	Gal.	Blk.	Gal.	Blk.	Gal.	Blk.	Gal.	Bik.	Gal.	Blk.	Gal.	Bik.	Gal.
T. & C. Bethlehem-3 Cleveland-4	36.0	14.0	37.0 39.0	18.0	41.5	21.5	42.0	22.0	42.5	23.0	43.0	23.5	43.5	24.0						
Oakland-19 Pittsburgh-5 Pittsburgh-10	25.0 36.0 36.0	3.0 14.0 14.0	28.0 39.0 39.0	7.0 17.0 18.0	30.5 41.5 41.5	10.5 19.5 21.5	31.0 42.0 42.0	21.0 20.5 22.0	31.5 42.5 42.5	22.0 21.0 23.0	32.0 43.0 43.0	12.5 21.5 23.5	32.5 43.5 43.5	13.0 22.5 24.0	29.5	8.0	32.5 32.5			
St. Louis-32 Sharon-90 Toledo-88	35.0 36.0	13.0	39.0 38.0 39.0	17.0	40.0	20.0	40.5	21.5	40.5	21.0	41.0	21.5	41.5	22.0	29.5		32.5		34.5	
Wheeling-15 Wheatland-89 Youngstown-8	36.0	14.0	39.0 38.0 39.0	17.0	39.5	19.5	40.5	20.5	40.5	21.0	41.0	21.5	42.0	22.5		11.5	32.5			14.5
EXTRA STRONG, PLAIN ENDS		6.									1									
Bethlehem-3 Cleveland-4 Oakland-19	35.5	15.0	37.5 39.5 28.5	19.0	41.5	22.5	42.0	23.0	42.5	24.0	43.0	24.5	43.5	25.0			33.0			
Pittsburgh Pittsburgh-10 St. Louis-32	35.5	15.0	39.5	19.0	41.5	22.5	42.0	23.0	42.5	24.0	43.0	24.5	43.5	25.0	29.0	7.5	33.0	14.0	36.5	17.5
Sharon-80 Toledo-88 Wheeling-15	35.5 35.5	15.0	38.5 39.5 39.5	19.0	41.5	22.5	42.0	23.0	42.5	24.0	43.0 43.0	24.5	43.5	25.0 25.0	29.0		33.0		36.5	
Wheatland-89 Youngstown-8:	34.0	13.5	38.0	17.5	38.5	19.5	39.5	20.5	39.5	21.0	40.0	21.5	41.0	22.5		10.0	33.0	14.0	36.5	17.5

Galvañized discounts basell on zinc at 17¢ per lb, Eart St. Touis. For each 1¢ change in zinc, discounts vary as follows: ½ in., ¾ in., and 1 in., % pt.; 1¼ in., 1½ in., 2 in., ¾ pt.; 2½ in., 3 in., ½ pt. Calculate discounts on even cents per lb of zinc, i.e., if zinc is 16.51° to 17.50¢ per lb, use 17¢. Jones & Laughlin discounts apply only when zinc price changes if. Threads only, buttweld and seamless. 1 pt. higher discount. Plain ends, buttweld and seamless. 3 in. and under, 3½ pts. higher discount. Buttweld inhers discount, 5 pt.

Track Boits Untreated

3

mini-8, cut Weld C.D. 25.86

48.39 60.02

62¢; 17; 4 4 in.,

cars, net: \$41.00 38.00

1/2-4 In. ik. Gal.

1.5 14.5

3.0 15.5 3.5 17.5 3.5

3.5 17.5

follows: ts per lb mges 14. 3½ pts.

1950

WAREHOUSE PRICES

Base prices, f.o.b. warehouse, dollars per 100 lb. (Metropolitan area delivery, add 20¢ to base price except Birmingham, San Francisco, Cincinnati, New Orleans, St. Paul (*), add 15¢; Philadelphia, add 25¢).

		SHEETS		ST	RIP	PLATES	SHAPES	BA	ARS	***	ALLOY BARS		
CITIES	Hot- Floiled	Cold- Rolled (15 gage)	Gaivanized (10 gage)	Hot- Rolled	Cold- Rolled		Standard Structural	Hat- Rolled	Gald- Finished	Hot- Rolled, A 4815 As-rolled	Het- Relied, A 4140 Ann.	Cold- Drawn, A 4815 As-rolled	Celd- Drawn, A 4140 Ann.
Baltimore	5.60	8.84	8.07	8.04		5.80	6.14	6.04	5.89				****
Birmingham*	5.60	8.40	8.75	5.55		5.95	5.70	5.55		****	****	****	****
Boston	6.20	7.00	7.74	8.15	*****	6.48	6.20	6.05	6.84	10.25	10.55	11.90	12.20
Buffalo	5.60	6.40	7.74	5.86	XXXX	6.05	5.80	5.60	6.40	10.15	10.45	11.80	12.10
Chicago*	5.60	6.40	7.75	5.55		5.80	5.70	5.55	6.45	10.85 9.80	10.10	11.45	11.75
Cincinnati*	5.87	6.44	7.39	5.80		6.19	6.09	5.80	6.61	10.15	10.45	11.80	12.10
Cleveland	5.60	6.40	8.10	5.69	6.90	5.92	5.82	5.57	8.40	9.91	10.21	11.56	11.86
Detroit	8.78	6.53	7.89	5.94		5.99	6.09	5.84	8.58	10.11	10.41	11.76	12.06
Houston												****	****
Indianapolis				2.4.4.6						****			
Kansas City								****			****		
Los Angeles	6.35	7.90	8.85	8.40	8.7016	6.40	6.35	8.35	7.55	11.30	11.30	13.20	13.50
Memphia													****
Milwaukee	5.74	6.54	7.89	5.69		5.94	5.84	5.89	8.44	9.94	10.24	11.59	11.89
New Orleans*													
New York	5.97-	7.841	8,442	6.59		6.58	6.40	6.42	7.29	10.45	10.75	1	
Norfolk	6.27	1											****
Philadelphia*	6.90	6.80	8.00	6.10		6.05	5.90	6.05	8.88	10,15	10.45	****	****
Pittaburah	5.00	6.40	7.75	5.65-		5.75	5.70	5.55	8.15	9.80	10.45	11.45	11.75
				5.95	****								
Portland	2.00				••••						,	****	****
Salt Lake City	7.95	****	9.70	8.70	****	8.05	8.30	8.65	9.00	****		****	
San Francisco*	8.65	8.052	8.55- 8.90 ²	6,60		6.50	6.45	8.45	8.20	11.30	11.30	13,20	13.20- 13.50
Smittle		****										×	****
St. Louis	5.85	6.65	8.00	5.80		6.13	6.03	5.80	8.55	10.05	10.35	11.70	12.00
St. Paul*													4555

BASE QUANTITIES (Standard unless otherwise keyed on prices.)
Hot-rolled sheets and strip, hot rolled bars and bar shapes, structural shapes, plate, galvanized sheets and cold-rolled sheets; 2000 to 9999 lb. Cold-finished bars; 2000 lb or over. Alloy bars; 1000 to 1999 lb.

All HR products may be combined to determine quantity bracket. All galvanized sheets may be combined to determine quantity bracket. CR sheets may not be combined with each other or with galv. sheets to determine quantity bracket.

Exceptions:

(1) 400 to 1499 lb; (2) 450 to 1499 lb; (3) 300 to 4999 lb; (4) 300 to 9999 lb; (5) 2000 to 5999 lb; (6) 1000 lb and over; (7) 500 to 1499 lb; (8) 400 lb and over; (9) 400 to 9999 lb; (10) 500 to 9999 lb; (11) 400 to 3999 lb; (12) 450 to 3749 lb; (13) 400 to 1999 lb; (14) 1500 lb and over; (15) 1000 to 9999 lb; (16) 6000 lb and over; (17) up to 1999 lb; (18) 1000 to 4999 lb; (19) 1500 to 3499 lb; (20) CR sheets may be combined for quantity; (21) 3 to 24 bundles.

PIG IRON PRICES

Dollars per gross ton. Delivered prices do not include 3 pct tax on freight.

PRODUCING POINT PRICES					DELIVERED	PRICES	(BASE G	RADES)					
Producing Point	Basic	No. 2 Foundry	Malle- able	Besse- mer	Low Phos.	Consuming Point	Producing Point	Rail Freight Rate	Basic	No. 2 Foundry	Malle- able	Besse- mer	Low. Phos
Bethleheen Birmingham Birmingham Burfalo Chicago Cleveland Daingerfield, Tex. Duluth Frentana Granite City Hubbard Iresten, Utah Pittsburgh Neville Island Gaseeve, Utah Starpeville Steeden Swedeland Telede Troy, N. Y. Yuungstown	54.00 48.38 52.00 52.00 52.00 52.00 52.00 52.00 53.00 52.00 52.00 52.00 52.00 52.00 52.00 54.00 54.00 55.00 54.00	54.50 48.88 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50 52.50	55.00 53.00 52.50 52.50 52.50 52.50 52.50 52.75 54.90 52.50 52.50 52.50 52.50 52.50	55.50 53.00 53.00 53.00 53.00 53.00 53.00 53.00 53.00 53.00 53.00 53.00 53.00	57.00	Boston Brooklyn Cincinnati Jersey City Los Angeles Los Angeles Manafield Philadelphia Philadelphia Philadelphia Philadelphia Rochester San Francisco San Francisco Seattle St. Louis Syracuse	Everett Steeiton Bethlehem Birmingham Bethlehem Genova-Irontan Fontana Cleveland, Tolede Bethlehem Swedeland Steeiton Buffalo Geneva-Irontan Fontana Granite City Buffalo	\$.0080 8.90 4.29 6.70 2.63 7.70 3.33 2.39 1.44 3.09 7.70 7.70 0.75 Arb. 3.58	55.08 59.70 56.70 55.30 56.39 57.49 54.60 59.70 54.70 58.70 59.70 51.85 55.58	52.85-53.05 58.79 55.58 57.13 60.20 57.20 55.83 66.89 7.94 57.59 66.89 67.94 57.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 60.20 67.20 6	53.55- 53.75 59.29 57.63 55.83 57.39 58.84 9.55.63 62.65 56.58	59.29 53.13 56.33 57.89 58.94 58.59	65.90

Monessen, \$54.00.

Producing points prices are subject to switching charges; silicon differential (not to exceed 50c per ton for each 0.25 pet silicon content in excess of base grade which is 1.75 to 2.25 pet for foundry iron); phosphorus differentials, a reduction of 38c per ton for phosphorus content of 0.70 pet and over; manganese differentials, a charge not to exceed 50c

per ton for each 0.50 pct manganese content in excess of 1.00 pct, 82 per ton extra may be charged for 0.5 to 0.75 pct nickel content and 81 per ton extra for each additional 0.25 pct nickel.

Silvery iron (blast furnace) silicon 6.01 to 6.50 pct C/L per g.t.. f.o.b. Jackson, Ohio—\$62.50; f.o.b. Buffalo, \$60.75. Add \$1.50 per ton for each additional 0.50 pet Si up to 17 pct.

Add 50c per ton for each 0.50 pet Mn over 1.00 pet. Add \$1.00 per ton for 0.75 pet or more P. Bessemer ferrosilicon prices are \$1.00 per ton above silvery iron prices of comparable analysis.

Charcoal pig iron base price for low phosphorus \$62.00 per gross ton, f.o.b. Lyle, Tenn. Delivered Chicago, \$70.56. High phosphorus charcoal pig iron is not being produced.

BOLTS, NUTS, RIVETS, SCREWS

		-9699	mer	L. L. S. C.		
(Base	disci	ount.	f.o.b.	mill.	Pitt	sburgh,
						hicago)

Machine and Carriage Bolts		
	Pct 0	ff Itat
	Less Case	C.
1/2 in. & smaller x 6 in. & shorter	15	28 1/2
9/16 in. & % in. x 6 in. & shorter	181/2	301/2
% in. & larger x 6 in. & shorter	17%	29 1/2
All diam. longer than 6 in Lag, all diam. x 6 in. &	14	27 1/2
shorter	23	35
Lag, all diam. longer than 6 in.	21	33

Lag, all diam. lo Plow bolts				33
Nuts, Hot Pre	ssed, C		unche	
	L	0.00	T.o.	10
½ in. & smaller	K	eg K.	Ker	z. K
	(R	eg.)	(h	vv.)
1/4 in. & smaller	. 15	2834	15	28 14
9/16 in. & % in.	. 12	25	6 36	21
% in. to 11/2 in				-
inclusive	. 9	23	1	1634
1% in. & larger	. 734	22	1	16 1/2
Nuts, Hot Pres				
14 in & smaller	96	97	99	24
½ in. & smaller 9/16 in. & % in.	1614	9914	614	91
% in. to 1 1/2 in	. 1072	20 72	0 72	
inclusive	19	25	2	173/
1% in. & larger	814	23		173
	-			11 72
Nuts, Cold Pun	ched-	-Hexag	08	
1/2 in. & smaller	. 26	37	22	34
9/16 in. & % in.	. 23	35	1736	30 1/2
% in. to 1 1/4 in	1.			
inclusive	. 191/2	31 1/2	12	25
1% in. & larger	. 12	25	6 1/2	21
Nuts, Semi-Fini	shed-	Hexag	on	
	P			1797

1% in. & larger.	12	25	6 1/2	21
Nuts, Semi-Finish	hed_	Hexag	on	
		g.	H	y.
1/2 in. & smaller.		45	281/2	39 1/2
9/16 in. & % in	29 14	40 1/2	22	34
% in. to 11/2 in.				
inclusive	24	36	15	281/4
1% in. & larger.	13	26	8 1/2	23
	Li	ght		
7/16 in. & small-				
er	35	45		
1/2 in. thru 1/8 in.	281/2	39 1/2		
% in. to 1½ in.				
inclusive	26	37		
#4 B-IA-				

			Pet Off List
Packaged,	steel, pla	ain finished	56-10
Packaged.	plated fli	nish	4110
Bulk, plair	n finish**	*******	67*
*Discour	its apply	to bulk sh	ipments in
not less th	an 15,000	pieces of	a size and
kind wher	e length	is 3-in, an	d shorter;
5000 piece	s for leng	ths longer	than 3-in.

5000 pieces for lengths longer than 3-in. For lesser quantities, packaged price applies.

**Zinc, Parkerized, cadmium or nickel plated finishes add 6¢ per lb net. For black oil finish, add 2¢ per lb net. Rivets .

Base per 100 lb

1/2 in. & larger	37.85
	Pet Off Lin
7/16 in. & smaller . F.o.b. Pittsburgh, Birmingham, Lebano	Cleveland, Chicago, on, Pa.
Cap and Set Screv	WS
(In bulk)	Pot Off List
Hexagon head cap i	
fine thread, 1/4 in.	thru % in. x 6
in., SAE 1020, brig	ht 54
% in. thru 1 in. up to	
14 in. thru 16 in. x	6 in. & shorter
high C double heat	treat 46
% in, thru 1 in, up to	& including 6 in. 41
Milled studs	
Flat head cap screw	
Fillister head cap, li	sted sizes 34
Set screws, sq head,	
diam. and smaller	

LAKE SUPERIOR ORES (51.50% Fe; natural content, delivered

lower lake ports)	
Per gross	ton
Old range, bessemer \$	
Old range, nonbessemer	
Mesabi, bessemer	
Mesabi, nonbessemer	
High phosphorus	
After adjustments for analyses, pr	
will be increased or decreased as the c	
may be for increases or decreases a	
Dec. 2, 1950, in lake vessel rates, ur	
lake rail freights, dock handling char	
and taxes thereon.	800

ELECTRODES

Cents per lb, f.o.b. plant, threaded electrodes with nipples, unboxed

Diam. in in.	Length in in.	Cents Per Ib
	GRAPHITE	
17, 18, 20	60, 72	17.00¢
8 to 16	48, 60, 72 48, 60	18.644
6	48, 60	19.954
4, 5	48, 60 40 40 24, 30	20.484
8	40	21.634
21/4	24, 30	22.05
2	24, 30	24.15¢
	CARBON	
40	100, 110 65, 110	7.654
40 35 30 24 20 17	65, 84, 110	7.654
24	72 to 104	7.654
20	84, 90	7.654
17	60, 72	7.65¢
	60, 72	8.16#
10, 12	60	8.42¢ 8.67¢

CLAD STEEL	
Base prices, cents per pound, f.o. Stainless-carbon Plate No 304, 20 pct,	b. mill Sheet
Coatesville, Pa. (21)*29.5 Washgtn, Pa. (39)*29.5 Claymont, Del. (29)*28.00	
Conshohocken, Pa. (26) New Castle, Ind. (55).*26.50 Nickel-carbon	*24.00 *25.50
10 pct. Coatesville (21) 32.5 Inconel-carbon 10 pct Coatesville (21) 40.5 Monel-carbon	
10 pct Coatesville (21) 33.5 No. 302 Stainless - copper- stainless, Carnegie, Pa.	
Aluminized steel sheets, hot dip, Butler, Pa. (7)	77.00 7.75

* Includes annealing and pickling, or sandblasting.

TOOL STEEL

		4.10.0.				Bas
W	Cr	v	Mo	F	Co	per l
18	4	1	-		-	\$1.1
18	4	1	-		5	\$1.7
18	4	2	-		-	\$1.24
1.5	4	1.5	3		-	78.5
6	4	2	6		-	84
High-	carbon	chromiu	m			63.5
		mangan				
		n				
		on				
		prices				
elegion	i ere	3¢ per	lh hi	orh	ORD T	West
		t higher		Bu	61.	AA CORE 4
Ted 15454 154	wihhi' o	t migner				

ELECTRICAL SHEETS

22 gage, HR cut lengths, f.o.b. mill

																		-	g	e	n	ta	pe		
Armature							0																		75
Electrical							×		*		*						×			×	*		4	7.	25
Motor																							-	8.	50
Dynamo .																								9.	30
Transform	er		7	2				,		0														9.	85
Transform	eı		6	5			0						0										1	0.	40
Transform	eı	0.	5	8							0	0	٠	0		0		0		0	0		1	1.	10
Transform	er		5	2																			1	1.	90
PRODU	CI	I	VI	ā		1	P	0	I	N	ľ	Г	S	-	_	E	36	26	10	1	1	E	tot	to	m.
W. Va., 1	5 :		E	31	ne.	1	el	2	81	n	r	d	g	re			F	1	L.		1	28		\mathbf{F}_{0}	ol-
lansbee, V	V.		7	78	à.			6	3	1		4	Ğ	r	à	n	1	te	9	1	C	it	y.	I	11
22°, add	70	è			1	ú	10	1	la	I	11	L		H	ĺ	u	t	H)1		Ī	In	nd.		3:
Mansfield.																									
30¢; Vand																									
Zanesville.									7				•	-		-	_	_	-		*	7			
			-		*																				

COK	E
Furnace, beehive (f.o.b. Connellsville, Pa	oven) Net Ton
Foundry, beehive (f.o.b.	oven)
Connellsville, Pa Foundry, oven coke	\$17.00 to \$17.50
Buffalo, del'd	
Chicago, f.o.b.	21.00
New England, del'd	24.30
Seaboard, N. J., f.o.b. Philadelphia, f.o.b.	22.00
Swedeland, Pa., f.o.b.	22.60
Plainesville, Ohio, f.o.	
Erie, del'd	
Cincinnati, del'd	33.71
St. Paul, f.o.b St. Louis, f.o.b	24.90
Birmingham, del'd	

C-R SPRING STEEL

			e per																	
0.26	to	0.40	carbo	on							0	0 1		9			9		5.1	15
0.41	to	0.60	carbo	n			0	0		0									6.8	0
0.61	to	0.80	carbo	on								0. 1			0				7.4	0
0.81	to	1.05	carbo	on															9.1	5
1.06	to	1.35	carbo	on							1							1	1.0	5
W	ore	ester	ad	d).	3	0	¢	:		8	šh		P	o	n,		N	61
Brit	ain	. Car	rnegie	. A	ī	91	W		Ċ	ä	ŝ	ti	0,		a	đ	đ	0	.35	
Detr	roit	. 0.20	to 0	.40	6	C	8	r	b		ı	M	Id	ı	6	0	•	: 1	oth	10
ETRO	les	add	20¢.	Ne	Y	v		3	la	Ÿ	70	n		0		Ī	£	to	0.	4
			54: 0																	-
	-	-				ľ		r.			1					1				

REFRACTORIES

Fire Cley Brick First quality, Ill., I (except Salina, P	(F.o.b. works) Carloads, Per 1000 (y., Md., Mo., Ohio, Pa. (a., add \$5) \$94.60
No. 1 Ohio	d., Ky., Mo., Ill. 8,00 79,20
Ground fire clay, no	

Silice Brick

Mt. Union, Pa., Ensley, Ala \$94.6
Childs, Pa
Hays, Pa
Chicago District104.5
Western Utah and Calif
Super Duty, Hays, Pa., Athens,
Tex., Chicago
Silica cement, net ton, bulk, East-
ern (except Hays, Pa.) 16.5
Silica cement, net ton, bulk, Hays,
Pa 18.7
Silica cement, net ton, bulk, Ensley,
Ala 17.6
Silica cement, net ton, bulk, Chi-
cago District 17.80
Silica cement, net ton, bulk, Utah
and Calif 24.71

Chrome Brick Per Net Ton Standard chemically bonded, Balt., Chester\$77.00

Magnesite Brick

Standard, Baltimore \$99.00 Chemically bonded, Baltimore 88.00
Grain Magnesite St. %-in. grains
Domestic, f.o.b. Baltimore, in bulk fines removed\$62.70
Domestic, f.o.b. Chewelah, Wash., in bulk 36.30
in sacks 41.80

Pead Burned Dolomite

F.o.b. producing points in Pennsylvania, West Virginia and Ohio, per net ton, bulk Midwest, add 10¢; Missouri Valley, add 20¢....\$18.8

METAL POWDERS


MEIAL POWDERS
Per pound, f.o.b. shipping point, in to- lots, for minus 100 mesh.
Swedish sponge iron c.i.f. New York, ocean bags 7.4¢ to 9.86 Canadian sponge iron, del'd.
in East
Fe, carload lots 9.0¢ to 15.0¢ Electrolytic iron, annealed.
99.5+% Fe 36.0¢ to 39.5¢ Electrolytic from unannealed,
minus 325 mesh, 99+% Fe Hydrogen reduced iron, mi-
nus 300 mesh, 98+% Fe 63.0¢ to 80.86 Carbonyl iron, size 5 to 10
micron, 98%, 99.8+% Fe 70.0¢ to \$1.35 Aluminum
Copper, electrolytic 10.25¢ plus metal value Copper, reduced10.00¢ plus metal value
Chromium electrolytic 98%
min., and quantity \$3.W
Lead
Molybdenum, 99% \$2.00
Nickel, unannealed 75.16 Nickel, annealed 81.16
Nickel spherical unappealed 78.8
Silicon 24.0W
Solder powder 6.5¢ to 8.5¢ plus met. value Stainless steel. 302
Stainless steel, 302 75.00 Tin 11.00¢ plus metal valor
Tungsten, 99%
Tungsten, 99%

B

Dece

No Excess Weight

when you use ELDMENTS



When you use Bethlehem Weldments in the manufacture of machines, pressure vessels, and other types of equipment, you'll find that excess weight is reduced to the minimum.

Bethlehem Weldments make possible decided savings in weight because they are made from rolled-steel plates, structural shapes and other sections of the exact thicknesses required. They are accurately flame-cut to customer specifications, and are then welded either into simple parts or intricate assemblies.

Bethlehem Weldments offer wide freedom in design, and can be produced in virtually any size. They can also be used in combination with steel castings or forgings. What's more, our modern shop facilities include bending, forming, flame-cutting and stress-relieving equipment.

If you'd like to learn more about the use of Bethlehem Weldments, call the nearest Bethlehem sales office, or write to us at Bethlehem, Pa.

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

Fabricated Steel Construction

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation **Export Distributor: Bethlehem Steel Export Corporation**

This stirrup-former assembly, built almost entirely with Bethlehem Weldments, weighs 18,350 lb. It is approximately 52 in. high, 101 in. long, and 86 in. wide.



BETHLEHEM WELDMENTS

December 14, 1950

161

18.70 17.60 17.60 24.75 t Ton \$77.00 899.00 raise \$62.70 \$13.00 im ton to 9.0 10.00 0 15.0 o 39.54 48.54 0 80.N

13.76

94.60 99.00 00.10 04.50 11.10

11.10 16.50

29.00 29.00 33.26 1 value 1 value 1 value

\$3.50 value 52.004 \$2.65 75.54 81.54 78.64 value 75.044 1 value \$3.48 23.854

don't scrap metal by turning!





The Torrington Rotary Swaging Machine uses every bit of stock. With 4000 hammer blows a minute, swaging reduces, sizes, rounds, tapers and points rod, wire and tubing. It makes metal tougher and more resilient. It hammers away minor surface defects.

Torrington Swagers are built to a mechanical perfection based on our 42 years' swaging experience. Send today for your free copy of the illustrated booklet describing the machine and the method.

THE TORRINGTON COMPANY Swager Department 555 Field Street . Torrington, Conn.



Send the coupon today for your free capy of this booklet.

Please send a copy of "The Torrington Swaging Machine" to:

51 Address

FOUNDED 1855 MARKETS & PRICES

Ferrochrome

Contract prices, cants per pound, contained Cr. lump size, bulk, in carloads, delivered. (65-72% Cr. 2% max. Sl.)
0.06% C. 30.25 0.20% C. 29.25
0.10% C. 29.75 0.50% C. 29.00
0.15% C. 29.50 1.00% C. 28.75
2.00% C. 29.50 1.00% C. 28.50
05-69% Cr. 4-9% C. 5-9% Sl. 22.60

High-Nitrogen Ferrochrome

Low-carbon type: 67-72% Cr. 0.75% N. Add 5¢ per ib to regular low carbon ferrochrome price schedule. Add 5¢ for each additional 0.35% N.

S. M. Ferrochrome

S. M. Ferrochreme

Contract price, cents per pound, chromium contained, lump size, delivered.

High carbon type: 60-65% Cr, 4-6% Si, 4-6% Mn, 4-6% C.
Carloads 21.60

Ton lots 22.75

Less ton lots 25.25

Low carbon type: 62-66% Cr, 4-6% Si, 4-6% Mn, 1.25% max. C.
Carloads 27.76

Ton lots 30.05

Less ton lots 31.85

Chromium Metal

Contract prices, per lb chromium contained packed, delivered, ton lots. 97% min. Cr. 1% max. Fe. 0.20% Max. C. \$1.09 0.50% max. C. 1.05 .60 min. C 1.04

Low Carbon Ferrochrome Silicon

(Cr 34-41%, Si 42-49%, C 0.05% max.) Contract price, carloads, f.o.b. Niagara Falls, freight allowed; lump 4-in. x down-bulk 2-in. x down, 21.75¢ per lb of con-tained Cr plus 12.00¢ per lb of contained St. Bulk 1-in. x down, 21.90¢ per lb con-tained Cr plus 12.20¢ per lb contained St.

Contract price per lb of alloy, dump.
delivered.
30-33% Ca, 60-65% Sl, 3.00% max. Fe
Carloads 19.00
Ton lots 22.10
Less ton lots 23.60

Calcium-Manganese—Silicon

CMSZ

Contract price, cents per pound of alloy, delivered.

Alloy 4: 45-49% Cr, 4-6% Mn, 18-21% Sl, 1.25-1.75% Zr, 3.00-4.5% C.

Alloy 5: 50.56% Cr, 4-6% Mn, 13.50-8.00% Sl, 0.75 to 1.25% Zr, 3.50-5.00% Cron lots 20.75

Less ton lots 22.00

Graphidox No. 4

SMZ

(Prices continued on p. 164)

TO INSURE PROMPT DELIVERIES ...



"STANDARD"

RECOMMENDS

STANDARDS

You can depend on prompt deliveries of UNBRAKO Products when you use standard sizes. For, despite shortages, stepped-up demand and other problems of the emergency, we've been able to keep full stocks of UNBRAKO "standards" on our dealers' shelves -ready for immediate delivery. And that's not all . . . Every time you use a standard size UNBRAKO it represents a substantial saving over the cost of a "special." Be sure you have our latest catalog of UNBRAKO standard products. Send for your copy of Bulletin 643-R today.



Knurled Head Socket Cap Screws Flat Head Socket Cap Screws Self-Locking Socket Set Screws

Knurled Head Stripper Bolts Precision-Ground Dowel Pins Fully-Formed Pressure Plugs

STANDARD PRESSED STEEL CO.

JENKINTOWN 10, PA.

Dec



18 Solder Joints-1¢

THIS EXAMPLE is typical of users' reports on hundreds of jobs using Allis-Chalmers Induction Heaters. In case after case, production proved faster and cheaper with Allis-Chalmers Induction Heaters.

or,

he

to

ry

ze

b

of

ve

(0)

our

CO

1950

Best of all, these units are highly versatile! The same heater can braze, solder, anneal, case and through harden by simply changing the work coil. Work coils are easy to install. When coils are changed, there's no need for additional output transformers (needed on most units) which require special shielding and skilled help to install.

Cost per part processed is amazingly low on high production items as shown in the example above. But even where production is fairly low,

cost is surprisingly low because the cost per hour to own and operate an Allis-Chalmers Induction Heater is probably less than you realized. This low cost plus versatility makes the unit a welcome addition in many job shops.

COST PER HOUR

to own and operate an Allis-Chalmers Induction Heater:

	0 kw	20 kw unit
Tube replacement (5,000 hrs)	0.070	0.110
Fixed energy	.020	.034
Load energy 50 % cycle	.140	.200
Water	.010	.032
Amertization 20,000 hrs	.244	.354
Total cost \$	0.484	\$0.730

Call your nearby Allis-Chalmers Sales Office and find out what Induction Heat — the A-C way — can do to your production costs.

Send Coupon Now!

Please send	me Induc	tion Heate	r booklet	6430A
Name				
Title				
	-			
Company				

ALLIS-CHALMERS

December 14, 1950



FOUNDED 1855 MARKETS & PRICES

FERROALLOYS

FERROALLOYS
Ferromanganese 78-82% Mn. maximum contract base price, gross ton, lump size. F.o.b. Birmingham
Spiegeleisen Contract prices gross ton, lump, f.o.b. 16-19% Mn 19-21% M1 3% max. Si Palmerton, Pa. \$69.00 \$70.00 \$71.00
Manganese Metal Contract basis, 2 in. x down, cents per pound of metal, delivered. 96% min. Mn. 0.2% max. C, 1% max Sl, 2% max. Fe. Carload, packed
Ton lots 31.26 Electrolytic Manganese F.o.b. Knoxville, Tenn., freight allowed east of Mississippi, cents per pound. Carloads 25 Ton lots 30 Lens ton lots 32
Medium Carbon Ferromanganese Mn 80% to 85%, C 1.25 to 1.50. Contract price, carloads, lump, bulk, delivered, per lb. of contained Mn
Low-Carbon Ferromanganese Contract price, cents per pound Mn contained, lump size, del'd., Mn. 85-80%.
0.07% max. C, 0.06% P, 90% Mn 26.25 28.10 29.30 0.07% max. C 25.75 27.60 28.80 0.15% max. C 25.25 27.10 28.30 0.30% max. C 24.75 26.60 27.80 0.50% max. C 24.25 26.10 27.30 0.50% max. C 24.25 26.10 27.30 0.75% max. C 24.25 23.10 24.30
Silicomanganese Contract basis, lump size, cents per pound of metal, delivered, 65-68% Mn. 18-20% SI, 1.5% max. C. For 2% max. C. deduct 0.2¢. 9.60 Carload bulk 9.60 Ton lots 11.25 Briquet, contract basis carlots, bulk delivered, per ib of briquet 10.86 Ton lots 11.45
Silvery iron (electric furnace) Si 14.01 to 14.50 pct, f.o.b. Keokuk. Iowa, or Wenatchee, Wash., \$36,50 grosston, freight allowed to normal trade area Si 15.01 to 15.50 pct, f.o.b. Niagara Falla. N. Y., \$80.00. Add \$1.00 per ton for each additional 0.50% Si up to and including 18%. Add \$1.00 for each 0.50% Mn over 1%.
Silicos Metal Contract price, cents per pound contained Si, lump size, delivered, for ton lots packed. 96% Si, 2% Fe
Silicon Briquets Contract price, cents per pound of briquet bulk, delivered, 40% Si, 1 lb Si briquets. Carload, bulk 6.75 Ton lots 8.35
Electric Ferrosilicon Contract price, cents per pound contained Si, lump, bulk, carloads, delivered 25% Si 19.00 75% Si 14.30 50% Si 12.00 85% Si 15.55 90-95% Si 17.50


Calcium Metal

Eastern zone contract prices, cents per pound of metal, delivered.

Cast Turnings Distilled
Ton lots \$2.05 \$2.95 \$3.75

Less ton lots . . 2.40 3.30 4.55

(Prices Continued on Page 166)



Shown here is the Pangborn Hydro-Finish unit which set new records at Fred Heinzelman & Sons. A pioneer of heat treated dies, the company reports: Hydro-Finish removes heat treat oxide discoloration, cuts hand polishing 60% to 70%, holds tolerances to a precision .0001"!

Find out how HYDRO-FINISH can save you money

Hydro-Finish is the answer to modern cleaning, decorating and finishing problems. As Fred Heinzelman & Sons have found, Hydro-Finish virtually eliminates tedious and expensive hand buffing and polishing on tool and die maintenance. Now, dies with heavy oxide discolorations can be cleaned faster and at lower cost.

And, on the production line, Hydro-Finish assures better bonding, electro-plating, painting—gives you the surface you want within .0001" with no pits, grooves or hard-to-clean imperfections left after cleaning.

For full information on the many ways Hydro-Finish can save you money, write today for Bulletin 1400-A to: PANGBORN CORPORATION, 1500 Pangborn Blvd, Hagerstown, Md.



De




...and Baled Sheet Metal Scrap Helps Keep Steel Production at a High Level

If you are not baling your sheet metal scrap, perhaps you should be...not only for the immediate benefit to your own operation... but in the interest of a strong industrial economy. More and more steel is needed for its continued strength and growth.

If you question the advisability of baling your sheet metal scrap, competent counsel is available without cost or obligation. Galland-Henning engineers offer you the benefit of many years' experience in all types of scrap metal baling . . . and in the design, construction and installation of powerful, efficient baling equipment which assures lowest possible cost-per-ton.

GALLAND-HENNING MFG. CO.



GALLAND-HENNING SCRAP METAL BALING PRESSES

A 5840-1P

December 14, 1950

ey

finman virpentool with

ydro-

ctro-

sur-

th no

you letin POllvd.,

1950



FOUR WAYS TO BEAT SHORTAGES IN METAL FINISHES

You can easily avoid problems due to scarcities of some materials by taking advantage of other time-tested techniques. For example:



In decorative chromium...

The plate is normally preceded by a deposit of copper and nickel to assure corrosion resistance. If you are short on nickel, use more copper. You'll still provide necessary rust-proofing. Many manufacturers use the Unichrome Pyrophosphate Copper Process because it provides a high quality plate and ties up fewer copper anodes.

Thinner deposits?

Thinner plate will be found suitable on many products not subjected to considerable handling, if the plated surface is reinforced by a clear lacquer or baked-on finish. Unichrome Clear Product Finishes protect chromium, copper, brass, nickel, silver.

Use zinc more

It's more plentiful than other metals and it's inexpensive. When processed in Unichrome Dip, zinc provides a sparkling finish that looks like chromium, resists corrosion. Such a finish not only costs less, but actually provides better rust-resistance.

Avoiding needless waste

Using Unichrome Coating 218X to insulate plating racks cuts waste. It lasts longer in all baths, thus reducing wasteful depositing of metal on the rack. It rinses freely, thereby minimizing loss of valuable plating salts by "drag out."

Write us for more details.

UNITED CHROMIUM, INCORPORATED

100 East 42nd St., New York 17, N. Y. Detroit 20, Mich • Waterbury 20, Conn. Chicago 4, iii. • Los Angeles 13, Calif. In Canada: United Chromium Limited, Toronto, Ont. FOUNDED 1855 MARKETS & PRICES

Other Ferroalloys

Alaifer, 20% Al, 40% Si, 40% Fe, contract basis, f.o.b. Suspension Bridge, N. Y.
Bridge, N. Y. Carload
Ton lots 9.55¢ Calcium molybdate, 45-40%, f.o.b. Langeloth, Pa, per pound contained Mo. \$1.15
Langeloth, Pa., per pound contained Mo
contract basis, delivered, per pound contained Cb. Ton lots
Ferro-Tantalum-columbium. 20%
D. per lb of contained Ch plus Ta. \$3.75
Ferromolybdenum, 55-75%, f.o.b. Langeloth, Pa., per pound con-
tained Mo \$1.32 Ferrophosphorus, electrolytic, 23- 26%, car lots, f.o.b. Siglo, Mt. Pleasant, Tenn., \$3 unitage, per gross ton \$65.00
10.1
Ferrotitanium, 40%, regular grade.
Falls, N. Y., and Bridgeville, Pa.,
Ferrotitanium, 25%, low carbon, 0.10% C max., f.o.b. Niagara Falis, N. Y., and Bridgeville, Pa., freight allowed, ton lots, per lb contained Til.
frails, N. Y., and Bridgeville, Pa., freight allowed, ton lots, per lb contained Ti
Less ton lots #1 66
Ferrotitanium, 15 to 19%, high car- bon, f.o.b. Niagara Falls, N. Y., freight allowed, carload per net ton
ton
Ferrovanadium, 35-55%, contract basis, delivered, per pound, contained V. Openhoarth 33.00-33.05
basis, delivered, per pound, contained V. Openhearth\$3.00-\$3.05
High ground steel (Drimon) 9.95
Molybdic oxide, briquets or cans, per ib contained Mo, f.o.b. Langeloth, Pa. \$1.14 bags, f.o.b. Washington, Pa.
bags, f.o.b. Washington, Pa., Langeloth, Pa
Al, contract basis, f.o.b. Philo, Ohio, freight allowed, per pound
Ton lots, bulk lump 11.50¢
Vanadium pentoxide, 88-92%
Zirconium, 35-40%, contract basis,
pound of alloy.
Zirconium, 12-15%, contract basis, lump, delivered, per lb of alloy. Carload, bulk 7.00¢

Boron Agents

Contract prices per ib of alloy, de Borosil, f.o.b. Philo, Ohio, freight	
Borosil, f.o.b. Philo. Ohio, freight	
allowed, B 3-4%, Si 40-45%, per	
th contained B	84 95
lb contained B	*1.50
Ton lots, per pound	454
Less ton lots, per pound	504
Combandam Mil 15 01st D 1 0st Cl	804
Carbortam, Ti 15-21%, B 1-2%, Si	
2-4%, Ai 1-2%, C 4.5-7.5% f.o.b. Suspension Bridge, N. Y., freight	
Suspension Bridge, N. Y., freight	
allowed.	
Ton lots, per pound 1	0.004
Ferroboron, 17.50% min. B, 1.50%	max.
Si, 0.50% max. Al, 0.50% max. C,	1 In.
x D. Ton lots	\$1.20
F.o.b. Wash., Pa.; 100 lb, up	-
10 to 14% B	.78
14 to 19% B	1.20
14 to 19% B. 19% min. B.	1.50
Grainal, f.o.b. Bridgeville, Pa.,	
freight allowed, 100 lb and over.	
No. 1	
	68¢
No. 79	50€
Manganese-Boron 75.00% Mn, 11	-20%
Manganese—Boron 75.00% Mn, 18 B, 5% max. Fe, 1.50% max. St,	3.00%
max. C, 2 in. x D, delivered.	
Ton lots	\$1.46
Less ton lots	1.57
Nickel-Boron 15-18% B, 1.00% max	E. AL
Nickel—Boron 15-18% B, 1.00% max 1.50% max. Si, 0.50% max. C,	1.00%
max. Fe, balance Ni, delivered.	
Less ton lots	\$1.80
Silcaz, contract basis, delivered.	
Ton lots	5.00e

Tempilstiks

the amazing Crayons that tell temperatures

A simple method of controlling temperatures in:

•	W	22		м	a
•		-	~	4	v

. FLAME-CUTTING vailable . TEMPERING

. FORGING . CASTING

. MOLDING . DRAWING

. STRAIGHTENING . HEAT-TREATING

It's this simple: Select the Tempilstik® for the working temperature you want. Mark your workpiece with it. When the Tempilstik* mark melts, the specified temperature has been reached.

IN GENERAL



Also

and

in pellet

to 2000 readings

Available in these temperatures (°F)

113	263	400	950	1500
125	275	450	1000	1550
138	288	500	1050	1600
150	300	550	1100	1650
163	313	600	1150	1700
175	325	650	1200	1750
200	338	700	1250	1800
213	350	750	1300	1850
225	363	800	1350	1900
238	375	850	1400	1950
250	388	900	1450	2000

FREE -Templi" "Basic Guide to Ferrous Metallurgy" -161/4" by 21" plastic-laminated wall chart in color. Send for sample pellets, stating temperature of interest to you.

GORDON "SERVICE

CLAUD S. GORDON CO.

Specialists for 36 Years in the Heat Treating and Temperature Control Field

Dept. 16 · 3000 South Welluce St., Chicago 16, ill. Dept. 16 · 2035 Hamilton Ave., Cleveland 14, Ohio

Dec

SAVE MONEY

ON PRESSED STEEL PARTS!

If you want to save money on pressed steel parts, call on Budd's wide experience in steel

parts, call on Budd's wide experience in steel stampings of all kinds.

Like hundreds of manufacturers, you can take advantage of Budd "know-how" to lower production costs on blanks and stampings, in both regular grade and stainless steel. At your service Budd places the best-equipped machine shop—for both large and small dies—on the Atlantic seaboard.

Write today, sending a sample, blue-print or pencil sketch of your product, and let us quote you a price.

THE BUDD COMPANY Specialty Dept. 16, Philadelphia 32, Pa.





HOT DIP GALVANIZING

JOS. P. CATTIE & BROS., INC.

Gaul & Letterly Sts., Philadelphia 25, Pa.

GALYANIZED PRODUCTS FURNISHED

PICKLING & OILING



GRAY TURRET HEAD METAL CUTTER OR NIBBLER

GRAY, Originator of First Practical Metal Cutter or Nibbler. Received N.A.M. Pioneer Award.

Most modern Nibbler for Template Cutting, Tool Rooms, Shipbuilding, Aircraft Parts, Aircraft Tubing, Sheet and Plate Shops.

GRAY MACHINE CO., Box 596, PHILADELPHIA, PA.



(° F)

0

0

ide

y"

ets,

14, Ohio

1950

SILVERY

A Blast Furnace Product made from Only Virgin Ores

JACKSON IRON & STEEL CO. - JACKSON, OHIO



- ACCURACY OF THREADS
 LOW CHASER COST
 ALL AROUND DEPENDABILITY
 Bulletins available: General Purpose
 Die Heads, Insert Chaser Die Head,
 Threading Machine.



THE EASTERN MACHINE SCREW CORP. 21-41 Barclay St., New Haven. Conn. Pacific Coast Representative: A. C. Behringer, 334 N. San Pedro St. Los Angeles, Calif. CANADA: F. F. Barber Machinery Company. Toronto.

FORGINGS

THE CANTON DROP FORGING & MFG. CO. CANTON, OHIO

TO SUIT **YOUR NEEDS**

STANDARD - BEVEL - SOUARE - SPECIAL GALVANIZED OR CADMIUM PLATED ALSO MANHOLE STEPS

NICETOWN PLATE WASHER CO., Inc.

JUNIATA AND CLARISSA STS.

NICETOWN

PHILADELPHIA 40, PA.



1669 W. LAFAYETTE BLVD., DETROIT 16, MICH.

Builders of SPECIAL PURPOSE MACHINERY

DIXIE-COWDREY

. Machine Corporation A subsidiary of Dixie Cup Co.

Designers and Custom Builders for over 75 years Write: Dixie-Cowdrey, Fitchburg, Mass., Phone: 5200

> COPPER—BRASS—BRONZE PERFORATED TO YOUR REQUIREMENTS SEND US YOUR DRAWINGS FOR PRICE PERFORATED METALS

FOR ALL INDUSTRIAL USES ALL SIZE AND SHAPE HOLES—ALL METALS ARCHITECTURAL GRILLES

DIAMOND MFG. CO.

BOX 28, Write for Catalog 85 WYOMING, PA.

CONSIDER GOOD USED EQUIPMENT FIRST

AIR COMFRESSOR

1374 cu. ft. Sullivan Class WN-114 Double Acting 14½"x8¾"x7" Air Compressor, Complete with 250 H.P. G.E. Syn. Motor 440/3/60 & Accessories

BENDING ROLL

14' Niles Pyramid Type Plate Bending Roll.

Top Roll 181/2", Bottom Rolls 14" Diameter. 25 H.P. Westinghouse 440/3/60

Main Drive Motor. 71/2 H.P. Westinghouse Elevating Motor

FURNACES-MELTING

500 lb. Moore Size "T" Melting Furnace, With 200 KVA G.E. Transformer 13,200 volt primary, 229 to 85 volt secondary. 3 phase, 60 cycle

HAMMERS-STEAM DROP

35,000 lb. Chambersburg Steam Drop Hammer. Bore of Cylinder 40" Diameter. Distance Between Vees 54". Built 1941

8000 lb. Chambersburg Steam Drop Hammer. 20 to 1 Steel Anvil (two piece) Safety Cap Cylinder

MANIPULATOR

8000 lb. Alliance Floor Type Straight Line Forging Manipulator

PRESS-HYDRAULIC FORGING

1000 ton United Steam Hydraulic Forging Press Complete with Accumulator, Intensifier, Tools—NEW 1942

PRESS-TRIMMING

No. 58 Bliss-Consolidated, With Side Trimming Arm. Approx. Stroke 8", Top of Bolster 54" x 32", Motor Driven, Elecl. Equipment Included

SAW-HACK

14" x 14" Peerless Hack Saw, Hydraulic Feed—NEW 1942

SHEAR-BAR

Mesta No. 8 Vertical Cold Bar Shear, Maximum Capacity 6" O.D. Carbon or Alloy Steel. Complete with Elecl. Equipment. NEW—Never Used.

STRAIGHTENER

No. 6 KANE & ROACH SHAPE STRAIGHTENER, Belt Drive. Capacity 5x5x%" Angles, 2¾" Rounds & Square, 6x1" Flats, etc.

TESTING MACHINE

120,000 lb. SOUTHWARK TATE-EMERY Universal Hydraulic Testing Machine— NEW 1946

RITTERBUSH & COMPANY INC.

50 Church Street, New York 8, N. Y.
Phone—Cort 7-3437

The Clearing House

NEWS OF USED, REBUILT AND SURPLUS MACHINERY

Copper Scrap-The shortage of copper magnet wire used in rebuilding electrical machinery is becoming so acute that at least one distributor has contacted rebuilding shops about a special plan for obtaining wire. He will collect scrap from these shops, and credit them with the amount received. When 30,000 lb has been accumulated from various shops, it will be sent to a smelter, refined and formed into wire bars or wire rod on a toll basis. This would then be sent to a wire maker, who would fabricate magnet wire from it, also on a toll basis. This wire would then be distributed to the shops according to the proportion of the original scrap they had contributed.

However, this is expensive, troublesome, and there is a considerable time delay between collection of the scrap and delivery of the wire, the NISA is warning its members.

Chicago Market—The used machinery market in the Chicago area experienced a slight dropping-off in demand during the first part of November. It is believed that uncertainty about election results caused some postponement of buying until elections were over. Starting in the middle of the month, inquiries for all types of equipment picked up and the industry is again undergoing a high demand period. Prices, during this minor lull, remained firm and high.

Letting of government contracts necessitating the use of heavy equipment has caused large press brakes and squaring shears to become almost nonexistent in this area. They are selling at prices within 20 to 30 pct of the cost of new machines, when they can be found. Automatic screw machines, vertical milling machines, and turret lathes—in fact, all types of late-model production equipment, are scarce. And the scarcity will grow as the defense program ex-

pands. Dealers are hard put to replace stocks, and a lot of dealer-to-dealer trading is going on.

Price Rise Due-Chicago trade sources expect used machinery prices to go still higher in the next few months when more contracts for heavy defense equipment are let by the government. A good part of the machinery sold in the area during the last few months has been going to the East, Southwest and West Coast, for use in the aircraft program. This demand is not expected to slacken. But now this demand is being reinforced by the contracts let in the Midwest for tanks, weapons carriers and aircraft motors. Prime contractors have these orders. Subcontractors will soon have a better idea of their requirements under these programs and will come into the local market more heavily. And there are more defense orders yet to come.

NISA Directors—The board of directors of the National Industrial Service Assn. met in Chicago last month. An enlarged committee to supervise the association's contacts with Washington was named. This Defense Coordination Committee is composed of F. W. Willey, chairman, W. W. Hanks, W. S. Giles, R. E. Ward, and W. J. Wheeler. The directors also authorized award of certificates of recognition to individuals with records of 50 years or more of service to the electrical industry.

Southeastern Chapter Elects—
The following officers were unanimously selected to guide the Southeastern Chapter of the NISA at a recent meeting in Greenville, S. C.: H. H. Grey, Southern Electric Service Co., president; O. A. Clot, Peninsular Armature Works, vice-president; and W. S. Ward, Electric Motor & Repair Co., secretary-treasurer.